

CLASS B PATCHES (SPECIAL) (VARIABLE DEPTH 15"-20")							
LOCATION	TYPE II	TYPE III	TYPE IV	SAW CUTS	DOWEL BARS	PAV'T. FABRIC	TIE BARS
	CU. YD.	CU. YD.	CU. YD.	FOOT	EACH	SQ. YD.	EACH
NORTH BOUND LANES							
MAIN ST. TO HAMILTON AVE.	48	26	52	1239	324	167	96
SOUTH BOUND LANES							
HARRISON T. TO LIBERTY ST.	76	32	57	1731	504	178	72
LIBERTY ST. TO FULTON ST.	124	64	74	2763	810	274	120
FULTON ST. TO MAIN ST.	24	13	29	620	162	84	
TOTAL	619			6353	1800	703	288

CLASS B PATCHES, 10"							
LOCATION	TYPE II	TYPE III	TYPE IV	SAW CUTS	DOWEL BARS	PAV'T. FABRIC	TIE BARS
	SQ. YD.	SQ. YD.	SQ. YD.	FOOT	EACH	SQ. YD.	EACH
NORTH BOUND LANES							
FULTON ST. TO MAIN ST.	249	67	183	2612	756	250	228
MAIN ST. TO HAMILTON ST.	269	41	-	1977	665	41	
SOUTH BOUND LANES							
HARRISON ST. TO LIBERTY ST.	181	51	92	1752	522	143	76
FULTON ST. TO MAIN ST.	156	39	129	1619	450	168	70
TOTAL	855	198	404	7960	2393	602	374

CLASS B PATCHES, 20"							
LOCATION	TYPE II	TYPE III	TYPE IV	SAW CUTS	DOWEL BARS	PAV'T. FABRIC	TIE BARS
	SQ. YD.	SQ. YD.	SQ. YD.	FOOT	EACH	SQ. YD.	EACH
SOUTH BOUND LANES							
LIBERTY ST. TO FULTON ST.	208	69	73	1881	558	142	62
TOTAL	208	69	73	1881	558	142	62

FILE NAME = sht-plan.dgn
 USER NAME = longer
 PLOT SCALE = 103.4029' / IN.
 PLOT DATE = 2/25/2009

DESIGNED - ---
 DRAWN - ---
 CHECKED - ---
 DATE - ---
 REVISED - ---
 REVISED - ---
 REVISED - ---
 REVISED - ---

STATE OF ILLINOIS
 DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES
 SCALE: NOT TO SCALE SHEET NO. 1 OF 1 SHEETS STA. _____ TO STA. _____

F.A.P. 64	SECTION (BCS)I	COUNTY PEORIA	TOTAL SHEETS 7	SHEET NO. 7
CONTRACT NO. 68066			ILLINOIS FED. AID PROJECT	