

STA. TO STA.	RT/LT	LENGTH	WIDTH	AREA		HOT-MIX ASPHALT SURF REM (2 1/4")	HOT-MIX ASPHALT SURF REM (1 1/2")	POLYMERIZED LEVEL BINDER (MM) IL-4.75, N50 (3/4")	POLYMERIZED HOT-MIX ASPHALT SURF CSE MIX "E" N70 (1 1/2")	HMA SHOULDERS (1 1/2")	*POLY BIT MAT (PR CT)	*AGG (PR CT)	AGG SHLD TYPE B (RT / LT)	INCIDENTAL HMA SURFACING (1 1/2")
				(SQ.FT)	(SQ.YD)	(SQ.YD)	(SQ.YD)	TON	TON	TON	TON	TON	TON	TON
WAR MEMORIAL EASTBOUND														
Mainline														
218+97	TO	297+20		7,823	24	187,752.00	20,861.33		20,328.00		876.18	1,752.35		10.85 62.58
Shoulders														
218+97	TO	222+56	RT	359	8	2,872.00	319.11		319.11		26.81	0.17	0.96	10.22
225+13	TO	240+55	RT	1,542	8	12,336.00	1,370.67		1,370.67		115.14	0.71	4.11	43.90
230+53	TO	240+55	LT	1,002	4	4,008.00	445.33		445.33		37.41	0.23	1.34	28.53
240+55	TO	241+00	RT	45	6	270.00	30.00		30.00		2.52	0.02	0.09	1.28
241+00	TO	245+21	RT	421	4	1,684.00	187.11		187.11		15.72	0.10	0.56	11.99
247+80	TO	271+64	RT	2,384	10	23,840.00	2,648.89		2,648.89		222.51	1.38	7.95	67.88
253+26	TO	258+70	LT	544	4	2,176.00	241.78		241.78		20.31	0.13	0.73	15.49
260+33	TO	267+50	LT	717	4	2,868.00	318.67		318.67		26.77	0.17	0.96	20.41
274+00	TO	291+24	RT	1,724	10	17,240.00	1,915.56		1,915.56		160.91	1.00	5.75	49.09
278+05	TO	289+43	LT	1,138	4	4,552.00	505.78		505.78		42.49	0.26	1.52	32.40
WAR MEMORIAL WESTBOUND														
Mainline														
218+97	TO	299+22		8,025	24	192,600.00	21,400.00		21,400.00		898.80	1,797.60		11.13 64.20
Shoulders														
218+97	TO	224+10	RT	513	8	4,104.00	456.00		456.00		38.30	0.24	1.37	14.61
230+49	TO	240+55	LT	1,006	4	4,024.00	447.11		447.11		37.56	0.23	1.34	28.64
229+62	TO	245+00	RT	1,538	8	12,304.00	1,367.11		1,367.11		114.84	0.71	4.10	43.79
250+00	TO	250+30	RT	30	4	120.00	13.33		13.33		1.12	0.01	0.04	0.85
250+30	TO	252+40	RT	210	7	1,470.00	163.33		163.33		13.72	0.08	0.49	5.98
253+26	TO	259+63	LT	637	4	2,548.00	283.11		283.11		23.78	0.15	0.85	18.14
252+40	TO	259+73	RT	733	10	7,330.00	814.44		814.44		68.41	0.42	2.44	20.87
260+33	TO	267+53	LT	720	4	2,880.00	320.00		320.00		26.88	0.17	0.96	20.50
260+22	TO	272+00	RT	1,178	10	11,780.00	1,308.89		1,308.89		109.95	0.68	3.93	33.54
274+47	TO	292+00	RT	1,753	10	17,530.00	1,947.78		1,947.78		163.61	1.01	5.84	49.91
278+05	TO	289+43	LT	1,138	4	4,552.00	505.78		505.78		42.49	0.26	1.52	32.40
BRANDYWINE DR														
Mainline														
9+05	TO	9+65		60	87	5,220.00	580.00		580.00		0.30	1.74		48.72
10+43	TO	10+88		45	75	3,375.00	375.00		375.00		0.20	1.13		31.50
War Memorial @ Brandywine: Right Turn Lanes														
218+97	TO	224+20	To Brandywine South	523	12	6,276.00	697.33	697.33		29.29	58.58		0.36	2.09
224+25	TO	227+25	To Brandywine North	300	12	3,600.00	400.00	400.00		16.80	33.60		0.21	1.20
227+25	TO	228+50		125	0 - 12	750.00	83.33	83.33		3.50	7.00		0.04	0.25
War Memorial @ Brandywine :Left Turn Lanes														
219+80	TO	220+85	To Brandywine South	105	0 - 14	735.00	81.67	81.67		3.43	6.86		0.04	0.25
220+85	TO	225+20		435	14	6,090.00	676.67	365.56		28.42	56.84		0.35	2.03
224+25	TO	227+30	To Brandywine North	305	14	4,270.00	474.44	474.44		19.93	39.85		0.25	1.42
227+30	TO	230+30		300	0 - 14	2,100.00	233.33	233.33		9.80	19.60		0.12	0.70
UNIVERSITY														
Mainline														
8+70	TO	9+62		92	150	13,800.00	1,533.33	1,533.33		64.40	128.80		0.80	4.60
10+40	TO	11+64		124	137	16,988.00	1,887.56	1,887.56		79.28	158.55		0.98	5.66
War Memorial @ University: Right Turn Lanes														
240+16	TO	242+26	To University South	210	0 - 16	1,680.00	186.67	186.67		7.84	15.68		0.10	0.56
242+26	TO	246+00		374	16	5,984.00	664.89	664.89		27.93	55.85		0.35	1.99
247+65	TO	251+03	To University North	338	12	4,056.00	450.67	450.67		18.93	37.86		0.23	1.35
251+03	TO	253+16		213	0 - 12	1,278.00	142.00	142.00		5.96	11.93		0.07	0.43
War Memorial @ University :Left Turn Lanes														
239+65	TO	242+68	To University North	303	0 - 24	3,636.00	404.00	404.00		16.97	33.94		0.21	1.21
242+68	TO	246+43		375	24	9,000.00	1,000.00	1,000.00		42.00	84.00		0.52	3.00
246+38	TO	251+27	To University South	489	24	11,736.00	1,304.00	1,304.00		54.77	109.54		0.68	3.91
251+27	TO	254+30		303	0 - 24	3,636.00	404.00	404.00		16.97	33.94		0.21	1.21
WESTWOOD														
Mainline														
249+90	TO	250+15	RT	25	40	1,000.00	111.11		111.11		0.06	0.33		9.33
259+70	TO	260+35	RT	65	30	1,950.00	216.67		216.67		0.11	0.65		18.20
270+12	TO	270+55	RT	43	25	1,075.00	119.44		119.44		0.06	0.36		10.03
War Memorial @ Westwood :Left Turn Lane														
257+00	TO	258+50	To Westwood from War-Memorial East Bound	150	0 - 12	450.00	50.00	50.00		2.10	4.20		0.03	0.15
258+50	TO	260+52		202	12	2,424.00	269.33	269.33		11.31	22.62		0.14	0.81

* 2 APPLICATIONS