

GENERAL NOTES (CONTINUED)

PAVEMENT STATION NUMBERS & PLACEMENT

THE CONTRACTOR SHALL PROVIDE LABOR AND MATERIALS REQUIRED TO IMPRINT PAVEMENT STATION NUMBERS IN THE FINISHED SURFACE OF THE PAVEMENT AND/OR OVERLAY. THE NUMBERS SHALL BE APPROXIMATELY 3/4 INCH (20mm) WIDE, 5 INCHES (125mm) HIGH AND 5/8 INCH (15mm) DEEP.

THE PAVEMENT STATION NUMBERS SHALL BE INSTALLED AS SPECIFIED HEREIN:

INTERVAL – 200 FEET (ENGLISH STATIONING) OR 100 METERS (METRIC STATIONING)

BOTTOM OF NUMBERS – 6 INCHES (150mm) FROM THE INSIDE EDGE OF THE PAVEMENT MARKING

LOCATION:

- * 2, 3 & 5 LANE PAVEMENTS – RIGHT EDGE OF PAVEMENT IN DIRECTION OF INCREASING STATIONS
- * MULTI-LANE DIVIDED ROADWAYS – OUTSIDE EDGE OF PAVEMENT IN BOTH DIRECTIONS
- * RAMPS – ALONG BASELINE EDGE OF PAVEMENT

POSITION – STATIONS SHALL BE PLACE SO THEY CAN BE READ FROM THE ADJACENT SHOULDER

FORMAT – ENGLISH (METRIC) PAVEMENT STATIONS SHALL USE THIS FORMAT "XXX (XX+X00)" WHERE X REPRESENTS THE PAVEMENT STATION

THIS WORK WILL NOT BE PAID FOR SEPARATELY, BUT WILL BE CONSIDERED INCLUDED IN THE COST OF ASSOCIATED PAVEMENT AND/OR OVERLAY PAY ITEMS.

TRAFFIC BARRIER TERMINAL TYPE 1, SPECIAL (TANGENT)

WHEN GUARDRAIL IS INSTALLED IN LINE WITH THE EDGE OF PAVEMENT OR SHOULDER, THE TERMINAL SHALL BE TAPERED AT A RATE OF 50:1 TO PROVIDE CLEARANCE FOR THE EXTRUDER TERMINAL.

GENERAL NOTES (CONTINUED)

HOT-MIX ASPHALT MIXTURE REQUIREMENTS

Mixture Use(s):	Hot-Mix Asphalt Surface Course & Incidental HMA Surfacing	Hot-Mix Asphalt Binder Course & Patches
AC/PG:	PG 64-22	PG 64-22
RAP%(MAX)**:	15.0%	25.0%
Design Air Voids:	4.0%@N = 50	4.0%@N = 50
Mixture Composition: (Gradation Mixture)	IL 9.5 OR IL 12.5	IL 19.0
Friction Aggregate	Mixture D (Dolomite only)	N. A.

** If 15 % > RAP is used, the contractor may be required to use a softer grade of asphalt as determined by the Materials Engineer.

JOB SPECIFIC NOTES

FILE NAME = 88406 sheets.dgn	USER NAME = kslmonkk	DESIGNED - DRAWN -	REVISED - REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	COMMITMENTS, GENERAL NOTES, AND JOB SPECIFIC NOTES	F.A.P. RTE. 685/618	SECTION 361RS-11C-2)	COUNTY MCDONOUGH	TOTAL SHEETS 52	SHEET NO. 3
PLOT SCALE = 100.0000 * / IN.	CHECKED -	REVISED -	SHEET NO. 2 OF 2 SHEETS			CONTRACT NO. 68406				
PLOT DATE = 4/22/2009	DATE -	REVISED -	ILLINOIS FED. AID PROJECT							