



Sta. LT & RT  
 Sta. 677+08 TO 725+49.44  
 Sta. 732+07.7 TO 759+07.88

OMISSION  
 Sta. 682+84 to 690+16.5

**LEGEND**

1. EXISTING PCC PAVEMENT 9-6-9
2. EXISTING HOT-MIX ASPHALT OVERLAY 3 1/2"
3. EXISTING 9" HOT-MIX ASPHALT BASE COURSE WIDENING
4. EXISTING AGGREGATE SHOULDERS
5. PROPOSED HOT-MIX ASPHALT BINDER COURSE 2 1/4"
6. PROPOSED AGGREGATE SHOULDERS TY B
7. PROPOSED HOT-MIX ASPHALT SURFACE COURSE - 1 1/2"
8. PROPOSED HOT-MIX ASPHALT SURFACE REMOVAL 3/4"
9. PROPOSED STRIP REFLECTIVE CRACK CONTROL TREATMENT, SYSTEM A
10. PROPOSED EPOXY PAVEMENT MARKING LINE 4"

FILE NAME = 68406 sheets.dgn	USER NAME = k1mknkk	DESIGNED -	REVISED -	<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>	<b>TYPICAL SECTIONS</b>			F.A.P. RTE. = 685/618	SECTION = 36(RS-1)C-2)	COUNTY = MCDONOUGH	TOTAL SHEETS = 52	SHEET NO. = 12
	PLOT SCALE = 100.0000' / IN.	DRAWN -	REVISED -					CONTRACT NO. 68406				
	PLOT DATE = 4/22/2009	CHECKED -	REVISED -		ILLINOIS FED. AID PROJECT							

NOT TO SCALE | SHEET NO. 3 OF 5 SHEETS | FOR STA. TO STA. SEE ABOVE