

TABULATION OF RESURFACING QUANTITIES

Location	Length	Width	Area	HMA Surface Removal Butt Joint	Aggregate (Prime Coat) 2 Appls.	Bituminous Materials (Prime Coat) 2 Appls.	HMA Surface Course, Mix "D", N50	HMA Binder Course, IL-19.0, N50	Temporary Ramp	Incidental HMA Surfacing	HMA Surface Removal, 3/4"
	FT	FT	SQ YD	SQ YD	TON	TON	TON	TON	SQ YD	TON	SQ YD
Sta. 622+00 to 622+30	30.0	26.0	86.7	86.7	0.35	0.04	7.3		14.5		
Sta. 622+30 to 622+75	45.0	26.0	130.0	57.8	0.52	0.07	10.9	11.9	8.7		72.2
Sta. 622+75 to 667+15	4,440.0	26.0	12,826.7		51.31	6.67	1,077.4	1,616.2			12,826.7
Sta. 667+15 to 676+62	947.0	28.0	2,946.3		11.79	1.53	247.5	371.2			2,946.3
Sta. 676+62 to 682+09	547.0	26.0	1,580.3		6.32	0.82	132.8	199.1			1,580.3
Sta. 682+09 to 682+54	45.0	26.0	130.0	57.8	0.52	0.07	10.9	11.9	8.7		72.2
Sta. 682+54 to 682+84	30.0	26.0	86.7	86.7	0.35	0.04	7.3		14.5		
Sta. 682+84 to 690+16.5	OMIT										
Sta. 690+16.5 to 690+46.5	30.0	26.0	86.7	86.7	0.35	0.04	7.3		14.5		
Sta. 690+46.5 to 690+91.5	45.0	26.0	130.0	57.8	0.52	0.07	10.9	11.9	8.7		72.2
Sta. 690+91.5 to 779+70	8,878.5	26.0	25,649.0		102.60	13.34	2,154.5	3,231.8			25,649.0
Sta. 779+70 to 780+15	45.0	26.0	130.0	57.8	0.52	0.07	10.9	11.9	8.7		72.2
Sta. 780+15 to 780+45	30.0	26.0	86.7	86.7	0.35	0.04	7.3		14.5		
Sideroads, Drives, & Mailbox Turnouts		3.0	622.0	111.4	* 1.24	* 0.25				83.0	
TOTAL				690.0	177.0	23.0	3685.0	5,466.0	93.0	83.0	43,291.0

RATES:

HOT-MIX ASPHALT SURFACE COURSE = 112 LB/SQ YD IN
 BIT. MAT'LS (PRIME COAT) MILLED SURFACE = 0.1 GAL/SQ YD
 BIT. MAT'LS (PRIME COAT) BINDER SURFACE = 0.03 GAL/SQ YD
 AGGREGATE (PRIME COAT) = 4.0 LB/SQ YD

* 1 APPLICATION

STRIP REFLECTIVE CRACK CONTROL TREATMENT, SYSTEM A

** Sta. 622+00 to 780+45	30,225.0 FOOT
--------------------------	---------------

AGGREGATE SHOULDERS, TYPE B

** Sta. 622+00 to 780+45	1,148.0 TON
--------------------------	-------------

CONSTRUCTION TEST STRIP

** Sta. 622+00 to 780+45	1.0 EACH
--------------------------	----------

** PAVING OMISSION - Sta. 682+84 to 690+16.5

FILE NAME = 68406 sheet.dgn	USER NAME = kilmerk	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	TABULATION OF RESURFACING QUANTITIES	F.A.P. RTE. = 685/618	SECTION = 36(RS-1C-2)	COUNTY = MCDONOUGH	TOTAL SHEETS = 52	SHEET NO. = 15
		DRAWN -	REVISED -							
		CHECKED -	REVISED -							
		DATE -	REVISED -							
					SHEET NO. 1 OF 1 SHEETS					CONTRACT NO. 68406