

SHORT-TERM PAVEMENT MARKING	
* Sta. 622+00 to 780+45	6,045.0 FEET

TEMPORARY PAINT PAVEMENT MARKING LINE 4"	
* Sta. 622+00 to 780+45	38,081.0 FEET

WORK ZONE PAVEMENT MARKING REMOVAL	
* Sta. 622+00 to 780+45	499.0 SQ FT

EPOXY PAVEMENT MARKING - LINE 4"					
STATION	YELLOW LINE 4"		WHITE - LINE 4"	TOTALS	
	SKIP DASH (FT)	NO PASSING (FT)			EDGE LINE (FT)
		LT	RT		
Rt & Lt 622+00 to 623+60		160.0	160.0	320.0	
Rt & Lt 623+60 to 631+40	195.0			1,560.0	
Rt & Lt 631+40 to 641+40	250.0		1,000.0	2,000.0	
Rt & Lt 641+40 to 647+70		630.0	630.0	1,260.0	
Rt & Lt 647+70 to 655+40	192.5	770.0		1,540.0	
Rt & Lt 655+40 to 682+84	686.0			5,488.0	
Rt & Lt 682+84 to 690+16.5	OMIT				
Rt & Lt 690+16.5 to 722+75	814.6			6,517.0	
Rt & Lt 722+75 to 727+20	111.25		445.0	890.0	
Rt & Lt 727+20 to 729+00	45.0			360.0	
Rt & Lt 729+00 to 738+00	225.0	900.0		1,800.0	
Rt & Lt 738+00 to 780+45	1,061.25			8,490.0	
Side road Subtraction (5 @ avg. 84.0' = 420.0')				- 420.0	
TOTALS	3,580.6	2,460.0	2,235.0	29,805.0	
TOTAL (YELLOW)				8,276.0 FT	
TOTAL (WHITE)				29,805.0 FT	
GRAND TOTAL				38,081.0 FT	

RAISED REFLECTIVE PAVEMENT MARKERS	
STATION	TWO WAY AMBER MARKER (EA)
* 622+00 to 780+45	205 EACH
TOTALS	205 EACH

RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	
STATION	(EA)
* 622+00 to 780+45	131 EACH
TOTALS	131 EACH

** PAVING OMISSION - Sta. 682+84 to 690+16.5

FILE NAME = 68406 sheets.dgn	USER NAME = kjlmenkk	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SCHEDULES OF QUANTITIES	F.A.P. RTE. = 685/618	SECTION = 36IRS-11C-21	COUNTY = MCDONOUGH	TOTAL SHEETS = 52	SHEET NO. = 17	
		DRAWN -	REVISED -			SHEET NO. 2 OF 4 SHEETS					
		CHECKED -	REVISED -			CONTRACT NO. 68406					
		DATE = 4/22/2009	REVISED -			ILLINOIS FED. AID PROJECT					