

### SUMMARY OF QUANTITIES

CODE NO.	PAY ITEM	UNIT	TOTAL QUANTITY	1000 100% FED	
40200800	AGGREGATE SURFACE COURSE, TYPE B	TON	30	30	
40600215	POLYMERIZED BITUMINOUS MATERIALS (PRIME COAT)	TON	26	26	
40600300	AGGREGATE (PRIME COAT)	TON	148	148	
40600895	CONSTRUCTING TEST STRIP	EACH	1	1	
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	238	238	
40600990	TEMPORARY RAMP	SQ YD	119	119	
40603335	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N50	TON	4,120	4,120	
40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	33	33	
44000157	HOT-MIX ASPHALT SURFACE REMOVAL, 2"	SQ YD	49,215	49,215	
44201789	CLASS D PATCHES, TYPE II, 12 INCH	SQ YD	806	806	
44201794	CLASS D PATCHES, TYPE III, 12 INCH	SQ YD	360	360	
44300200	STRIP REFLECTIVE CRACK CONTROL TREATMENT	FOOT	35,949	35,949	
48101200	AGGREGATE SHOULDERS, TYPE B	TON	467	467	
48203100	HOT-MIX ASPHALT SHOULDERS	TON	68	68	
X 63000003	STEEL PLATE BEAM GUARD RAIL, TYPE A, 9 FOOT POSTS	FOOT	375	375	
X 63100167	TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) TANGENT	EACH	2	2	
63200310	GUARDRAIL REMOVAL	FOOT	422	422	
67000500	ENGINEER'S FIELD OFFICE, TYPE B	CAL MO	4	4	
67100100	MOBILIZATION	L SUM	1	1	
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1	1	

X SPECIALTY ITEM