

TEMPORARY PAINT PAVEMENT MARKING SCHEDULE

LOCATION	LINE 4"						LINE 8"	LINE 12"	LETTERS & SYMBOLS
	SOLID - WHITE		SOLID - YELLOW		SKIP DASH - YELLOW				
	NB	SB	NB	SB	NB	SB			
	FT.	FT.	FT.	FT.	FT.	FT.			
STA. 143+19.60 TO STA. 146+00.00	280	280			70				
STA. 146+00.00 TO STA. 153+65.00	765	765	765			191			
STA. 153+65.00 TO STA. 165+10.00	1,145	1,145	1,145	1,145					
STA. 165+10.00 TO STA. 172+34.60 (BK)	725	725		725	181				
STA. 164+14.70 (AH) TO STA. 168+33.76	419	419		419	105				
STA. 168+33.76 TO STA. 205+54.00 (BK)	3,720	3,720			930				
STA. 0+00.00 (AH) TO STA. 11+96.18	1,196	1,196			299				
STA. 11+96.18 TO STA. 24+82.52	1,286	1,286	1,286			322			
STA. 24+82.52 TO STA. 29+40.58	458	458	458	458					
STA. 29+40.58 TO STA. 40+52.48	1,112	1,112		1,112	278				
STA. 40+52.48 TO STA. 46+97.00	645	645			161				
STA. 47+89.00 TO STA. 59+81.85	1,193	1,193	1,193			298			
STA. 59+81.85 TO STA. 66+90.00	708	708	708	708					
STA. 82+25.00 TO STA. 83+45.00	120	120	241	240			17		
STA. 83+45.00 TO STA. 83+89.56	45	45		89					
STA. 83+89.56 TO STA. 84+89.56	100			200		100		18	
STA. 84+89.56 TO STA. 85+62.00	72								
STA. 85+62.00 TO STA. 86+00.00	38		86	76			16		
STA. 86+00.00 TO STA. 86+35.43	35		71	71					
STA. 86+35.43 TO STA. 86+57.80 (BK)	22	22	45	45		22	16	9	
STA. 88+92.87 (AH) TO STA. 89+70.60	78	78	155	155		78	31	9	
STA. 89+70.60 TO STA. 91+31.00	160	160	321	321			63		
STA. 91+31.00 TO STA. 93+35.46	204	204	409	410			23		
STA. 93+35.46 TO STA. 106+25.30	1,290	1,290	1,290	1,290					
STA. 106+25.30 TO STA. 111+53.30	528	528	528	528					
SUB-TOTAL	16,346	16,100	8,701	7,991	2,835	200	165	35	
TOTAL			51,973				200	165	35

FILE NAME = PHASE II PLANS.dgn	USER NAME = johnsonv	DESIGNED -	REVISED -
		DRAWN -	REVISED -
		CHECKED -	REVISED -
		DATE -	REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

SCHEDULES OF QUANTITIES

SHEET NO. 4 OF 5 SHEETS

F.A.S. RTE. 1380	SECTION 2RS-4, 3RS-3, 7RS-4	COUNTY PEORIA	TOTAL SHEETS 23	SHEET NO. 12
CONTRACT NO. 68612				
ILLINOIS FED. AID PROJECT				