

SHORT-TERM PAVEMENT MARKING				
LOCATION	LENGTH	NO. OF APPLICATIONS	TOTAL LENGTH	
	FT.		FT.	
STA. 143+19.60 TO STA. 172+34.60 (BK)	292	4	1,166	
STA. 164+14.70 (AH) TO STA. 205+54.00 (BK)	414	4	1,656	
STA. 0+00.00 (AH) TO STA. 46+97.00	470	4	1,879	
STA. 47+89.00 TO STA. 66+90.00	190	4	760	
STA. 82+25.00 TO STA. 83+89.56	16	4	66	
STA. 83+89.56 TO STA. 84+89.56	20	4	80	
STA. 84+89.56 TO STA. 86+35.43	15	4	58	
STA. 86+35.43 TO STA. 86+57.80 (BK)	4	4	18	
STA. 88+92.87 (AH) TO STA. 89+70.60	16	4	62	
STA. 89+70.60 TO STA. 111+53.30	218	4	873	
		4		
SUB-TOTAL	1,655	4	6,618	
TOTAL		6,618		

WORK ZONE PAVEMENT MARKING REMOVAL		
LOCATION	LENGTH	AREA
	FT.	SQ FT.
TEMPORARY PAVEMENT MARKING		
LINE 4"	51,973	17,324
LINE 8"	200	133
LINE 12"	165	165
LETTERS & SYMBOLS		35
SUB-TOTAL	17,658	
TOTAL	17,658	

RAISED REFLECTIVE PAVEMENT MARKER					
LOCATION	TWO-WAY 80' CENTERS	TWO-WAY 40' CENTERS	ONE-WAY 40' CENTERS	ONE-WAY 40' CENTERS	ONE-WAY 20' CENTERS
	AMBER	AMBER	AMBER	CRYSTAL	CRYSTAL
	EACH	EACH	EACH	EACH	EACH
STA. 143+19.60 TO STA. 146+00	5				
STA. 146+00 TO STA. 153+65.00		20		40	
STA. 153+65.00 TO STA. 165+10.00		30		60	
STA. 165+10.00 TO STA. 172+34.60 (BK)	10				
STA. 164+14.70 (AH) TO STA. 168+33.76	6				
STA. 168+33.76 TO STA. 205+54.00 (BK)	48				
STA. 0+00.00 (AH) TO STA. 11+96.18	16				
STA. 11+96.18 TO STA. 24+82.52	17				
STA. 24+82.52 TO STA. 29+40.58		12			
STA. 29+40.58 TO STA. 40+52.48	15				
STA. 40+52.48 TO STA. 46+97.00	9				
STA. 47+89.00 TO STA. 59+81.85	16				
STA. 59+81.85 TO STA. 66+90.00		19			
STA. 82+25.00 TO STA. 83+45.00			6		
STA. 83+45.00 TO STA. 83+89.56		2			
STA. 83+89.56 TO STA. 84+89.56		6			6
STA. 84+89.56 TO STA. 85+62.00					
STA. 85+62.00 TO STA. 86+00.00			2		
STA. 86+00.00 TO STA. 86+35.43			2		
STA. 86+35.43 TO STA. 86+57.80 (BK)			2		2
STA. 88+92.87 (AH) TO STA. 89+70.60			4		4
STA. 89+70.60 TO STA. 91+31.00			8		
STA. 91+31.00 TO STA. 93+35.46			10		
STA. 93+35.46 TO STA. 106+25.30	17				
STA. 106+25.30 TO STA. 111+53.30	8				
SUB-TOTAL	167	89	34	100	12
TOTAL	256	34	112		

WORK ZONE PAVEMENT MARKING REMOVAL		
LOCATION	LENGTH	AREA
	FT.	SQ FT.
SHORT-TERM PAVEMENT MARKING (4")	1,655	552
SUB-TOTAL	552	
TOTAL	552	

RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	
LOCATION	EACH
JOBSITE	342
TOTAL	342