

SUMMARY OF QUANTITIES				CONSTRUCTION CODE			
CODE NO.	ITEM	UNIT	TOTAL QUANTITY	HSIP	NHF		NHF
				ROADWAY 1000-2A 90% FED. 10% ST.	HWY LIGHTING Y030-1E 80% FED. 20% ST.	MOWING 1000-2A 100% STATE	ROADWAY 1000-2A 80% FED. 20% ST.
28000400	PERIMETER EROSION BARRIER	FOOT	898	898			
28000500	INLET AND PIPE PROTECTION	EACH	14	14			
28100825	STONE DUMPED RIPRAP, CLASS B3	TON	389	389			
28200200	FILTER FABRIC	SQ YD	917	917			
31100100	SUB-BASE GRANULAR MATERIAL, TYPE A	TON	4,921				4,921
31101900	SUB-BASE GRANULAR MATERIAL, TYPE C	TON	703				703
35501450	HOT-MIX ASPHALT BASE COURSE	TON	1,117	1,117			
35600900	HOT-MIX ASPHALT BASE COURSE WIDENING	TON	63	63			
40200100	AGGREGATE SURFACE COURSE, TYPE A	TON	58	58			
40600215	POLYMERIZED BITUMINOUS MATERIALS (PRIME COAT)	TON	4	4			
40600300	AGGREGATE (PRIME COAT)	TON	23	23			
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	313	313			
40600990	TEMPORARY RAMP	SQ YD	64	64			
40603235	POLYMERIZED HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N70	TON	282	282			
40603540	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	742	742			
40701946	HOT-MIX ASPHALT PAVEMENT (FULL-DEPTH), 13 1/4"	SQ YD	2,304	2,304			
42300200	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 6 INCH	SQ YD	143	143			
44000100	PAVEMENT REMOVAL	SQ YD	3,516				3,516
44000157	HOT-MIX ASPHALT SURFACE REMOVAL, 2"	SQ YD	578	578			
44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	249	249			
44000920	BITUMINOUS CONCRETE SHOULDER REMOVAL	SQ YD	572	572			
44002805	ISLAND REMOVAL	SQ FT	77	77			
44300200	STRIP REFLECTIVE CRACK CONTROL TREATMENT	FOOT	1,577	1,577			

FILE NAME =
shv01.dgn

USER NAME = johnsonv
PLOT SCALE = 100.0000' / IN.
PLOT DATE = 3/19/2009

DESIGNED -	REVISED -
DRAWN -	REVISED -
CHECKED -	REVISED -
DATE -	REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

SUMMARY OF QUANTITIES
SHEET NO. 2 OF 5 SHEETS

F.A.P. RTE. 313/534	SECTION 6R-1; (109EX) R	COUNTY HENDERSON	TOTAL SHEETS 81	SHEET NO. 6
CONTRACT NO. 68818				
ILLINOIS FED. AID PROJECT				