

TRAFFIC CONTROL & PROTECTION			
LOCATION	STD. 701201	STD. 701306	STD. 701326
	L SUM	L SUM	L SUM
JOBSITE	1	1	1
TOTAL	1	1	1

LUMINAIRE, SODIUM VAPOR, VERTICAL MOUNT, 250 W	
LOCATION (STA/OFFSET)	EACH
SE QUADRANT OF INTERSECTION	
LT. STA. 763+36 (64') - US 34	2
TOTAL	2

FURNISHING AND ERECTING RIGHT-OF-WAY MARKERS	
LOCATION (STA/OFFSET)	UNIT
IL 94/116	
LT. STA. 5+85.00 (85')	1
LT. STA. 7+75.00 (85')	1
RT. STA. 7+77.82 (45')	1
LT. STA. 9+00.00 (33')	1
RT. STA. 10+00.00 (45')	1
RT. STA. 10+10.00 (33')	1
US 34	
LT. STA. 753+80.00 (70')	1
LT. STA. 754+00.00 (75')	1
LT. STA. 760+75.25 (75')	1
TOTAL	9

CHANGEABLE MESSAGE SIGN		
LOCATION	NO. SIGNS	CAL MO
JOBSITE		
IL 94/116	1	5
US 34	2	5
TOTAL	15	

ELECTRIC SERVICE INSTALLATION (SPECIAL)	
LOCATION (STA/OFFSET)	EACH
SE QUADRANT OF INTERSECTION	
LT. STA. 763+36 (64') - US 34	1
TOTAL	1

STRIP REFLECTIVE CRACK CONTROL TREATMENT	
LOCATION	FT
US 34	
LT. STA. 754+26.33 TO STA. 770+03.10	1,576.77
TOTAL	1,577

ROCK FILL	
LOCATION	TON
IL 94/116	
STA. 3+75.00 TO STA. 4+75.00	201
US 34	
STA. 764+50.00 TO STA. 766+00.00	403
TOTAL	604

REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	
LOCATION	CU YD
IL 94/116	
STA. 3+75.00 TO STA. 4+75.00	131
US 34	
STA. 764+50.00 TO STA. 766+00.00	262
TOTAL	393

TRAFFIC CONTROL SURVEILLANCE	
LOCATION	CAL DA
JOBSITE	20
TOTAL	20

POROUS GRANULAR EMBANKMENT	
LOCATION	TON
IL 94/116	
STA. 3+75.00 TO STA. 4+75.00	67
US 34	
STA. 764+50.00 TO STA. 766+00.00	135
TOTAL	202

GEOTECHNICAL FABRIC FOR GROUND STABILIZATION	
LOCATION	SQ YD
IL 94/116	
STA. 3+75.00 TO STA. 4+75.00	196
US 34	
STA. 764+50.00 TO STA. 766+00.00	393
TOTAL	589

CONCRETE MEDIAN, TYPE SM-4.24	
LOCATION	SQ FT
INTERSECTION US 34 & IL 94/116	250.47
TOTAL	250

FILE NAME = sh01.dgn	USER NAME = johnsonv	DESIGNED -	REVISED -
		DRAWN -	REVISED -
		CHECKED -	REVISED -
		DATE -	REVISED -

**STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION**

SCHEDULES OF QUANTITIES

SHEET NO. 2 OF 10 SHEETS

F.A.P. RTE. 313/534	SECTION 6R-1j (109EX) R	COUNTY HENDERSON	TOTAL SHEETS 81	SHEET NO. 17
CONTRACT NO. 68818			ILLINOIS FED. AID PROJECT	