

| SCHEDULE OF CULVERT QUANTITIES                   |                                     |   |   |   |                  |                 |                          |                    |                 |
|--|-------------------------------------|---|---|---|------------------|-----------------|--------------------------|--------------------|-----------------|
| LOCATION   | PRECAST CONC. BOX CULVERTS, 2' X 2' | PRECAST CONC. BOX CULVERT END SECTIONS, 2' X 2' | PRECAST CONC. BOX CULVERT END SECTIONS, 3' X 3' | PIPE CULVERTS, TY 2, CS OR AL CULVERT PIPE, 18" | END SECTIONS 18" | CONCRETE COLLAR | EXPANSION BOLTS 3/4 INCH | REINFORCEMENT BARS | TRENCH BACKFILL |
|  | FT                                  | EACH  | EACH  | FT  | EACH             | CU YD           | EACH                     | LB                 |                 |
| <b>US 34</b>                                     |                                     |   |   |   |                  |                 |                          |                    |                 |
| 74.4' LT. STA. 762+20.82                         |                                     |   | 1   |   |                  | 0.36            | 8                        | 26                 |                 |
| 30' RT. STA. 765+43.63 TO 30' RT. STA. 765+79.63 |                                     |   |   | 36  | 2                |                 |                          |                    | 3               |
| 54' LT. STA. 763+89.20 TO 59' RT. STA. 763+89.20 |                                     |   |   |   |                  |                 |                          |                    |                 |
| <b>IL 94/116</b>                                 |                                     |   |   |   |                  |                 |                          |                    |                 |
| 36.3' LT. STA. 7+44.75 TO 23.4' STA. 7+57.36     | 18                                  | 1   |   |   |                  | 0.27            | 8                        | 20                 | 16              |
| <b>TOTAL</b>                                     | <b>18</b>                           | <b>1</b>  | <b>1</b>  | <b>36</b>                                       | <b>2</b>         | <b>0.63</b>     | <b>16</b>                | <b>46</b>          | <b>19</b>       |

| RIPRAP SCHEDULE                      |                               |               |
|--------------------------------------|-------------------------------|---------------|
| LOCATION                             | STONE DUMPED RIPRAP, CLASS B3 | FILTER FABRIC |
|                                      | TON                           | SQ YD         |
| <b>US 34</b>                         |                               |               |
| LT. STA. 761+50.00 TO STA. 762+15.82 | 87.25                         | 203.75        |
| LT. STA. 762+15.82 TO STA. 762+25.82 | 6.38                          | 17.21         |
| LT. STA. 762+25.82 TO STA. 763+00.00 | 98.33                         | 229.63        |
| LT. STA. 767+50.00 TO STA. 768+10.90 | 80.73                         | 188.52        |
| LT. STA. 768+10.90 TO STA. 768+20.90 | 6.38                          | 17.21         |
| LT. STA. 768+20.90 TO STA. 769+00.00 | 104.85                        | 244.86        |
| <b>IL 94 / IL 116</b>                |                               |               |
| LT. STA. 7+53 (At Box Culvert)       | 5.56                          | 15.56         |
| <b>SUB-TOTAL</b>                     | <b>389.48</b>                 | <b>916.74</b> |
| <b>TOTAL</b>                         | <b>389</b>                    | <b>917</b>    |

| TEMPORARY DITCH CHECKS         |           |                     |
|--------------------------------|-----------|---------------------|
| LOCATION                       | EACH      | No. of Applications |
| <b>US 34</b>                   |           |                     |
| LT. STA. 754+00 TO STA. 763+50 | 39        | 2                   |
| LT. STA. 765+50 TO STA. 770+00 | 18        | 2                   |
| <b>IL 94 / IL 116</b>          |           |                     |
| LT. STA. 3+50 TO STA. 10+30    | 13        | 2                   |
| RT. STA. 3+50 TO STA. 10+30    | 17        | 2                   |
| <b>SUB-TOTAL</b>               | <b>87</b> | <b>2</b>            |
| <b>TOTAL</b>                   |           | <b>174</b>          |

| FILLING EXISTING CULVERTS                        |          |                      |             |
|--|----------|----------------------|-------------|
| LOCATION   | EACH     | FOR INFORMATION ONLY |             |
|  |          | LENTH                | SIZE/TYPE   |
| 54' LT. STA. 763+89.20 TO 59' RT. STA. 763+89.20 | 1        | 113                  | 2' x 2' BOX |
| <b>TOTAL</b>                                     | <b>1</b> |                      |             |

| INLET AND PIPE PROTECTION |          |                     |
|---------------------------|----------|---------------------|
| LOCATION                  | EACH     | No. of Applications |
| <b>US 34</b>              |          |                     |
| LT. STA. 754+21.00        | 1        | 2                   |
| LT. STA. 762+20.82        | 1        | 2                   |
| RT. STA. 765+36.62        | 2        | 2                   |
| LT. STA. 768+14.62        | 1        | 2                   |
| <b>IL 94/116</b>          |          |                     |
| LT. STA. 7+53.00          | 1        | 2                   |
| RT. STA. 8+10.00          | 1        | 2                   |
| <b>SUB-TOTAL</b>          | <b>7</b> | <b>2</b>            |
| <b>TOTAL</b>              |          | <b>14</b>           |