

COMMITTMENTS

ROUTE	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
I-155	90-[(106X)HB]P	TAZEWELL	5	2

No commitments have been made for this project.

GENERAL NOTES

Cleaning & painting of the existing steel shall be as specified in the special provision for "Cleaning and Painting Existing Steel Structures". All beams, bearings, and all other structural steel shall be cleaned per Near White Blast Cleaning – SSPC SP 10 according to the following schedule.

Bridge 1 & 2 – Entire Structure, except the previously metalized beam ends

The designated paint system shall be Paint System 5 – MCU.
The final finish coat for the interior and exterior shall be according to the following schedule:

Bridge No. 1 & 2 – Paint system 5 shall be used and all exterior fascias including the bottom of the bottom flanges shall be blue (Munsell No. 10B 3/6). All of the underside shall be painted Gray (Munsell No. 5B 7/1).

SSPC QP1 & QP2 PAINTING CONTRACTOR CERTIFICATIONS ARE NOT REQUIRED FOR THIS CONTRACT

AIR MONITORS – None for this project

**COMMITMENTS &
GENERAL NOTES**