

SUMMARY OF QUANTITIES				URBAN 90% FEDERAL 10% STATE	
CODE NUMBER	PAY ITEM	UNIT	QUANTITY	ROADWAY 1000	STRUCTURES X271-2A
20200100	EARTH EXCAVATION	CU YD	89	89	
20400800	FURNISHED EXCAVATION	CU YD	140	140	
20700220	POROUS GRANULAR EMBANKMENT	CU YD	330		330
20700400	POROUS GRANULAR EMBANKMENT, SPECIAL	CU YD	399		399
25000210	SEEDING, CLASS 2A	ACRE	1.5	1.5	
25000350	SEEDING, CLASS 7	ACRE	1.5	1.5	
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	137	137	
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	137	137	
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	137	137	
25100105	MULCH, METHOD 1	ACRE	7.5	7.5	
25100630	EROSION CONTROL BLANKET	SQ YD	6831	6831	
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	760	760	
28000400	PERIMETER EROSION BARRIER	FOOT	1431	1431	
28100707	STONE DUMPED RIPRAP, CLASS A4	SQ YD	44	44	
28200200	FILTER FABRIC	SQ YD	44	44	
<del>3100100</del>	<del>SUB-BASE GRANULAR MATERIAL, TYPE A</del>	<del>TON</del>	<del>56</del>	<del>56</del>	
35600724	HOT - MIX ASPHALT BASE COURSE WIDENING, 12"	SQ YD	397	397	
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	0.2	0.2	
40600300	AGGREGATE (PRIME COAT)	TON	1.2	1.2	
40600982	HOT - MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	402	402	
40600990	TEMPORARY RAMP	SQ YD	38	38	
40603245	POLYMERIZED HOT - MIX ASPHALT BINDER COURSE, IL-19.0, N105	TON	24	24	
40603310	HOT - MIX ASPHALT SURFACE COURSE, MIX "C", N50	TON	33	33	
40603575	POLYMERIZED HOT - MIX ASPHALT SURFACE COURSE, MIX "E", N105	TON	47	47	
42001430	BRIDGE APPROACH PAVEMENT CONNECTOR (FLEXIBLE)	SQ YD	91	91	
44000100	PAVEMENT REMOVAL	SQ YD	87	87	
44000700	APPROACH SLAB REMOVAL	SQ YD	228	228	
44004250	PAVED SHOULDER REMOVAL	SQ YD	322	322	
48101200	AGGREGATE SHOULDERS, TYPE B	TON	371	371	
50102400	CONCRETE REMOVAL	CU YD	59.3		59.3

SUMMARY OF QUANTITIES				URBAN 90% FEDERAL 10% STATE	
CODE NUMBER	PAY ITEM	UNIT	QUANTITY	ROADWAY 1000	STRUCTURES X271-2A
50104650	SLOPE WALL REMOVAL	SQ YD	645		645
50104710	REMOVAL OF EXISTING BEARINGS	EACH	24		24
50104720	REMOVAL OF EXISTING CONCRETE DECK	EACH	1		1
50157300	PROTECTIVE SHIELD	SQ YD	339		339
50200100	STRUCTURE EXCAVATION	CU YD	399		399
50300225	CONCRETE STRUCTURES	CU YD	154.0		154.0
50300255	CONCRETE SUPERSTRUCTURE	CU YD	464.7		464.7
50300260	BRIDGE DECK GROOVING	SQ YD	1191		1191
50300300	PROTECTIVE COAT	SQ YD	1523		1523
50500305	ERECTING STRUCTURAL STEEL	L SUM	1		1
50500505	STUD SHEAR CONNECTORS	EACH	2984		2984
50501120	STRUCTURAL STEEL REMOVAL	L SUM	1		1
50501130	STRUCTURAL STEEL REPAIR	POUND	490		490
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	127,430		127,430
50800515	BAR SPLICERS	EACH	1143		1143
51100100	SLOPE WALL 4 INCH	SQ YD	660		660
51500100	NAME PLATES	EACH	1		1
52000110	PREFORMED JOINT STRIP SEAL	FOOT	70		70
52100210	ERECTING ELASTOMERIC BEARING ASSEMBLY, TYPE I	EACH	12		12
52100220	ERECTING ELASTOMERIC BEARING ASSEMBLY, TYPE II	EACH	6		6
52100520	ANCHOR BOLTS, 1"	EACH	24		24
52100540	ANCHOR BOLTS, 1 1/2"	EACH	24		24
58700300	CONCRETE SEALER	SQ FT	341		341
59000200	EPOXY CRACK INJECTION	FOOT	53		53
59100100	GEOCOMPOSITE WALL DRAIN	SQ YD	109		109
<del>60100060</del>	<del>CONCRETE HEADWALL FOR PIPE DRAINS</del>	<del>EACH</del>	<del>4</del>		<del>4</del>
60100945	PIPE DRAINS 12"	FOOT	270	270	
60109580	PIPE UNDERDRAINS FOR STRUCTURES 4"	FOOT	152		152
60500305	FILLING INLETS	EACH	3	3	
* 63000001	STEEL PLATE BEAM GUARD RAIL, TYPE A, 6 FOOT POSTS	FOOT	650	650	

\* SPECIALTY ITEMS

FILE NAME =	USER NAME = laughton1	DESIGNED LLQ	REVISED -
or:\p\work\PROJECTS\ALGHL\INR\08131885\072464_03-04_500.dgn		DRAWN JJS	REVISED -
	PLOT SCALE = 1/8"=1'-0"	CHECKED MTM	REVISED -
	PLOT DATE = Mar-19-2009 11:05:58AM	DATE MARCH 5, 2009	REVISED -

STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION

BL-55 SUMMARY OF QUANTITIES

F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
55	(B4-3HB-618R	SANGAMON	90	3
S.N. 084-0028		CONTRACT NO. 72A64		
FED. ROAD DIST. NO. 6 ILLINOIS FED. AID PROJECT				
SCALE: N/A	SHEET NO. 1 OF 1 SHEETS	STA.	TO STA.	