

S U M M A R Y O F Q U A N T I T I E S

CODE NO.	ITEM	UNIT	80% FED.
			20% STATE
			SFTY-2A
			TOTAL QTY
20400805	FURNISHED EXCAVATION, SPECIAL	CU YD	100
63000001	STEEL PLATE BEAM GUARD RAIL, TYPE A, 6 ^{FOOT} POSTS	FOOT	4712.5
63000003	STEEL PLATE BEAM GUARD RAIL, TYPE A, 9 ^{FOOT} POSTS	FOOT	1887.5
63000025	STEEL PLATE BEAM GUARD RAIL, ATTACHED TO STRUCTURES	FOOT	37.5
63100075	TRAFFIC BARRIER TERMINAL, TYPE 5A	EACH	14
63100167	TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) TANGENT	EACH	21
63100169	TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) FLARED	EACH	2
63100175	TRAFFIC BARRIER TERMINAL, TYPE 2 (SPECIAL)	EACH	2
63200307	STEEL PLATE BEAM GUARD RAIL REMOVAL, ATTACHED TO STRUCTURE	FOOT	37.5
63200310	GUARDRAIL REMOVAL	FOOT	7937
67100100	MOBILIZATION	L SUM	1
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1
78200410	GUARDRAIL MARKERS, TYPE A	EACH	112
78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	24
X0325194	IMPACT ATTENUATORS (FULLY REDIRECTIVE, NARROW), TEST LEVEL 3, SPECIAL	EACH	2
X0325363	REMOVE AND REPLACE STEEL BRIDGE RAIL, TYPE T-1 (SPECIAL)	FOOT	1591.2

QUANTITIES
FAP 510 (IL 96)
SECTION 120 GUARDRAIL
HANCOCK COUNTY