

EROSION CONTROL SCHEDULE

STATION LOCATION	28000250 TEMPORARY EROSION CONTROL SEEDING POUND	28000300 TEMPORARY DITCH CHECKS EACH	28000400 PERIMETER EROSION BARRIER FOOT	28100107 STONE RIPRAP, CLASS A4 SQ YD	28200200 FILTER FABRIC SQ YD	60100905 PIPE DRAINS 4" FOOT
MULE CREEK						
STA. 398+24.98 TO STA. 398+30.98, RT				4.0	4.0	
STA. 400+12.63 TO STA. 400+33.20, RT				33.3	33.3	
STA. 400+12.98 TO STA. 400+32.22, LT				38.3	38.3	
398+29.50, LT		1				
398+29.50, RT		1				
400+38.50, LT		1				
394+00.00 TO 398+55.50, LT			455.5			
394+00.00 TO 398+55.50, RT			459.6			
400+12.50 TO 403+43.17, RT			344.0			
403+59.43 TO 405+00.00, RT			144.4			
402+12.50 TO 404+12.00, LT			432.0			
398+63.50, 39.8' LT						9.1
398+63.50, 31.7' RT						5.1
400+04.50, 45.6' LT						15.6
400+04.50, 39.6' RT						8.9
BIG MUDDY CREEK						
STA. 573+55.28 TO STA. 573+68.58, RT				26.7	26.7	
STA. 573+67.01 TO STA. 573+87.63, LT				17.3	17.3	
STA. 575+98.94 TO STA. 576+03.94, RT				13.6	13.6	
STA. 576+11.06 TO STA. 576+16.06, RT				10.8	10.8	
569+00.00, LT			61.3			
569+05.00 TO 571+00.00, LT			210.4			
569+36.00 TO 570+38.48, RT			147.3			
570+45.53 TO 571+00.00, RT			102.1			
573+00.00 TO 573+34.85, LT			44.0			
573+00.00 TO 573+75.00, RT			78.8			
573+46.96 TO 573+75.00, LT			31.0			
576+00.00 TO 578+50.00, LT			250.0			
576+00.00 TO 576+94.11, RT			104.0			
577+26.63 TO 578+50.00, RT			123.5			
574+00.23, 39.4' LT						11.8
573+74.22, 32.0' RT						5.1
575+52.02, 42.4' LT TO 575+92.24, 27.8' LT						42.8
575+45.13, 41.8' RT TO 575+71.38, 29.5' RT						29.0
ENTIRE PROJECT	1760.0					
TOTALS	1760.0	3	2987.9	144.1	144.1	127.4

CLASS SI CONCRETE (OUTLET) SCHEDULE

STATION LOCATION	A-A TO D-D* FOOT	D-D TO E-E* FOOT	E-E TO OUTLET* FOOT	60600095 QUANTITY PER OUTLET CU YD
MULE CREEK				
400+47.11 TO 400+89.11, LT	42.0	4.0	17.3	4.5
400+47.50 TO 400+89.50, RT	42.0	4.0	17.3	4.5
BIG MUDDY CREEK				
573+12.48 TO 573+48.48, LT	36.0	4.0	17.3	4.1
573+01.33 TO 573+37.33, RT	36.0	4.0	17.3	4.1
TOTALS				17.2

*SEE STANDARD 606201-01

GUTTER SCHEDULE

STATION LOCATION	44000400 GUTTER REMOVAL FOOT	44002600 GUTTER OUTLET REMOVAL FOOT	60602800 CONCRETE GUTTER, TYPE B FOOT
MULE CREEK			
400+42.29 TO 405+00.00, RT	457.7		
400+46.94 TO 405+00.00, LT	453.1		
400+71.11 TO 405+00.00, LT			429.1
400+71.50 TO 405+00.00, RT			428.7
400+16.43 TO 400+46.94, LT		33.4	
399+99.55 TO 400+42.29, RT		53.4	
BIG MUDDY CREEK			
569+00.00 TO 573+34.12, LT	434.1		
569+00.00 TO 573+35.68, RT	435.7		
569+00.00 TO 573+24.48, LT			424.7
569+00.00 TO 573+13.33, RT			413.5
573+34.12 TO 573+62.74, LT		30.4	
573+35.68 TO 573+63.61, RT		29.2	
TOTALS	1780.6	146.4	1695.9

SEEDING SCHEDULE

STATION LOCATION	25000210 SEEDING, CLASS 2 (SPECIAL) ACRE
MULE CREEK	
394+00.00 TO 398+55.50, LT	0.16
394+00.00 TO 398+23.00, RT	0.20
400+38.50 TO 405+00.00, LT	0.48
400+38.50 TO 405+00.00, RT	0.27
BIG MUDDY CREEK	
569+00.00 TO 573+94.13, LT	0.27
569+00.00 TO 573+81.87, RT	0.19
575+73.87 TO 578+50.00, RT	0.05
575+86.13 TO 578+50.00, LT	0.05
TOTALS	1.6

RIGHT-OF-WAY SCHEDULE

STATION LOCATION	66600105 FURNISHING AND ERECTING RIGHT-OF-WAY MARKERS EACH	66700305 PERMANENT SURVEY MARKERS, TYPE II EACH
MULE CREEK		
397+50.03, 49.8' RT	1	
398+00.00, 50.0' LT	1	
399+00.00, 75.0' RT	1	
401+00.00, 100.0' LT	1	
402+50.00, 100.0' RT	1	
402+50.00, 75.0' RT	1	
403+00.00, 50.0' LT	1	
404+00.00, 50.0' RT	1	
TO BE DETERMINED		1
BIG MUDDY CREEK		
568+65.00, 45.0' LT	1	
569+00.00, 70.0' LT	1	
569+45.00, 70.0' LT	1	
569+60.00, 40.0' RT	1	
569+80.00, 45.0' LT	1	
570+10.00, 70.0' RT	1	
570+50.00, 70.0' RT	1	
571+00.00, 45.0' LT	1	
571+50.00, 55.0' RT	1	
571+75.00, 65.0' LT	1	
572+50.00, 65.0' LT	1	
573+00.00, 45.0' LT	1	
577+67.35, 55.0' RT	1	
577+67.35, 40.0' RT	1	
TO BE DETERMINED		1
TOTALS	22	2

TREE REMOVAL SCHEDULE

STATION LOCATION	20100110 TREE REMOVAL (6-15 UNITS DIAMETER) UNIT
BIG MUDDY CREEK	
570+10.00, 81.0' RT	10
570+15.00, 70.0' RT	9
570+30.0, 78.0' RT	12
570+34.00, 95.0' RT	12
570+31.00, 81.0' RT	6
570+48.00, 100.0' RT	9
570+48.00, 94.0' RT	13
569+50.00, 53.0' LT	14
569+50.00, 53.0' LT	6
569+50.00, 53.0' LT	13
TOTALS	104

