

SUMMARY OF QUANTITIES			1001 STATE	CONSTRUCTION TYPE CODE		
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	Y030-1E		
				LIGHTING		
67100100	MOBILIZATION	L SUM	1	1		
70100310	TRAFFIC CONTROL AND PROTECTION, STANDARD 701421	L SUM	1	1		
80400100	ELECTRIC SERVICE INSTALLATION	EACH	3	3		
81021330	CONDUIT PUSHED, 2" DIA., PVC	FOOT	655	655		
81603010	UNIT DUCT, 600V, 2-1C NO.10, 1/C NO.10 GROUND, (XLP-TYPE USE), 3/4" DIA. POLYETHYLENE	FOOT	4258	4258		
81900200	TRENCH AND BACKFILL FOR ELECTRICAL WORK	FOOT	3291	3291		
82102250	LUMINAIRE, SODIUM VAPOR, HORIZONTAL MOUNT, 250 WATT	EACH	24	24		
82500605	LIGHTING CONTROLLER PHOTOCELL RELAY	EACH	3	3		
83003600	LIGHT POLE, ALUMINUM, 45 FT. M.H., 15 FT. DAVIT ARM	EACH	24	24		
83600355	LIGHT POLE FOUNDATION METAL, 15" BOLT CIRCLE, 8" X 6"	EACH	24	24		
83800650	BREAKAWAY DEVICE, COUPLING, WITH STAINLESS STEEL SCREEN	EACH	96	96		
84200500	REMOVAL OF EXISTING LIGHTING UNIT, SALVAGE	EACH	2	2		
84200700	LIGHTING FOUNDATION REMOVAL	EACH	2	2		
84500110	REMOVAL OF LIGHTING CONTROLLER	EACH	2	2		
84500120	REMOVAL OF ELECTRIC SERVICE INSTALLATION	EACH	2	2		

FILE NAME - c:\pwork\FWIDOT\MCCLELLAN\A\dms35988	USER NAME = mclellan d774345-shd-light.dgn	DESIGNED - DRAWN -	REVISED - REVISED -
	PLOT SCALE = 50.0000' / 1" /	CHECKED -	REVISED -
	PLOT DATE = 3/11/2009	DATE	REVISED -

**STATE OF ILLINOIS  
DEPARTMENT OF TRANSPORTATION**

**SUMMARY OF QUANTITIES**

SCALE: SHEET NO. OF SHEETS STA. TO STA.

F.A.P. RTE. 322	SECTION (46,47)L-2	COUNTY MACON	TOTAL SHEETS 12	SHEET NO. 3
CONTRACT NO. 74345				
FED. ROAD DIST. NO. 7 ILLINOIS FED. AID PROJECT				