

GENERAL NOTES

THIS SECTION SHALL BE CONSTRUCTED IN ACCORDANCE WITH THE PLANS, THE "STANDARD SPECIFICATIONS FOR ROAD AND BRIDGE CONSTRUCTION", ADOPTED JANUARY 1, 2007; THE "SUPPLEMENTAL SPECIFICATIONS AND RECURRING SPECIAL PROVISIONS" INDICATED ON THE CHECK SHEET, AND "THE SPECIAL PROVISIONS" INCLUDED IN THE PROPOSAL.

THE WORK INCLUDED IN THIS SECTION CONSISTS OF REMOVING EXISTING CONCRETE DECK, STRUCTURAL STEEL BEAMS AND SCALES, REMOVE AND REPLACE BACK WALL, REMOVE AND REPLACE APPROACH PAVEMENTS, INSTALL NEW WEIGH-TRONIX SCALE AND ANY OTHER WORK NECESSARY TO COMPLETE THIS SECTION.

DURING THE REPAIR OF THE SCALE PIT, THE PIT SHALL BE CLEANED OUT BY THE CONTRACTOR AND APPROVED BY THE RESIDENT ENGINEER. NO ADDITIONAL COMPENSATION WILL BE ALLOWED FOR THIS WORK.

INDEX OF SHEETS

<u>SHEET NO.</u>	<u>TITLE</u>
1	COVER SHEET AND INDEX OF SHEETS
2	INDEX OF SHEETS AND GENERAL NOTES
3	SUMMARY OF QUANTITIES
4	GENERAL DATA
5	GENERAL PLAN AND ELEVATION
6	CONCRETE REMOVAL DETAILS
7	CONCRETE BACKWALL DETAILS
8	APPROACH PAVEMENT DETAILS

THE FOLLOWING STANDARDS ARE A PART OF THESE PLANS AND ARE INCLUDED FOLLOWING THE LAST NUMBERED SHEET OF THE PLANS.

000001-05	
001001-02	STANDARD SYMBOLS, ABBREVIATIONS AND PATTERNS
001006	AREAS OF REINFORCEMENT BARS
701901-01	DECIMAL OF AN INCH AND OF A FOOT TRAFFIC CONTROL DEVICES

FILE NAME =	USER NAME = steffenk	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	GENERAL NOTES & INDEX OF SHEETS	F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
ct:\pw\work\PIWIDOT\STEFFENK\08130057\0	74370-shr-cover.dgn	DRAWN -	REVISED -			70		Fayette	8	2
PLOT SCALE = 50.0000' / IN.	CHECKED -	REVISED -				CONTRACT NO. 74370				
PLOT DATE = 4/2/2009	DATE -	REVISED -				SCALE:	SHEET NO. OF SHEETS	STA. TO STA.	ILLINOIS FED. AID PROJECT	
						• D-7 WEIGH STATION REPAIRS 2009				