

SUMMARY OF QUANTITIES

SUMMARY OF QUANTITIES			TOTAL QUANTITIES	CONSTRUCTION TYPE CODE			SUMMARY OF QUANTITIES			TOTAL QUANTITIES	CONSTRUCTION TYPE CODE		
CODE NO	ITEM	UNIT		1000 100% STATE	-----	-----	CODE NO	ITEM	UNIT		1000 100% STATE	-----	-----
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	55.1	55.1			70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	1563	1563		
40600300	AGGREGATE (PRIME COAT)	TON	265	265			70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	560	560		
40600645	LEVELING BINDER (MACHINE METHOD), N90	TON	3680	3680			70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SO FT	1954	1954		
40600990	TEMPORARY RAMP	SQ YD	2013	2013			*78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SO FT	474	474		
40603545	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N90	TON	6553	6553			*78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	73297	73297		
44000158	HOT-MIX ASPHALT SURFACE REMOVAL, 2 1/4"	SO YD	86355	86355			*78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	1563	1563		
44001700	COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT	FOOT	322	322			*78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	560	560		
44003100	MEDIAN REMOVAL	SO FT	233	233			*78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	774	774		
44200188	PAVEMENT PATCHING, TYPE I, 16 INCH	SO YD	36	36			*78200300	PRISMATIC CURB REFLECTOR	EACH	52	52		
44200192	PAVEMENT PATCHING, TYPE II, 16 INCH	SO YD	134	134			*78200410	GUARDRAIL MARKERS, TYPE A	EACH	6	6		
44200196	PAVEMENT PATCHING, TYPE III, 16 INCH	SO YD	58	58			*78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	4	4		
44200198	PAVEMENT PATCHING, TYPE IV, 16 INCH	SO YD	54	54			78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	1349	1349		
44300200	STRIP REFLECTIVE CRACK CONTROL TREATMENT	FOOT	21141	21141			*80300100	LOCATING UNDERGROUND CABLE	FOOT	250	250		
48101200	AGGREGATE SHOULDERS, TYPE B	TON	188	188			*88600600	DETECTOR LOOP REPLACEMENT	FOOT	4910	4910		
48203029	HOT-MIX ASPHALT SHOULDERS, 8"	SO YD	139	139			X4400220	CURB REMOVAL AND REPLACEMENT	FOOT	98	98		
50105220	PIPE CULVERT REMOVAL	FOOT	81	81			*X7800100	PAINT PAVEMENT MARKING - RAISED MEDIAN	SO FT	197	197		
54200640	PIPE CULVERTS, TYPE 1, CORRUGATED STEEL OR ALUMINUM CULVERT PIPE 15"	FOOT	81	81			*X7800200	PAINT PAVEMENT MARKING CURB	FOOT	1216	1216		
60618300	CONCRETE MEDIAN SURFACE, 4 INCH	SO FT	2097	2097			20048665	RAILROAD PROTECTIVE LIABILITY INSURANCE	L SUM	1	1		
63000002	STEEL PLATE BEAM GUARD RAIL, TYPE A, 6.75' POSTS	FOOT	62.5	62.5									
63100167	TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) TANGENT	EACH	4	4									
63200310	GUARDRAIL REMOVAL	FOOT	550	550									
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	6	6									
67100100	MOBILIZATION	L SUM	1	1									
70102630	TRAFFIC CONTROL AND PROTECTION, STANDARD 701601	L SUM	1	1									
70102632	TRAFFIC CONTROL AND PROTECTION, STANDARD 701602	L SUM	1	1									
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1	1									
70102640	TRAFFIC CONTROL AND PROTECTION, STANDARD 701801	L SUM	1	1									
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	23440	23440									
70300210	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	SO FT	474	474									
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	73297	73297									

*specialty items

REV.

FILE NAME =	USER NAME = #USER#	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES	F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
#FILE#		DRAWN -	REVISED -			594	(61-63)RS-3	MADISON	40	3
PLOT SCALE = #SCALE#		CHECKED -	REVISED -			CONTRACT NO. T6B71				
PLOT DATE = #DATE#		DATE -	REVISED -			FED. ROAD DIST. NO. - ILLINOIS FED. AID PROJECT				
				SCALE: _____ SHEET NO. ____ OF ____ SHEETS STA. _____ TO STA. _____						