

# SUMMARY OF QUANTITIES

SUMMARY OF QUANTITIES			URBAN 100'-STATE	CONSTRUCTION TYPE CODE		
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	SFTY-2A		
50102400	CONCRETE REMOVAL	CU YD	41	41		
50300255	CONCRETE SUPERSTRUCTURE	CU YD	45	45		
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	6650	6650		
50800515	BAR SPLICERS	EACH	27	27		
52000208	FINGER PLATE EXPANSION JOINT, 3"	FOOT	86	86		
52000600	FABRIC REINFORCED ELASTOMERIC TROUGH	FOOT	93	93		
67000200	ENGINEER'S FIELD OFFICE, TYPE A	EACH	6	6		
67100100	MOBILIZATION	L SUM	1	1		
70100700	TRAFFIC CONTROL AND PROTECTION, STANDARD 701406	L SUM	1	1		
70101605	TRAFFIC CONTROL AND PROTECTION, STANDARD 701402 (SPECIAL)	EACH	1	1		
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	3440	3440		
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	15598	15598		
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	1288	1288		
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	5213	5213		
70400100	TEMPORARY CONCRETE BARRIER	FOOT	675	675		
70400200	RELOCATE TEMPORARY CONCRETE BARRIER	FOOT	612.5	612.5		
* 78008210	POLYUREA PAVEMENT MARKING TYPE I - LINE 4"	FOOT	4850	4850		
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	125	125		
78100200	TEMPORARY RAISED REFLECTIVE PAVEMENT MARKER	EACH	92	92		
78300100	PAVEMENT MARKING REMOVAL	SQ FT	1367	1367		
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	125	125		
X0321781	MECHANICAL SPLICE	EACH	230	230		
Z0030250	IMPACT ATTENUATORS, TEMPORARY (NON-REDIRECTIVE), TEST LEVEL 3	EACH	1	1		
Z0030350	IMPACT ATTENUATORS, RELOCATE (NON-REDIRECTIVE), TEST LEVEL 3	EACH	1	1		
40300200	BITUMINOUS MATERIALS (PRIME COAT)	TON	0.3	0.3		
40600300	AGGREGATE (PRIME COAT)	TON	2	2		
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	436	436		
40600990	TEMPORARY RAMP	SQ YD	83	83		
40603575	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX E, N105	TON	252.5	252.5		
48203100	HOT-MIX ASPHALT SHOULDERS	TON	44	44		
Z0016200	DECK SLAB REPAIR (PARTIAL)	SQ YD	300	300		
58100200	WATERPROOFING MEMBRANE SYSTEM	SQ YD	2056	2056		

\*Specialty Items

FILE NAME =	USER NAME = gelinh	DESIGNED -	REVISED -	<b>STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION</b>	<b>SUMMARY OF QUANTITIES</b>	F.A.I. RTE. 255	SECTION 82-1B-3-I	COUNTY ST CLAIR	TOTAL SHEETS 21	SHEET NO. 2
o:\pwork\pwidot\GELINH\dms88449\0876667-shr-500.dgn		DRAWN -	REVISED -							
	PLOT SCALE = 50.0000 / IN.	CHECKED -	REVISED -		SCALE: _____	SHEET NO. ___ OF ___ SHEETS		STA. _____ TO STA. _____		FED. ROAD DIST. NO. _____ ILLINOIS FED. AID PROJECT
	PLOT DATE = 4/18/2009	DATE -	REVISED -							<b>CONTRACT NO. 76C67</b>