

INDEX OF SHEETS

- 1 COVER SHEET
- 2 INDEX OF SHEETS, HIGHWAY STANDARDS,
GENERAL NOTES & COMMITMENTS
- 3 SUMMARY OF QUANTITIES
- 4 TYPICAL SECTIONS
- 5 SCHEDULE OF QUANTITIES
- 6-7 PHASE I RUNAROUND CONSTRUCTION
- 8-9 PHASE II RUNAROUND REMOVAL
- 10-11 STORM WATER POLLUTION PREVENTION PLAN
- 12-13 EROSION CONTROL
- 14-15 PLAT OF HIGHWAYS
- 16-17 GUARDRAIL DETAILS
- 19-23 PHASE I CONSTRUCTION CROSS SECTIONS
- 24-29A PHASE II REMOVAL CROSS SECTION
- 18 ENTRANCE DETAILS**

GENERAL NOTES:

1. THE STANDARDS AND REVISION NUMBERS SHALL APPLY TO THIS PROJECT.
2. THE CONTRACTOR SHALL VERIFY ALL DIMENSIONS AND CONDITIONS IN THE FIELD PRIOR TO CONSTRUCTION AND ORDERING MATERIALS.
3. ILLINOIS STATE LAW REQUIRES A 48-HOUR NOTICE BE GIVEN TO UTILITIES WITHIN THE PROJECT AREA BEFORE DIGGING BY CALLING J.U.L.I.E. AND BY NOTIFYING NON-J.U.L.I.E. MEMBERS INDIVIDUALLY. AGENCIES KNOWN TO HAVE FACILITIES WITHIN THE PROJECT AREA ARE AS FOLLOWS:
 - AMERENIP (GAS & ELECTRIC)
 - AT&T ILLINOIS
 - VILLAGE OF FAYETTEVILLE (WATER & SEWER)
 - VERIZON NORTH, INC.
 MEMBERS OF J.U.L.I.E. (800) 892-0123 OR 811 ARE INDICATED BY •. NON-MEMBERS MUST BE NOTIFIED INDIVIDUALLY.
4. THE RESIDENT ENGINEER SHALL VERIFY THE EXISTENCE OF HIGHWAY LIGHTING AND/OR I.T.S. UTILITIES WITHIN THE PROJECT LIMITS. IF HIGHWAY LIGHTING AND/OR I.T.S. EXISTS WITHIN THE PROJECT LIMITS, AND IF THESE ITEMS REQUIRE LOCATING, THE CONTRACTOR SHALL BE DIRECTED TO DO SO ACCORDING TO SECTION 803 OF THE STANDARD SPECIFICATIONS. THIS WORK SHALL BE PAID FOR ACCORDING TO ARTICLE 109.04 OF THE STANDARD SPECIFICATIONS.
5. ALL EXISTING RIGHT-OF-WAY LINES SHOWN ON THE PLAN SHEETS ARE GRAPHICAL REPRESENTATIONS AND SHALL NOT BE USED AS A MEANS TO ESTABLISH OWNERSHIP. IN ALL MATTERS RELATING TO RIGHT-OF-WAY, THE PLAT OF HIGHWAYS SHALL BE THE CONTROLLING DOCUMENT.
6. THE CONTRACTOR FOR CONTRACT 76885 WILL SUPPLY, INSTALL, MAINTAIN AND REMOVE TRAFFIC CONTROL AND PROTECTION, STANDARD 701331.
7. THE REMOVAL OF THE END SECTIONS PLACED ON TEMPORARY PIPE CULVERTS SHALL BE INCLUDED IN THE COST OF THE END SECTION.
8. THE REMOVAL OF EXISTING END SECTIONS SHALL BE INCLUDED IN THE COST OF PIPE CULVERT REMOVAL.
9. THE PROPOSED TRAFFIC BARRIER TERMINAL ATTACHED TO THE NORTHEAST CORNER OF SN 082-0078 SHALL COMPLY WITH THE DETAILS IN THE PLANS AND MANUFACTURER'S DETAILS IN ORDER TO MATCH THE EXISTING GUARDRAIL ELEMENTS THAT WERE ERECTED PRIOR TO JANUARY 1, 2007.

COMMITMENTS

NONE

HIGHWAY STANDARDS

- 000001-05 635006-03
- 280001-04 635011-02
- 542401-01 701201-03
- 630001-08 701326-03
- 630301-05 701901-01

FILE NAME =	USER NAME = owenbj	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	INDEX OF SHEETS, HIGHWAY STANDARDS, GENERAL NOTES AND COMMITMENTS	F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
cr:\pw\work\pwidot\owenbj\dms91591\p1n82295b.dgn	PLOT SCALE = 50.0000' / 1".	DRAWN -	REVISED -			817	421R-1	ST. CLAIR	29	2
PLOT DATE = 12/19/2008	DATE -	CHECKED -	REVISED -			CONTRACT NO. 76C74				
						SCALE:		SHEET NO. OF SHEETS		STA. TO STA.

Rev.