SUMMARY OF QUANTITIES

SUMMARY OF QUANTITIES

CODE NO	ITEM	UNIT	100% STATE TOTAL QUANTITIES	CONSTRUCTION TYPE CODE 1000-2A		
20100500	TREE REMOVAL, ACRES	ACRE	0.75	0.75		
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	225	225		
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	225	225		
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	225	225		
20200100	EARTH EXCAVATION	CU YD	14250	14250		
20400800	FURNISHED EXCAVATION	CU YD	12650	12650		
25000200	SEEDING, CLASS 2	ACRE	2.5	2.5		
25100115	MULCH, METHOD 2	ACRE	2.5	2.5		
25100630	EROSION CONTROL BLANKET	SQ YD	810	810		
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	250	250		
28000300	TEMPORARY DITCH CHECKS	EACH	1	1		
28000400	PERIMETER EROSION BARRIER	FOOT	1515	1515		
28000500	INLET AND PIPE PROTECTION	EACH	4	4		
35100700	AGGREGATE BASE COURSE, TYPE A 8"	SQ YD	2250	2250		
40200700	AGGREGATE SURFACE COURSE, TYPE A 8"	SQ YD	470	470		
40603085	HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N70	TON	725	725		
40603340	HOT-MIX ASPHALT SURFACE COURSE, MIX "D", N70	TON	190	190		
44000100	PAVEMENT REMOVAL	SQ YD	2250	2250		
44004250	PAVED SHOULDER REMOVAL	SQ YD	90	90		
48100500	AGGREGATE SHOULDERS, TYPE A 6"	SQ YD	55	55		
48203029	HOT-MIX ASPHALT SHOULDERS, 8"	SQ YD	90	90		
50105220	PIPE CULVERT REMOVAL	FOOT	60	60		
54213459	END SECTIONS 24"	EACH	6	6		
54213471	END SECTIONS 36"	EACH	4	4		
5422D024	PIPE CULVERTS, CLASS D, TYPE 2 24" (TEMPORARY)	FOOT	255	255		
5422D036	PIPE CULVERTS, CLASS D, TYPE 2 36" (TEMPORARY)	FOOT	50	50		
542D1081	PIPE CULVERTS, CLASS D, TYPE 2 36"	FOOT	60	60		
* 63000000	STEEL PLATE BEAM GUARD RAIL, TYPE A	FOOT	200	200		
63200310	GUARDRAIL REMOVAL	FOOT	225	225		
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	3	3		
67100100	MOBILIZATION	L SUM	1	1		
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1	1		

SUMMARY OF QUANTITIES

CODE NO	ITEM	UNIT	100% STATE TOTAL QUANTITIES	CONSTRUCTION TYPE CODE 1000-2A		
70100500	TRAFFIC CONTROL AND PROTECTION, STANDARD 701326	L SUM	1	1		
70500100	TEMPORARY STEEL PLATE BEAM GUARD RAIL, TYPE A	FOOT	362.5	362.5		
* 78200410	GUARDRAIL MARKERS, TYPE A	EACH	5	5		
* 78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	3	3		
X7050167	TEMPORARY TRAFFIC BARRIER TERMINAL, TYPE 1, SPECIAL (TANGENT)	EACH	3	3		

*Specialty Items

Rev.

FILE NAME = c:\pw_work\pwidot\owenbj\dms51591\pln022205b.dgn	USER NAME = owenbj	DESIGNED -	REVISED -
		DRAWN -	REVISED -
	PLOT SCALE = 50.0000 ' / IN.	CHECKED -	REVISED -
	PLOT DATE = 12/19/2008	DATE -	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: | SHEET NO. OF SHEETS | STA. TO STA.

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
817	421R-1	ST. CLAIR	29	3

CONTRACT NO. 76C74

FED. ROAD DIST. NO. | ILLINOIS | FED. AID PROJECT