

SCHEDULE OF QUANTITIES												
LOCATION	APPROX LENGTH WIDTH		SEEDING CL 2 (ACRE)	NITROGEN FERT NUTR (POUND)	PHOSPHOROUS FERT NUTR (POUND)	POTASSIUM FERT NUTR (POUND)	MULCH METHOD 2 (ACRE)	PERIMETER EROS BAR (FOOT)	CL D PATCH T2 12" (SQ YD)	FORCE MAIN CLEANOUT VAULT (EACH)	FORCE MAIN CLEANOUT VAULT HD F&L (EACH)	LOCATING STORM SEWER/DEEP WELL FORCE MAIN (EACH)
STATION 1+95	20	20	0.01	0.83	0.83	0.83	0.01	80		1		1
STATION 6+30	20	20	0.01	0.83	0.83	0.83	0.01	80		1		1
STATION 10+30	20	20						80	7		1	1
STATION 15+00	20	20						80	7		1	1
STATION 18+30	20	20						80	7		1	1
TOTALS			0.02	1.65	1.65	1.65	0.02	400.00	21.00	2	3	5