

SUMMARY OF QUANTITIES

CODE NUMBER	ITEM DESCRIPTION	UNIT	TOTAL QUANTITY	HBP FUNDING	
				80% FEDERAL; X028-2A	20% STATE
				JOHNSON SN 044-7014	PERRY SN 073-7053
QUANTITY	QUANTITY	QUANTITY	QUANTITY	QUANTITY	QUANTITY
20300100	CHANNEL EXCAVATION	CU YD	23	8.0	15
20700220	POROUS GRANULAR EMBANKMENT	CU YD	1080	740	340
25000200	SEEDING, CLASS 2	ACRE	0.3	0.2	0.1
25000350	SEEDING, CLASS 7	ACRE	0.3	0.2	0.1
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	39	26.0	13.0
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	27	18.0	9.0
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	27	18.0	9.0
25000700	AGRICULTURAL GROUND LIMESTONE	TON	0.6	0.4	0.2
25100115	MULCH, METHOD 2	ACRE	0.6	0.4	0.2
28000300	TEMPORARY DITCH CHECKS	EACH	6	2	4
28000400	PERIMETER EROSION BARRIER	FOOT	773	248.0	525.0
28100209	STONE RIPRAP, CLASS A5	TON	146	146.0	0.0
28100210	STONE RIPRAP, CLASS A5(SPECIAL)	TON	57	0.0	57.0
28200200	FILTER FABRIC	SQ YD	105	73	32
35600716	HOT-MIX ASPHALT BASE COURSE WIDENING, 10"	SQ YD	170	0	170
40603090	HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N90	TON	83	83.0	0.0
40603320	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N90	TON	12	12.0	0.0
42000501	PORTLAND CEMENT CONCRETE PAVEMENT 10" (JOINTED)	SQ YD	145	0	145
44000100	PAVEMENT REMOVAL	SQ YD	313	170	143
48101600	AGGREGATE SHOULDERS, TYPE B 8"	SQ YD	32	32	0
50100100	REMOVAL OF EXISTING STRUCTURES	EACH	2	1	1
50200100	STRUCTURE EXCAVATION	CU YD	1286	1021	265
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	20990	5750	15240
50800515	BAR SPLICERS	EACH	58	0	58
51205200	TEMPORARY SHEET PILING	SQ FT	890	0	890
54011109	PRECAST CONCRETE BOX CULVERT 11'x9'	FOOT	66	66.0	0.0
54002020	EXPANSION BOLTS 3/4 INCH	EACH	56	56	0
54003000	CONCRETE BOX CULVERTS	CU YD	123.6	35.0	88.6
63100087	TRAFFIC BARRIER TERMINAL, TYPE 6A	EACH	4	0	4
63100167	TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) TANGENT	EACH	3	0	3
63200310	GUARDRAIL REMOVAL	FOOT	237.5	0	237.5
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	3	0	3

FILE NAME	USER NAME = cornellm	DESIGNED	REVISED	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES	F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
onhp...ork\PIWEDT\CORNE...LLM\ams49840\c...78261.sht.misc.dgn	DRAWN	REVISED	881/329			35B-1/18B-1	JOHNSON/PERRY	26	3	
PLOT SCALE = 50.0000' / 1"	CHECKED	REVISED	CONTRACT NO. 78069							
PLOT DATE = 3/18/2009	DATE	REVISED	FED. ROAD DIST. NO.			ILLINOIS FED. AID PROJECT				
SCALE:						SHEET NO. OF SHEETS		STA. TO STA.		