

INDEX OF SHEETS

SHEET NO.	DESCRIPTION
1	COVER SHEET
2	SIGNATURE BLOCK
3	INDEX OF SHEETS; HIGHWAY STANDARDS; GENERAL NOTES
4	SUMMARY OF QUANTITIES
5 - 7	TYPICAL SECTIONS
8	PCC PAVEMENT SCHEDULE; PAVEMENT MARKING SCHEDULE
9	PAVEMENT REMOVAL DETAIL
10	PCC PAVEMENT LAYOUT DETAIL
11	PAVEMENT MARKING DETAIL
12 - 13	CURB AND GUTTER REPAIR DETAIL
14 - 17	TRAFFIC CONTROL (SPECIAL) - STAGE 1 THRU 4
18	DETOUR SIGNING SCHEDULE
19 - 24	DETOUR SIGNING PLAN

HIGHWAY STANDARDS

420001-07
 420101-04
 420111-02
 420701-02
 424001-05
 606001-04
 701306-02
 701311-03
 701501-05
 701901-01
 780001-02
 BLR 17-4
 BLR 21-8

GENERAL NOTES

1. PRIOR TO PLACEMENT OF THE FINAL PAVEMENT MARKINGS, THE RESIDENT ENGINEER SHOULD CONTACT THE BUREAU OF OPERATIONS AND ARRANGE FOR INSPECTION AND APPROVAL OF THE PAVEMENT MARKING LAYOUT.
2. THE CONTRACTOR SHALL STAMP STATIONING IN THE PROPOSED PCC MATS AT 300 FO. INTERVALS ON ALTERNATING SIDES OF THE PAVEMENT AND AS DIRECTED BY THE ENGINEER. THE STATION SYMBOL STAMPS USED SHALL BE FURNISHED BY THE CONTRACTOR. THEY SHALL BE 5 1/2" TALL OF A DESIGN APPROVED BY THE ENGINEER AND SHALL REMAIN THE PROPERTY OF THE CONTRACTOR.
3. AT ALL LOCATIONS WHERE THE PROPOSED HOT-MIX ASPHALT OR CONCRETE PAVEMENT JOINS AN EXISTING HOT-MIX ASPHALT OR CONCRETE PAVEMENT, A FULL DEPTH SAWED JOINT SHALL BE CONSTRUCTED. THE COST OF THIS JOINT WILL BE INCLUDED IN THE COST OF THE TYPE OF PAVEMENT BEING CONSTRUCTED.
4. COMMITMENTS: NO LANE CLOSURE DURING THRESHERMANS FESTIVAL FROM AUGUST 19TH TO AUGUST 23RD..

PAVEMENT CORE SCHEDULE

Sta. 1263+00 (North of Mulberry St. on Main St.)	0" - 3 5/8" Asphalt
	3 5/8" - 7 3/8" Brick
	7 3/8" - 11 1/2" Sand, Gravel & Cinders
	11 1/2" - 3' Medium, very moist, brown silty Clay
Sta. 1264+80 (On Main St. south of Intersection with Water St.)	0" - 1 3/4" Asphalt
	1 3/4" - 5 1/2" Brick
	5 1/2" - 9 1/2" Sand, Gravel & Cinders
	9 1/2" - 3' Medium, very moist, brown silty Clay
140' east of Intersection of Main St. and Water St. (IL 154) (East end of square)	0" - 3" Asphalt
	3" - 13" Concrete
	13" - 16" Asphalt
	16" - 3' Stiff, very moist, brown Clay
Sta. 1266+65 (On Water St./IL 13/127 - West end of square)	0" - 5 1/4" Asphalt
	5 1/4" - 9" Brick
	9" - 12" Sand
	12" - 15" Sand, Gravel & Cinders
	15" - 3' Stiff, very moist, brown Clay
Sta. 1265+14.6 (Intersection of Main St. and Water St. on Water St.)	0" - 2 1/4" Asphalt
	2 1/4" - 6" Brick
	6" - 9" Sand
	9" - 17" Sand, Gravel & Cinders
	17" - 3' Stiff, very moist, brown Clay

*FAP 42/841

FILE NAME =	USER NAME = moor-dkr	DESIGNED - ----	REVISED - ----	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	INDEX OF SHEETS STANDARDS	F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
et:\pwork\PIWIDOT\MCCOROKR\10128164\781	7-shit-mso.dgn	DRAWN - ----	REVISED - ----			8	(8,103,108)I-1	PERRY	24	3
	PLOT SCALE = 100.0000' / IN.	CHECKED - ----	REVISED - ----							
	PLOT DATE = 3/24/2009	DATE - ----	REVISED - ----		SCALE: _____ SHEET NO. ____ OF ____ SHEETS STA. _____ TO STA. _____					FED. ROAD DIST. NO. _____ ILLINOIS FED. AID PROJECT
								CONTRACT NO. 78117		