

SUMMARY OF QUANTITIES

FAP 42/841 (IL
13/127/154)

URBAN
100% STATE
PERRY
1000
QUANTITY

PAY CODE	ITEM DESCRIPTION	UNIT	TOTAL QUANTITY	
X0325542	HIGH EARLY STRENGTH PORTLAND CEMENT CONCRETE PAVEMENT 10" (JOINTED)	SQ YD	1796	1796
X0325702	NIGHTTIME WORK ZONE LIGHTING	L SUM	1.0	1.0
31100500	SUB-BASE GRANULAR MATERIAL, TYPE A 6"	SQ YD	1796	1796
42001300	PROTECTIVE COAT	SQ YD	1925	1925
42400500	PORTLAND CEMENT CONCRETE SIDEWALK, SPECIAL	SQ FT	317	317
44000100	PAVEMENT REMOVAL	SQ YD	1796	1796
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	263	263
44000600	SIDEWALK REMOVAL	SQ FT	223	223
60603800	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.12	FOOT	263	263
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	2.0	2.0
67100100	MOBILIZATION	L SUM	1.0	1.0
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1.0	1.0
70101800	TRAFFIC CONTROL AND PROTECTION, (SPECIAL)	L SUM	1.0	1.0
70101830	TRAFFIC CONTROL AND PROTECTION, STANDARD BLR 21	L SUM	1.0	1.0
70102620	TRAFFIC CONTROL AND PROTECTION, STANDARD 701501	L SUM	1.0	1.0
70106800	CHANGEABLE MESSAGE SIGN	CAL MO	2.0	2.0
70300100	SHORT- TERM PAVEMENT MARKING	FOOT	24	24
70300220	TEMPORARY PAVEMENT MARKING-LINE 4"	FOOT	307	307
70300240	TEMPORARY PAVEMENT MARKING-LINE 6"	FOOT	358	358
70300280	TEMPORARY PAVEMENT MARKING-LINE 24"	FOOT	18	18
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	60	60
* 72000100	SIGN PANEL - TYPE 1	SQ FT	464	464
* 72000200	SIGN PANEL - TYPE 2	SQ FT	114	114
* 78008210	POLYUREA PAVEMENT MARKING TYPE I - LINE 4"	FOOT	307	307
* 78008230	POLYUREA PAVEMENT MARKING TYPE I - LINE 6"	FOOT	358	358
* 78008270	POLYUREA PAVEMENT MARKING TYPE I - LINE 24"	FOOT	18	18

**Specialty Items*

*FAP 42/841

FILE NAME =	USER NAME = macordkr	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES	F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.		
o:\pw_work\PI\DOT\MCCORDKR\d0128164\781	7-shit-misc.dgn	DRAWN -	REVISED -			---	(S.103.1081)-1	PERRY	24	4		
	PLOT SCALE = 100.0000' / IN.	CHECKED -	REVISED -			SCALE: _____	SHEET NO. _____ OF _____ SHEETS	STA. _____ TO STA. _____	CONTRACT NO. 78117			
	PLOT DATE = 3/23/2009	DATE -	REVISED -			FED. ROAD DIST. NO. - (ILLINOIS) FED. AID PROJECT						