



**SUPERSTRUCTURE  
BILL OF MATERIALS**

Bar	No.	Size	Length	Shape
a	573	#5	25'-8"	—
a1	327	#5	6'-5"	U
b	189	#5	24'-10"	—
b1	52	#6	30'-0"	—
b2	186	#5	28'-8"	—
m	6	#6	25'-8"	—
m1	16	#6	8'-7"	—
m2	6	#6	7'-0"	—
m3	4	#6	1'-9"	—
s1	54	#4	8'-8"	□
Item	Unit	Quantity		
Reinforcement Bars, Epoxy Coated	Pound	31,150		
Concrete Superstructures	Cu. Yd.	122.6		

SECTION 03-26140-00-BR  
SECTION 03-21117-00-BR  
LIVINGSTON COUNTY

**SUPERSTRUCTURE PLAN  
AND CROSS SECTION**

- NOTES:**
- 1.) Work this sheet with Sheet B7.
  - 2.) Bars indicated thus 27x7-#5 Etc. indicates 27 lines of bars with 7 lengths per line.
  - 3.) Minimum bar lap #5 = 1'-8".