

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
358	B6-00075-00-AS	WOODFORD	74	7
STA. _____		TO STA. _____		
FED. ROAD DIST. NO. 4		ILLINOIS		FED. AID PROJECT

SEEDING SCHEDULE (1 OF 2)						25000100	25000200	25100115	28000250	25000400	25000500	25000600
LOCATION	PLAN AREA	PLAN AREA	PLAN AREA X SLOPE FACTOR (1.03)	PLAN AREA X SLOPE FACTOR (1.06)	TOTAL AREA	SEEDING, CLASS 1	SEEDING, CLASS 2	MULCH, METHOD 2	TEMPORARY EROSION CONTROL SEEDING	FERTILIZER		
										NITROGEN FERTILIZER NUTRIENT	PHOSPHORUS FERTILIZER NUTRIENT	POTASSIUM FERTILIZER NUTRIENT
STATION TO STATION	FORESLOPES (1:4)	BACKSLOPES (1:3)	FORESLOPES (1:4)	BACKSLOPES (1:3)					100 LBS/ACRE X 3 APPLICATIONS	90 LBS/ACRE	90 LBS/ACRE	90 LBS/ACRE
	SQ.FT.	SQ.FT.	SQ.FT.	SQ.FT.	SQ.FT.	ACRE	ACRE	ACRE	POUND	POUND	POUND	POUND
RIGHT SIDE												
STA. 167+00.00 RT TO STA. 169+33.82 RT	4036.66	1798.17	4157.76	1906.06	6063.82		0.14	0.14	41.76	12.53	12.53	12.53
STA. 169+33.82 RT TO STA. 170+60.93 RT	2558.41	962.30	2635.16	1020.04	3655.21		0.08	0.08	25.17	7.55	7.55	7.55
STA. 170+60.93 RT TO STA. 171+00.00 RT	1335.56	655.49	1375.63	694.82	2070.45		0.05	0.05	14.26	4.28	4.28	4.28
STA. 171+00.00 RT TO STA. 176+00.00 RT	8989.61	4320.76	9259.30	4580.01	13839.31		0.32	0.32	95.31	28.59	28.59	28.59
STA. 176+00.00 RT TO STA. 181+00.00 RT	8035.55	5964.95	8276.62	6322.85	14599.47		0.34	0.34	100.55	30.16	30.16	30.16
STA. 181+00.00 RT TO STA. 186+00.00 RT	8385.48	6815.43	8637.05	7224.36	15861.41		0.36	0.36	109.24	32.77	32.77	32.77
STA. 186+00.00 RT TO STA. 191+00.00 RT	8846.57	5153.52	9111.97	5462.73	14574.70		0.33	0.33	100.38	30.11	30.11	30.11
STA. 191+00.00 RT TO STA. 196+00.00 RT	7737.62	5529.16	7969.74	5860.91	13830.65		0.32	0.32	95.25	28.58	28.58	28.58
STA. 196+00.00 RT TO STA. 201+00.00 RT	10599.56	5341.86	10917.54	5662.37	16579.91		0.38	0.38	114.19	34.26	34.26	34.26
STA. 201+00.00 RT TO STA. 206+00.00 RT	11713.81	2282.57	12065.22	2419.53	14484.75		0.33	0.33	99.76	29.93	29.93	29.93
STA. 206+00.00 RT TO STA. 210+80.00 RT	11939.60	2848.77	12297.79	3019.70	15317.49		0.35	0.35	105.49	31.65	31.65	31.65
STA. 210+80.00 RT TO STA. 211+50.40 RT	730.94	739.23	752.87	783.58	1536.45	0.04		0.04	10.58	3.17	3.17	3.17
STA. 210+80.00 RT TO STA. 211+50.40 RT	1121.84	1406.22	1155.50	1490.59	2646.09	0.06		0.06	18.22	5.47	5.47	5.47
STA. 212+76.68 RT TO STA. 213+00.00 RT	45.98	161.41	47.36	171.10	218.46	0.005		0.01	1.50	0.45	0.45	0.45
STA. 213+00.00 RT TO STA. 216+00.00 RT	4583.13	3756.41	4720.62	3981.80	8702.42		0.20	0.20	59.93	17.98	17.98	17.98
STA. 216+00.00 RT TO STA. 221+00.00 RT	11117.01	6878.59	11450.52	7291.30	18741.82		0.43	0.43	129.08	38.72	38.72	38.72
STA. 221+00.00 RT TO STA. 223+00.00 RT	4766.50	4727.85	4909.49	5011.52	9921.01		0.23	0.23	68.33	20.50	20.50	20.50
STA. 223+00.00 RT TO STA. 223+95.41 RT	2907.13	1512.92	2994.34	1603.70	4598.04		0.11	0.11	31.67	9.50	9.50	9.50
STA. 223+95.41 RT TO STA. 226+00.00 RT	5684.84	2002.42	5855.38	2122.57	7977.95		0.18	0.18	54.94	16.48	16.48	16.48
STA. 226+00.00 RT TO STA. 231+00.00 RT	9649.64	4350.38	9939.13	4611.41	14550.54		0.33	0.33	100.21	30.06	30.06	30.06
STA. 231+00.00 RT TO STA. 236+00.00 RT	9493.56	5866.65	9778.37	6218.65	15997.02		0.37	0.37	110.17	33.05	33.05	33.05
STA. 236+00.00 RT TO STA. 241+00.00 RT	7691.16	6263.18	7921.90	6638.97	14560.87		0.33	0.33	100.28	30.08	30.08	30.08
STA. 241+00.00 RT TO STA. 246+00.00 RT	10680.95	5612.93	11001.38	5949.70	16951.08		0.39	0.39	116.74	35.02	35.02	35.02
STA. 246+00.00 RT TO STA. 248+00.00 RT	4213.68	1594.30	4340.09	1689.96	6030.04		0.14	0.14	41.53	12.46	12.46	12.46
STA. 248+00.00 RT TO STA. 249+50.00 RT	2864.99	1205.88	2950.94	1278.24	4229.18		0.10	0.10	29.13	8.74	8.74	8.74
STA. 249+50.00 RT TO STA. 251+25.80 RT	3800.32	1384.58	3914.33	1467.65	5381.99	0.12		0.12	37.07	11.12	11.12	11.12
STA. 251+25.80 RT TO STA. 253+00.00 RT	4423.81	575.57	4556.52	610.11	5166.63	0.12		0.12	35.58	10.67	10.67	10.67
STA. 252+38.01 RT	19514.51	TEMPORARY EASEMENT			19514.51	0.45		0.45	134.40	40.32	40.32	40.32
STA. 253+00.00 RT TO STA. 256+00.00 RT	6411.00	1990.09	6603.33	2109.49	8712.83		0.20	0.20	60.01	18.00	18.00	18.00
STA. 256+00.00 RT TO STA. 261+00.00 RT	9580.74	4793.57	9868.16	5081.19	14949.35		0.34	0.34	102.96	30.89	30.89	30.89
STA. 261+00.00 RT TO STA. 266+00.00 RT	12950.70	3548.72	13339.22	3761.64	17100.87		0.39	0.39	117.77	35.33	35.33	35.33
STA. 266+00.00 RT TO STA. 267+00.00 RT	1489.13	1006.92	1533.81	1067.34	2601.14		0.06	0.06	17.91	5.37	5.37	5.37
STA. 267+00.00 RT TO STA. 271+00.00 RT	8812.23	3963.00	9076.60	4200.78	13277.37		0.30	0.30	91.44	27.43	27.43	27.43
STA. 273+80.00 RT	6000.00	TEMPORARY EASEMENT			6000.00		0.14	0.14	41.32	12.40	12.40	12.40
STA. 271+00.00 RT TO STA. 276+00.00 RT	15598.72	7087.60	16066.68	7512.86	23579.53		0.54	0.54	162.39	48.72	48.72	48.72
STA. 276+00.00 RT TO STA. 277+51.55 RT	4622.28	2431.56	4760.94	2577.46	7338.40		0.17	0.17	50.54	15.16	15.16	15.16
STA. 277+51.55 RT TO STA. 280+00.00 RT	5569.79	3741.85	5736.89	3966.37	9703.25		0.22	0.22	66.83	20.05	20.05	20.05
TOTAL RIGHT SIDE ONLY						0.79	8.18	8.97	2691.90	807.57	807.57	807.57

PLOT DATE = 04/15/09
 FILE NAME = SCHEDULE
 PLOT SCALE = 1"=100'
 USER NAME = JLM

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES

DESIGNED BY: AMPH & KLM
 DATE: APRIL 2009

DRAWN BY: AMPH & KLM
 CHECKED BY: JLM & RAH