

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
358	B6-00075-00-AS	WOODFORD	74	8
STA. _____ TO STA. _____		FED. ROAD DIST. NO. 4 ILLINOIS FED. AID PROJECT		

SEEDING SCHEDULE (2 OF 2)						25000100	25000200	25100115	28000250	25000400	25000500	25000600
LOCATION	PLAN AREA	PLAN AREA	PLAN AREA X SLOPE FACTOR (1.03)	PLAN AREA X SLOPE FACTOR (1.06)	TOTAL AREA	SEEDING, CLASS 1	SEEDING, CLASS 2	MULCH, METHOD 2	TEMPORARY EROSION CONTROL SEEDING	FERTILIZER		
										NITROGEN FERTILIZER NUTRIENT	PHOSPHORUS FERTILIZER NUTRIENT	POTASSIUM FERTILIZER NUTRIENT
STATION TO STATION	FORESLOPES (1:4)	BACKSLOPES (1:3)	FORESLOPES (1:4)	BACKSLOPES (1:3)					100 LBS/ACRE X 3 APPLICATIONS	90 LBS/ACRE	90 LBS/ACRE	90 LBS/ACRE
	SQ.FT.	SQ.FT.	SQ.FT.	SQ.FT.	SQ.FT.	ACRE	ACRE	ACRE	POUND	POUND	POUND	POUND
LEFT SIDE												
STA. 167+00.00 LT TO STA. 169+00.00 LT	4355.76	1236.68	4486.43	1310.89	5797.32		0.13	0.13	39.93	11.98	11.98	11.98
STA. 169+00.00 LT TO STA. 170+60.93 LT	3545.29	1485.29	3651.65	1574.41	5226.06		0.12	0.12	35.99	10.80	10.80	10.80
STA. 170+60.93 LT TO STA. 172+00.00 LT	3079.18	1368.77	3171.55	1450.90	4622.45		0.11	0.11	31.84	9.55	9.55	9.55
STA. 172+00.00 LT TO STA. 173+50.00 LT	2977.73	1128.76	3067.06	1196.48	4263.54		0.10	0.10	29.36	8.81	8.81	8.81
STA. 173+00.00 LT TO STA. 174+00.00 LT	502.93	514.03	518.02	544.87	1062.89	0.02		0.02	7.32	2.20	2.20	2.20
STA. 174+00.00 LT TO STA. 175+00.00 LT	1100.81	981.45	1133.83	1040.34	2174.17	0.05		0.05	14.97	4.49	4.49	4.49
STA. 175+00.00 LT TO STA. 177+00.00 LT	3627.37	1805.59	3736.19	1913.93	5650.12		0.13	0.13	38.91	11.67	11.67	11.67
STA. 172+00.00 LT TO STA. 177+95.00 LT	1227.95	342.94	1264.79	363.51	1628.30		0.04	0.04	11.21	3.36	3.36	3.36
STA. 177+95.00 LT TO STA. 182+62.00 LT	7621.92	3525.89	7850.58	3737.44	11588.02		0.27	0.27	79.81	23.94	23.94	23.94
STA. 182+62.00 LT TO STA. 183+00.00 LT	177.96	162.24	183.30	171.97	355.27		0.01	0.01	2.45	0.73	0.73	0.73
STA. 183+00.00 LT TO STA. 184+49.50 LT	2280.33	1146.41	2348.74	1215.20	3563.94	0.08		0.08	24.55	7.36	7.36	7.36
STA. 184+49.50 LT TO STA. 187+30.00 LT	4631.07	2481.65	4770.00	2630.55	7400.55	0.17		0.17	50.97	15.29	15.29	15.29
STA. 187+30.00 LT TO STA. 192+00.00 LT	8113.84	5306.04	8357.26	5624.40	13981.66		0.32	0.32	96.29	28.89	28.89	28.89
STA. 192+00.00 LT TO STA. 197+24.54 LT	7949.33	6644.59	8187.81	7043.27	15231.08		0.35	0.35	104.90	31.47	31.47	31.47
STA. 197+24.54 LT TO STA. 202+00.00 LT	10112.66	6317.94	10416.04	6697.01	17113.05		0.39	0.39	117.86	35.36	35.36	35.36
STA. 202+00.00 LT TO STA. 207+00.00 LT	8991.10	6256.14	9260.83	6631.51	15892.34		0.36	0.36	109.45	32.84	32.84	32.84
STA. 207+00.00 LT TO STA. 211+26.00 LT	7388.05	4413.53	7609.69	4678.34	12288.03		0.28	0.28	84.63	25.39	25.39	25.39
STA. 211+26.00 LT TO STA. 217+00.00 LT	9338.77	6064.86	9618.93	6428.75	16047.69		0.37	0.37	110.52	33.16	33.16	33.16
STA. 217+00.00 LT TO STA. 222+00.00 LT	7836.24	7083.67	8071.33	7508.69	15580.03		0.36	0.36	107.30	32.19	32.19	32.19
STA. 222+00.00 LT TO STA. 223+95.41 LT	4831.37	4621.56	4976.31	4898.85	9875.16		0.23	0.23	68.01	20.40	20.40	20.40
STA. 223+95.41 LT TO STA. 227+00.00 LT	6163.75	4526.13	6348.66	4797.70	11146.36		0.26	0.26	76.77	23.03	23.03	23.03
STA. 227+00.00 LT TO STA. 232+00.00 LT	9848.18	2932.91	10143.62	3108.88	13252.51		0.30	0.30	91.27	27.38	27.38	27.38
STA. 232+00.00 LT TO STA. 237+00.00 LT	8059.80	4683.13	8301.60	4964.12	13265.72		0.30	0.30	91.36	27.41	27.41	27.41
STA. 237+00.00 LT TO STA. 242+00.00 LT	7004.85	4300.99	7215.00	4559.05	11774.05		0.27	0.27	81.09	24.33	24.33	24.33
STA. 242+00.00 LT TO STA. 247+00.00 LT	7155.85	4197.88	7370.52	4449.76	11820.28		0.27	0.27	81.41	24.42	24.42	24.42
STA. 247+00.00 LT TO STA. 250+66.64 LT	5539.61	2190.76	5705.80	2322.21	8028.01		0.18	0.18	55.29	16.59	16.59	16.59
STA. 250+66.64 LT TO STA. 257+00.00 LT	11118.60	4860.98	11452.16	5152.64	16604.80		0.38	0.38	114.36	34.31	34.31	34.31
STA. 258+76.69 LT	1261.85		TEMPORARY EASEMENT		1261.85		0.03	0.03	8.69	2.61	2.61	2.61
STA. 257+00.00 LT TO STA. 258+76.69 LT	1819.68	1759.84	1874.27	1865.43	3739.69		0.09	0.09	25.76	7.73	7.73	7.73
STA. 258+76.69 LT TO STA. 262+00.00 LT	4229.88	2933.05	4356.78	3109.03	7465.81		0.17	0.17	51.42	15.43	15.43	15.43
STA. 262+00.00 LT TO STA. 267+00.00 LT	8811.68	4693.37	9076.03	4974.98	14051.01		0.32	0.32	96.77	29.03	29.03	29.03
STA. 267+00.00 LT TO STA. 272+00.00 LT	11692.61	4799.63	12043.39	5087.61	17131.00		0.39	0.39	117.98	35.39	35.39	35.39
STA. 272+00.00 LT TO STA. 275+00.00 LT	12982.55	5012.78	13372.02	5313.54	18685.57		0.43	0.43	128.69	38.61	38.61	38.61
STA. 273+80.00 LT	15750.00		TEMPORARY EASEMENT		15750.00		0.36	0.36	108.47	32.54	32.54	32.54
STA. 275+00.00 LT TO STA. 277+11.80 LT	2323.72	2097.83	2393.43	2223.70	4617.13		0.11	0.11	31.80	9.54	9.54	9.54
STA. 277+11.80 LT TO STA. 280+00.00 LT	5577.36	3533.49	5744.69	3745.50	9490.19		0.22	0.22	65.36	19.61	19.61	19.61
TOTAL LEFT SIDE ONLY						0.33	7.65	7.98	2392.74	717.82	717.82	717.82
TOTAL LEFT & RIGHT SIDE						1.12	15.83	16.95	5084.64	1525.39	1525.39	1525.39

DATE = 4/15/2009
 FILE NAME = SCHEDULE
 PLOT SCALE = 1"=50'
 USER NAME = RUSBR

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES

DESIGNED BY: AMPH & KLM
 DATE: APRIL 2009

DRAWN BY: AMPH & KLM
 CHECKED BY: JLH & RAH