CONTRACT NO. 89477

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
358	86-00075-00-AS	WOODFORD	74	9
STA. _____		TO STA._____		
FED. ROAD DIST. NO. 4	ILLINOIS	FED. AID PROJECT		

TEMPORARY DITCH CHECK SCHEDULE (1 OF 4)

LOCATION	DISTANCE	SLOPE	AVG. SPACING	28000300	28000310
STATION TO STATION	FEET	%	FEET	TEMPORARY DITCH CHECKS	AGGREGATE DITCH CHECK
				EACH	EACH
RIGHT SIDE					
STA. 167+00.00 RT TO STA. 169+00.00 RT	200.00	1.25	100.00		
STA. 167+00.00 RT				1	
STA. 168+00.00 RT				1	
STA. 174+00.00 RT TO STA. 184+50.00 RT	1050.00	0.30	200.00		
STA. 176+00.00 RT				1	
STA. 178+00.00 RT				1	
STA. 180+00.00 RT				1	
STA. 182+00.00 RT				1	
STA. 184+00.00 RT				1	
STA. 184+50.00 RT TO STA. 188+00.00 RT	350.00	1.60	94.00		
STA. 185+44.00 RT				1	
STA. 186+38.00 RT				1	
STA. 187+32.00 RT				1	
STA. 188+00.00 RT				1	
STA. 188+00.00 RT TO STA. 199+00.00 RT	1100.00	0.60	200.00		
STA. 190+00.00 RT				1	
STA. 192+00.00 RT				1	
STA. 194+00.00 RT				1	
STA. 197+00.00 RT				1	
STA. 198+00.00 RT					1
STA. 200+00.00 RT TO STA. 203+00.00 RT	300.00	1.00	100.00		
STA. 200+50.00 RT					1
STA. 201+00.00 RT				1	
STA. 214+00.00 RT TO STA. 218+00.00 RT	400.00	2.00	75.00		
STA. 214+75.00 RT				1	
STA. 215+50.00 RT				1	
STA. 216+25.00 RT				1	
STA. 217+00.00 RT				1	
STA. 217+75.00 RT				1	
STA. 218+00.00 RT TO STA. 220+00.00 RT	200.00	1.50	100.00		
STA. 219+00.00 RT				1	
STA. 220+00.00 RT					1
STA. 220+00.00 RT TO STA. 222+00.00 RT	200.00	0.60	200.00		
STA. 222+00.00 RT					1
STA. 232+00.00 RT TO STA. 239+00.00 RT	700.00	1.00	150.00		
STA. 233+50.00 RT				1	
STA. 235+00.00 RT				1	
STA. 236+50.00 RT				1	
STA. 238+00.00 RT				1	
STA. 239+00.00 RT TO STA. 243+00.00 RT	400.00	1.70	88.00		
STA. 239+88.00 RT				1	
STA. 240+76.00 RT				1	
STA. 241+64.00 RT				1	
STA. 242+52.00 RT				1	
STA. 243+00.00 RT				1	
STA. 243+00.00 RT TO STA. 246+00.00 RT	300.00	2.40	63.00		
STA. 243+63.00 RT				1	
STA. 244+26.00 RT				1	
STA. 244+89.00 RT				1	
STA. 245+52.00 RT				1	
STA. 246+15.00 RT				1	
STA. 246+00.00 RT TO STA. 252+00.00 RT	600.00	0.30	200.00		
STA. 250+00.00 RT				1	
STA. 252+00.00 RT TO STA. 257+00.00 RT	500.00	1.50	100.00		
STA. 253+00.00 RT				1	
STA. 254+00.00 RT				1	
STA. 255+00.00 RT				1	
STA. 256+00.00 RT				1	
STA. 257+00.00 RT				1	
			SUBTOTAL 1	**42**	**4**

TEMPORARY DITCH CHECK SCHEDULE (2 OF 4)

LOCATION	DISTANCE	SLOPE	AVG. SPACING	28000300	28000310
STATION TO STATION	FEET	%	FEET	TEMPORARY DITCH CHECKS	AGGREGATE DITCH CHECK
				EACH	EACH
RIGHT SIDE CONTINUED					
STA. 259+00.00 RT TO STA. 262+00.00 RT	300.00	3.00	50.00		
STA. 259+50.00 RT				1	
STA. 260+00.00 RT				1	
STA. 260+50.00 RT				1	
STA. 261+00.00 RT				1	
STA. 261+50.00 RT				1	
STA. 262+00.00 RT					1
STA. 262+00.00 RT TO STA. 264+00.00 RT	200.00	0.70	100.00		
STA. 263+00.00 RT				1	
STA. 264+00.00 RT				1	
STA. 264+00.00 RT TO STA. 267+00.00 RT	300.00	0.30	200.00		
STA. 266+00.00 RT				1	
STA. 267+00.00 RT TO STA. 269+00.00 RT	200.00	0.30	200.00		
STA. 269+00.00 RT				1	
STA. 269+00.00 RT TO STA. 273+00.00 RT	400.00	1.50	100.00		
STA. 270+00.00 RT				1	
STA. 271+00.00 RT				1	
STA. 272+00.00 RT				1	
STA. 272+90.00 RT				1	
STA. 274+00.00 RT TO STA. 277+00.00 RT	300.00	0.30	100.00		
STA. 275+00.00 RT					1
STA. 276+00.00 RT				1	
STA. 277+50.00 RT TO STA. 281+00.00 RT	350.00	0.30	100.00		
STA. 278+50.00 RT					1
STA. 279+50.00 RT				1	
LEFT SIDE					
STA. 167+00.00 LT TO STA. 169+00.00 RT	200.00	1.25	100.00		
STA. 167+00.00 LT				1	
STA. 168+00.00 LT				1	
STA. 169+00.00 LT				1	
STA. 170+00.00 LT TO STA. 174+00.00 RT	400.00	1.50	150.00		
STA. 171+50.00 LT				1	
STA. 173+00.00 LT				1	
STA. 174+00.00 LT TO STA. 176+00.00 LT	200.00	2.00	100.00		
STA. 175+00.00 LT				1	
STA. 176+00.00 LT				1	
STA. 176+00.00 LT TO STA. 185+00.00 LT	900.00	0.20	200.00		
STA. 180+00.00 LT				1	
STA. 185+00.00 LT TO STA. 188+00.00 LT	300.00	2.00	75.00		
STA. 186+50.00 LT				1	
STA. 187+25.00 LT				1	
STA. 188+00.00 LT				1	
STA. 188+00.00 LT TO STA. 198+00.00 LT	1000.00	0.70	200.00		
STA. 190+00.00 LT				1	
STA. 192+00.00 LT				1	
STA. 194+00.00 LT				1	
STA. 196+00.00 LT				1	
STA. 198+00.00 LT TO STA. 199+00.00 LT	100.00	3.50	43.00		
STA. 198+50.00 LT					1
STA. 200+00.00 LT TO STA. 203+00.00 LT	300.00	1.00	150.00		
STA. 200+50.00 LT					1
STA. 201+50.00 LT				1	
STA. 203+00.00 LT TO STA. 208+00.00 LT	500.00	0.50	200.00		
STA. 205+00.00 LT				1	
STA. 207+00.00 LT				1	
STA. 208+00.00 LT TO STA. 212+00.00 LT	400.00	0.60	200.00		
STA. 209+00.00 LT				1	
STA. 210+00.00 LT				1	
			SUBTOTAL 2	**35**	**5**

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES

DESIGNED BY: AMPH & KLM
DRAWN BY: AMPH & KLM
DATE: APRIL 2009
CHECKED BY: JLH & RAH

PLOT DATE = $DATE$
FILE NAME = $FILEL$
PLOT SCALE = $SCALE$
USER NAME = $USER$