

F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
358	86-00075-00-AS	WOODFORD	74	10
STA. _____		TO STA. _____		
FED. ROAD DIST. NO. 4 ILLINOIS FED. AID PROJECT				

TEMPORARY DITCH CHECK SCHEDULE (3 OF 4)

LOCATION	DISTANCE	SLOPE	AVG. SPACING	28000300	28000310
STATION TO STATION	FEET	%	FEET	TEMPORARY DITCH CHECKS EACH	AGGREGATE DITCH CHECK EACH
LEFT SIDE CONTINUED					
STA. 212+00.00 LT TO STA. 216+00.00 LT	400.00	1.50	100.00		
STA. 213+00.00 LT				1	
STA. 214+00.00 LT				1	
STA. 215+00.00 LT				1	
STA. 216+00.00 LT				1	
STA. 216+00.00 LT TO STA. 222+00.00 LT	600.00	0.70	200.00		
STA. 218+00.00 LT				1	
STA. 220+00.00 LT				1	
STA. 222+00.00 LT					1
STA. 226+00.00 LT TO STA. 230+00.00 LT	400.00	0.50	200.00		
STA. 228+00.00 LT				1	
STA. 230+00.00 LT				1	
STA. 230+00.00 LT TO STA. 232+00.00 LT	200.00	1.50	100.00		
STA. 231+00.00 LT				1	
STA. 232+00.00 LT TO STA. 234+00.00 LT	200.00	2.00	75.00		
STA. 232+75.00 LT				1	
STA. 233+50.00 LT				1	
STA. 234+00.00 LT TO STA. 239+00.00 LT	500.00	0.70	200.00		
STA. 235+00.00 LT					
STA. 237+00.00 LT					
STA. 239+00.00 LT TO STA. 243+00.00 LT	400.00	1.00	150.00		
STA. 240+50.00 LT				1	
STA. 242+00.00 LT				1	
STA. 243+00.00 LT TO STA. 247+00.00 LT	400.00	1.50	100.00		
STA. 243+00.00 LT				1	
STA. 244+00.00 LT				1	
STA. 245+00.00 LT				1	
STA. 246+00.00 LT				1	
STA. 247+00.00 LT				1	
STA. 247+00.00 LT TO STA. 251+00.00 LT	400.00	0.30	200.00		
STA. 249+00.00 LT				1	
STA. 251+50.00 LT					1
STA. 252+00.00 LT TO STA. 259+00.00 LT	700.00	1.50	100.00		
STA. 252+50.00 LT					1
STA. 253+50.00 LT				1	
STA. 254+50.00 LT				1	
STA. 255+50.00 LT				1	
STA. 256+50.00 LT				1	
STA. 257+50.00 LT				1	
STA. 259+00.00 LT TO STA. 260+00.00 LT	100.00	0.60	100.00		
STA. 260+00.00 LT					
STA. 260+00.00 LT TO STA. 262+00.00 LT	200.00	3.00	50.00		
STA. 260+50.00 LT				1	
STA. 261+00.00 LT				1	
STA. 261+50.00 LT				1	
STA. 262+00.00 LT					1
STA. 262+00.00 LT TO STA. 264+00.00 LT	200.00	1.60	94.00		
STA. 262+94.00 LT				1	
STA. 263+88.00 LT				1	
STA. 264+00.00 LT TO STA. 267+00.00 LT	300.00	0.30	200.00		
STA. 266+00.00 LT				1	
STA. 267+00.00 LT TO STA. 269+00.00 LT	200.00	0.30	200.00		
STA. 269+00.00 LT				1	
STA. 269+00.00 LT TO STA. 273+00.00 LT	400.00	1.50	100.00		
STA. 270+00.00 LT				1	
STA. 271+00.00 LT				1	
STA. 272+00.00 LT				1	
STA. 273+00.00 LT				1	
STA. 278+00.00 LT TO STA. 281+00.00 LT	300.00	1.00	150.00		
STA. 279+50.00 LT				1	
SUBTOTAL 3				36	4

TEMPORARY DITCH CHECK SCHEDULE (4 OF 4)

LOCATION	DISTANCE	SLOPE	AVG. SPACING	28000300	28000310
STATION TO STATION	FEET	%	FEET	TEMPORARY DITCH CHECKS EACH	AGGREGATE DITCH CHECK EACH
ALONG 1700 N					
STA. 1702+00.00 RT				1	
STA. 1703+00.00 LT				1	
STA. 1703+00.00 RT				1	
ALONG 1800 N					
STA. 1802+00.00 LT				1	
STA. 1802+00.00 RT				1	
STA. 1804+00.00 LT				1	
STA. 1804+00.00 RT				1	
SUBTOTAL 4				7	0
SUBTOTAL 1				42	4
SUBTOTAL 2				35	5
SUBTOTAL 3				36	4
SUBTOTAL 4				7	0
GRAND TOTAL				120	13

AGGREGATE SURFACE COURSE, TYPE B

LOCATION		ALIGNMENT	FOR INFO ONLY				WEIGHT TON
STATION	LT/RT		AREA		THICKNESS	VOLUME	
			SQ.FT.	SQ.YD.	INCH	CU.YD.	
STA. 169+33.82	RT	COUNTY HIGHWAY #1	1217.74	135.30	6	22.55	46.23
STA. 174+05.50	LT	COUNTY HIGHWAY #1	786.60	87.40	6	14.57	29.86
STA. 177+95.00	LT	COUNTY HIGHWAY #1	1141.70	126.86	6	21.14	43.34
STA. 182+62.00	LT	COUNTY HIGHWAY #1	1130.63	125.63	6	20.94	42.92
STA. 184+49.50	LT	COUNTY HIGHWAY #1	872.37	96.93	6	16.15	33.12
STA. 196+00.00	RT	COUNTY HIGHWAY #1	1173.93	130.44	6	21.74	44.57
STA. 197+24.54	LT	COUNTY HIGHWAY #1	2109.49	234.39	6	39.06	80.08
STA. 211+26.00	LT	COUNTY HIGHWAY #1	1233.32	137.04	6	22.84	46.82
STA. 211+50.40	RT	COUNTY HIGHWAY #1	800.68	88.96	6	14.83	30.40
STA. 212+76.68	RT	COUNTY HIGHWAY #1	800.68	88.96	6	14.83	30.40
STA. 248+00.00	RT	COUNTY HIGHWAY #1	1477.00	164.11	6	27.35	56.07
STA. 250+66.64	LT	COUNTY HIGHWAY #1	994.53	110.50	6	18.42	37.76
STA. 251+25.80	RT	COUNTY HIGHWAY #1	1020.68	113.41	6	18.90	38.75
STA. 258+76.69	LT	COUNTY HIGHWAY #1	1441.16	160.13	6	26.69	54.71
STA. 267+00.00	LT	COUNTY HIGHWAY #1	1070.15	118.91	6	19.82	40.63
STA. 267+00.00	RT	COUNTY HIGHWAY #1	1350.69	150.08	6	25.01	51.28
STA. 1901+00.00	RT	TR 1900 N	730.00	81.11	6	13.52	27.71
STA. 1901+00.00	LT	TR 1900 N	763.00	84.78	6	14.13	28.97
STA. 1903+50.00	RT	TR 1900 N	416.00	46.22	6	7.70	15.79
STA. 1903+50.00	LT	TR 1900 N	478.00	53.11	6	8.85	18.15
TOTAL						797.54	

PLOT DATE = 04/07/09
 FILE NAME = 040709.DWG
 PLOT SCALE = 1/8"=1'-0"
 USER NAME = MUSENA

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SCHEDULE OF QUANTITIES

DESIGNED BY: AMPH & KLM
 DATE: APRIL 2009

DRAWN BY: AMPH & KLM
 CHECKED BY: JLH & RAH