

SUMMARY OF QUANTITIES

SUMMARY OF QUANTITIES		SAFETY CODE		2A	1F
CODE NO.	ITEM	CONSTRUCTION CODE		J000	Y031
		UNIT	TOTAL QUANTITY	ROADWAY	TRAFFIC SIGNALS
20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	22	22	
20100210	TREE REMOVAL (OVER 15 UNITS DIAMETER)	UNIT	16	16	
20200100	EARTH EXCAVATION	CU YD	638	638	
* 20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	250	250	
20400800	FURNISHED EXCAVATION	CU YD	820	820	
* 21000300	GRANULAR EMBANKMENT, SPECIAL	TON	510	510	
21001000	GEOTECHNICAL FABRIC FOR GROUND STABILIZATION	SQ YD	750	750	
* 21101505	TOPSOIL EXCAVATION AND PLACEMENT	CU YD	443	443	
* 21101625	TOPSOIL FURNISH AND PLACE, 6"	SQ YD	114	114	
21301072	EXPLORATION TRENCH 72" DEPTH	FOOT	100	100	
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	81	81	
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	81	81	
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	81	81	
* 25000900	SEEDING, CLASS 1 (SPECIAL)	ACRE	0.9	0.9	
25200100	SODDING	SQ YD	129	129	
* 25200200	SUPPLEMENTAL WATERING	UNIT	43	43	
28000300	TEMPORARY DITCH CHECKS	EACH	1	1	
28000400	PERIMETER EROSION BARRIER	FOOT	1,112	1,112	
28000500	INLET AND PIPE PROTECTION	EACH	5	5	
28000510	INLET FILTERS	EACH	12	12	
28100105	STONE RIPRAP, CLASS A3	SQ YD	16	16	
35101100	AGGREGATE BASE COURSE, TYPE A 12"	SQ YD	2,494	2,494	
40200800	AGGREGATE SURFACE COURSE, TYPE B	TON	4	4	
40201000	AGGREGATE FOR TEMPORARY ACCESS	TON	17	17	
40600990	TEMPORARY RAMP	SQ YD	4	4	
40603085	HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N70	TON	259	259	
* 42000301	PORTLAND CEMENT CONCRETE PAVEMENT 8" (JOINTED)	SQ YD	1,954	1,954	
42001300	PROTECTIVE COAT	SQ YD	2,328	2,328	
42300200	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 6 INCH	SQ YD	68	68	
42300400	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 8 INCH	SQ YD	76	76	
42400300	PORTLAND CEMENT CONCRETE SIDEWALK 6 INCH	SQ FT	8,123	8,123	
42400800	DETECTABLE WARNINGS	SQ FT	100	100	
44000100	PAVEMENT REMOVAL	SQ YD	543	543	
44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	276	276	

*SEE SPECIAL PROVISIONS

FILE NAME = p:\C0010461\Plans\sheets\summary.dgn PLOT DATE = 2/9/2009 1:17:24 PM	DESIGNED - R.L.H.	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SUMMARY OF QUANTITIES	F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
	DRAWN - J.L.B.	REVISED -			7170	08-00277-00-PV	CHAMPAIGN	44	4
	CHECKED - J.T.P.	REVISED -			CONTRACT NO. 91397				
	DATE - 2-09	REVISED -			SCALE : NONE	SHEET NO. 4 OF 44 SHEETS	STA. TO STA.	FED. ROAD DIST. NO.	ILLINOIS FED. AID PROJECT HD-5181 (044)