

SUMMARY OF QUANTITIES					
SP	CODE NO.	ITEM DESCRIPTION	UNIT	TOTAL QUANTITY	CONSTRUCTION TYPE CODE
	20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	381	I000-2A X023-2A
	20100210	TREE REMOVAL (OVER 15 UNITS DIAMETER)	UNIT	396	396
	20200100	EARTH EXCAVATION	CU YD	4,482	4,482
	20300100	CHANNEL EXCAVATION	CU YD	365	365
	20400800	FURNISHED EXCAVATION	CU YD	7,105	7,105
	20700110	POROUS GRANULAR EMBANKMENT	TON	1,186	1,186
	20800150	TRENCH BACKFILL	CU YD	411	411
	21400100	GRADING AND SHAPING DITCHES	FOOT	200	200
	25000200	SEEDING, CLASS 2	ACRE	0.9	0.9
	25000400	NITROGEN FERTILIZER NUTRIENT	POUND	81	81
	25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	81	81
	25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	81	81
	25000700	AGRICULTURAL GROUND LIMESTONE	TON	1.8	1.8
	25100115	MULCH, METHOD 2	ACRE	0.9	0.9
	25100630	EROSION CONTROL BLANKET	SQ YD	4,840	4,840
	28000300	TEMPORARY DITCH CHECKS	EACH	15	15
	28000400	PERIMETER EROSION BARRIER	FOOT	1,075	1,075
	28000500	INLET AND PIPE PROTECTION	EACH	3	3
	28100107	STONE RIPRAP, CLASS A4	SQ YD	796	796
	28200200	FILTER FABRIC	SQ YD	796	796
	31101810	SUB-BASE GRANULAR MATERIAL, TYPE B 12"	SQ YD	9,150	9,150
	40200500	AGGREGATE SURFACE COURSE, TYPE A 6"	SQ YD	95	95
	40201000	AGGREGATE FOR TEMPORARY ACCESS	TON	250	250
	40300100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	4,600	4,600
	40600300	AGGREGATE (PRIME COAT)	TON	17	17
	40701851	HOT-MIX ASPHALT PAVEMENT (FULL-DEPTH), 8 1/2"	SQ YD	8,250	8,250
	40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	80	80
	42400100	PORTLAND CEMENT CONCRETE SIDEWALK 4 INCH	SQ FT	15,586	15,586
	42400800	DETECTABLE WARNINGS	SQ FT	65	65
	44000100	PAVEMENT REMOVAL	SQ YD	586	586
	44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	361	361
	44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	352	352
	44000600	SIDEWALK REMOVAL	SQ FT	155	155
	44201717	CLASS D PATCHES, TYPE II, 6 INCH	SQ YD	170	170
	50100200	REMOVAL OF EXISTING STRUCTURES	L SUM	1	1
	50105220	PIPE CULVERT REMOVAL	FOOT	379	379
	50200100	STRUCTURE EXCAVATION	CU YD	920	920
	50300225	CONCRETE STRUCTURES	CU YD	188	188
	50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	20,625	20,625
	50900805	PEDESTRIAN RAILING	FOOT	246	246
	51201600	FURNISHING STEEL PILES HP 12X53	FOOT	635	635
	51202305	DRIVING PILES	FOOT	635	635

*SP = SEE SPECIAL PROVISION
 Δ = SPECIALTY ITEMS

SUMMARY OF QUANTITIES					
SP	CODE NO.	ITEM DESCRIPTION	UNIT	TOTAL QUANTITY	CONSTRUCTION TYPE CODE
	51203600	TEST PILE STEEL HP 12X53	EACH	1	I000-2A X023-2A
	51500100	NAME PLATES	EACH	1	1
	54200220	PIPE CULVERTS, CLASS D, TYPE 1 15" (CSCP)	FOOT	65	65
	54213660	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 15"	EACH	1	1
	54213663	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 18"	EACH	1	1
	54213870	STEEL END SECTIONS 15"	EACH	4	4
	550A0050	STORM SEWERS, CLASS A, TYPE 1 12"	FOOT	306	306
	550A0070	STORM SEWERS, CLASS A, TYPE 1 15"	FOOT	155	155
	550A0340	STORM SEWERS, CLASS A, TYPE 2 12"	FOOT	715	715
	550A0360	STORM SEWERS, CLASS A, TYPE 2 15"	FOOT	390	390
	550A0380	STORM SEWERS, CLASS A, TYPE 2 18"	FOOT	46	46
	60224700	RESTRICTED DEPTH MANHOLES, 4'-DIAMETER, TYPE 3 FRAME AND GRATE	EACH	6	6
	60234200	INLETS, TYPE A, TYPE 1 FRAME, OPEN LID	EACH	1	1
	60235700	INLETS, TYPE A, TYPE 3 FRAME AND GRATE	EACH	6	6
	60240220	INLETS, TYPE B, TYPE 3 FRAME AND GRATE	EACH	6	6
	60604400	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.18	FOOT	3,235	3,235
	66600105	FURNISHING AND ERECTING RIGHT-OF-WAY MARKERS	EACH	9	9
	67100100	MOBILIZATION	L SUM	1	0.5 0.5
	70103700	TRAFFIC CONTROL COMPLETE	L SUM	1	0.5 0.5
	70300230	TEMPORARY PAVEMENT MARKING - LINE 5'	FOOT	6,825	6,825
	70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	230	230
	70300250	TEMPORARY PAVEMENT MARKING - LINE 8"	FOOT	360	360
	70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	457	457
	70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	38	38
	72000100	SIGN PANEL - TYPE 1	SQ FT	102	102
	72800100	TELESCOPING STEEL SIGN SUPPORT	FOOT	375	375
	78000300	THERMOPLASTIC PAVEMENT MARKING - LINE 5"	FOOT	6,825	6,825
	78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	196	196
	78000500	THERMOPLASTIC PAVEMENT MARKING - LINE 8"	FOOT	360	360
	78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	457	457
	78004200	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - INLAID - LETTERS AND SYMBOLS	SQ FT	260	260
	78004280	PREFORMED PLASTIC PAVEMENT MARKING, TYPE B - INLAID - LINE 24"	FOOT	38	38
	X0322033	STORM SEWER (WATER MAIN REQUIREMENTS) 12 INCH	FOOT	323	323
	X0322034	STORM SEWER (WATER MAIN REQUIREMENTS) 15 INCH	FOOT	38	38
	X0322035	STORM SEWER (WATER MAIN REQUIREMENTS) 18 INCH	FOOT	38	38
	X0323330	PRECAST CONCRETE SUBSTRUCTURE	L SUM	1	1
	X0325574	THREE-SIDED PRECAST CONCRETE STRUCTURES, 32'X9'	FOOT	68	68
	XX006806	HOT-MIX ASPHALT DRIVEWAY PAVEMENT	SQ YD	336	336
	Z0013798	CONSTRUCTION LAYOUT	L SUM	1	0.5 0.5

FILE NAME = ...\\0702502\draw\sheet\0quant.dgn

USER NAME = OpenH&B Springfield
 PLOT SCALE = 6.0000 ' / IN.
 PLOT DATE = 10/9/2008

DESIGNED - BMB
 DRAWN - GLD
 CHECKED - JMM
 DATE - 08/2008

REVISED -
 REVISED -
 REVISED -
 REVISED -

**MEADOWBROOK ROAD
 CITY OF SPRINGFIELD
 SPRINGFIELD, ILLINOIS**

SUMMARY OF QUANTITIES

SCALE: N/A SHEET NO. 3 OF 33 SHEETS STA. N/A TO STA. N/A