

| SUMMARY OF QUANTITIES | | | |
|-----------------------|----------|--|----------------|
| SP | CODE NO. | ITEM DESCRIPTION | TOTAL QUANTITY |
| * | 20200100 | EARTH EXCAVATION | 170 |
| | 20700220 | POROUS GRANULAR EMBANKMENT | 53 |
| | 20800150 | TRENCH BACKFILL | 87 |
| * | 25200700 | SODDING, SPECIAL | 136 |
| | 28100107 | STONE RIPRAP, CLASS A4 | 513 |
| | 28200200 | FILTER FABRIC | 513 |
| | 31101000 | SUB-BASE GRANULAR MATERIAL, TYPE B | 373 |
| | 42001300 | PROTECTIVE COAT | 464 |
| | 42100100 | CONTINUOUSLY REINFORCED PORTLAND CEMENT CONCRETE PAVMENT 8" | 464 |
| | 42100700 | PAVEMENT REINFORCEMENT 8" | 464 |
| | 42300400 | PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 8 INCH | 43 |
| * | 42400100 | PORTLAND CEMENT CONCRETE SIDEWALK 4 INCH | 1,638 |
| * | 44000100 | PAVEMENT REMOVAL | 937 |
| | 44000500 | COMBINATION CURB AND GUTTER REMOVAL | 297 |
| | 44000600 | SIDEWALK REMOVAL | 1,437 |
| * | 50100200 | REMOVAL OF EXISTING STRUCTURES | 1 |
| | 50200100 | STRUCTURE EXCAVATION | 118 |
| | 50300100 | FLOOR DRAINS | 16 |
| | 50300225 | CONCRETE STRUCTURES | 39.6 |
| | 50300255 | CONCRETE SUPERSTRUCTURE | 700.8 |
| | 50300260 | BRIDGE DECK GROOVING | 1,078 |
| * | 50300300 | PROTECTIVE COAT | 1,413 |
| * | 50800205 | REINFORCEMENT BARS, EPOXY COATED | 167,090 |
| | 50800515 | BAR SPLICERS | 24 |
| Δ | 50900105 | ALUMINUM RAILING, TYPE L | 97 |
| Δ | 50901720 | BICYCLE RAILING | 98 |
| Δ | 50901750 | PARAPET RAILING | 98 |
| | 51500100 | NAME PLATES | 1 |
| | 54248510 | CONCRETE COLLAR | 2 |
| | 550A0050 | STORM SEWERS, CLASS A, TYPE 1 12" | 144 |
| | 55100500 | STORM SEWER REMOVAL 12" | 178 |
| | 59000200 | EPOXY CRACK INJECTION | 13 |
| * | 60224600 | RESTRICTED DEPTH MANHOLES, 4'-DIAMETER, TYPE 1 FRAME, CLOSED LID | 1 |
| | 60240215 | INLETS, TYPE B, TYPE 1 FRAME, CLOSED LID | 1 |
| | 60255500 | MANHOLES TO BE ADJUSTED | 1 |
| | 60257900 | MANHOLES TO BE RECONSTRUCTED | 1 |

| SUMMARY OF QUANTITIES | | | |
|-----------------------|----------|---|----------------|
| SP | CODE NO. | ITEM DESCRIPTION | TOTAL QUANTITY |
| | 60500060 | REMOVING INLETS | 8 |
| | 60603800 | COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.12 | 29 |
| * | 60605000 | COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24 | 151 |
| | 66400105 | CHAIN LINK FENCE, 4' | 54 |
| | 67100100 | MOBILIZATION | 1 |
| * | 70103700 | TRAFFIC CONTROL COMPLETE | 1 |
| | 70300630 | TEMPORARY PAINT PAVEMENT MARKING LINE 5" | 5,985 |
| | 70300645 | TEMPORARY PAINT PAVEMENT MARKING LINE 12" | 873 |
| | 70400100 | TEMPORARY CONCRETE BARRIER | 237.5 |
| | 70400200 | RELOCATE TEMPORARY CONCRETE BARRIER | 237.5 |
| * Δ | 78005100 | EPOXY PAVEMENT MARKING - LETTERS AND SYMBOLS | 63 |
| * Δ | 78005120 | EPOXY PAVEMENT MARKING - LINE 5" | 1,325 |
| * Δ | 78005130 | EPOXY PAVMENT MARKING - LINE 6" | 125 |
| * Δ | 78005180 | EPOXY PAVEMENT MARKING - LINE 24" | 48 |
| | 78100200 | TEMPORARY RAISED REFLECTIVE PAVEMENT MARKER | 13 |
| Δ | 81012400 | CONDUIT IN TRENCH, 1 1/4" DIA., PVC | 190 |
| * Δ | 81021530 | CONDUIT, AUGERED 1 1/4" DIA., PVC | 35 |
| Δ | 81100400 | CONDUIT ATTACHED TO STRUCTURE, 1 1/4" DIA., GALVANIZED STEEL | 106 |
| Δ | 81900200 | TRENCH AND BACKFILL FOR ELECTRICAL WORK | 190 |
| Δ | 87301215 | ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 2C | 331 |
| Δ | 88600100 | DETECTOR LOOP, TYPE I | 94 |
| * | XX003437 | REMOVE AND REINSTALL EXISTING PRECAST REINFORCED CONCRETE FLARED END SECTIONS | 2 |
| * | XX007026 | FENCE REMOVAL AND REINSTALLATION | 20 |
| * | X0322752 | WORK ZONE PAVEMENT MARKING REMOVAL | 6,858 |
| * | X6020074 | INLETS, TYPE A, TYPE 3V FRAME AND GRATE | 4 |
| * | X6020075 | INLETS, TYPE B, TYPE 3V FRAME AND GRATE | 4 |
| * | X6060500 | CORRUGATED MEDIAN REMOVAL | 547 |
| * | Z0013798 | CONSTRUCTION LAYOUT | 1 |
| * | Z0022800 | FENCE REMOVAL | 54 |
| * | Z0024478 | FLEXIBLE DELINEATORS | 15 |
| * | Z0030260 | IMPACT ATTENUATORS, TEMPORARY (FULLY REDIRECTIVE, NARROW), TEST LEVEL 3 | 2 |
| * | Z0030330 | IMPACT ATTENUATORS, RELOCATE (FULLY REDIRECTIVE), TEST LEVEL 3 | 2 |

Δ SPECIALTY ITEMS
CONSTRUCTION TYPE CODE: X020-2A

FILE NAME =
...Draw\Sheets\sumquan01.dgn

USER NAME = Brad Downen
PLOT SCALE = 50,0000' / IN.
PLOT DATE = 3/10/2009

DESIGNED - MJO
DRAWN - GLD
CHECKED - BJD
DATE - 03/10/2009

REVISED -
REVISED -
REVISED -
REVISED -

CITY OF SPRINGFIELD
SPRINGFIELD, ILLINOIS

GENERAL NOTES & SUMMARY OF QUANTITIES
S.N. 084-6001 (E)
WASHINGTON STREET OVER JACKSONVILLE BRANCH

SCALE: SHEET NO. OF SHEETS STA. TO STA.

| | | | | |
|---|----------------|----------|--------------------|-----------|
| F.A.U. RTE. | SECTION* | COUNTY | TOTAL SHEETS | SHEET NO. |
| 7977 | 05-00443-00-BR | SANGAMON | 28 | 2 |
| FED. ROAD DIST. NO. 6 (ILLINOIS) FED. AID PROJECT | | | CONTRACT NO. 03485 | |

*CITY OF SPRINGFIELD