

ILLINOIS DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

LOCATION OF WORK				CONSTRUCTION TYPE CODE: SFTY				
CODE NO.	ITEM	UNIT	TOTAL QUANTITY	FIRST / SOUTH STREET SIDEWALK	ZIMMERMAN DRIVE SHARED PATH	ADA RAMP UPGRADE	BROOKSIDE GLEN SCHOOL SIDEWALK	VARIOUS SIDEWALK REPAIR
20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	1,163	176	987			
20100210	TREE REMOVAL (OVER 15 UNITS DIAMETER)	UNIT	1,092		1,092			
20101200	TREE ROOT PRUNING	EACH	75		50			25
20200100	EARTH EXCAVATION	CU YD	937	88	846		3	
20400800	FURNISHED EXCAVATION	CU YD	2,083		2,080		3	
20800150	TRENCH BACKFILL	CU YD	4		4			
* 21400100	GRADING AND SHAPING DITCHES	FOOT	50	50				
25000200	SEEDING, CLASS 2	ACRE	2.6	0.5	2		0.1	
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	229	45	180		4	
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	229	45	180		4	
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	229	45	180		4	
* 25100120	MULCH, METHOD 2	TON	6	1	4		0.2	
28000300	TEMPORARY DITCH CHECKS	EACH	16		16			
28000400	PERIMETER EROSION BARRIER	FOOT	200	200				
28000500	INLET AND PIPE PROTECTION	EACH	5	1	4			