

AREAS TO BE REPLACED	
LOCATION	SQ FT
500 FIRST STREET	60
545 FIRST STREET	80
545 FIRST STREET	80
555 FIRST STREET	80
315 QUAIL ROOST COURT	50
430 QUAIL ROOST COURT	60
440 QUAIL ROOST COURT	40
440 QUAIL ROOST COURT	40
455 QUAIL ROOST COURT	60
465 QUAIL ROOST COURT	40
475 QUAIL ROOST COURT	60
475 QUAIL ROOST COURT	60
305 PHEASANT RUN	40
300 PHEASANT RUN	20
300 PHEASANT RUN	80
410 PHEASANT RUN	20
425 PHEASANT RUN	60
425 PHEASANT RUN	20
425 PHEASANT RUN	40
435 PHEASANT RUN	60
435 PHEASANT RUN	60
435 PHEASANT RUN	40
440 PHEASANT RUN	40
440 PHEASANT RUN	40
460 PHEASANT RUN	40
460 PHEASANT RUN	20
515 PHEASANT RUN	100
515 PHEASANT RUN	60
495 PHEASANT RUN	48
701 PHEASANT RUN	80
300 RAMBLEWOOD LANE	20
465 RAMBLEWOOD LANE	80
495 RAMBLEWOOD LANE	60
<b>TOTAL SQ FT</b>	<b>1,738</b>

AREAS TO BE REPLACED	
LOCATION	SQ FT
700 FIRST STREET	60
700 FIRST STREET	50
305 TURTLE DOVE DRIVE	50
305 TURTLE DOVE DRIVE	24
410 TURTLE DOVE DRIVE	40
410 TURTLE DOVE DRIVE	40
456 TURTLE DOVE DRIVE	60
456 TURTLE DOVE DRIVE	50
456 TURTLE DOVE DRIVE	40
860 GROUSE COURT	40
700 MALLARD WAY	50
705 MALLARD WAY	50
705 MALLARD WAY	80
785 MALLARD WAY	60
230 RAMBLEWOOD LANE	80
241 RAMBLEWOOD LANE	60
201 RAMBLEWOOD LANE	20
114 RAMBLEWOOD LANE	60
760 LOST TREE DRIVE	24
790 LOST TREE DRIVE	20
701 TIMBER EDGE DRIVE	16
795 TIMBER EDGE DRIVE	16
981 GOOSENECK TRAIL	40
<b>TOTAL SQ FT</b>	<b>1,030</b>

SIDEWALK SCHEDULE	
LOCATION	AREA (SQ FT)
<b>FIRST STREET</b>	
SOUTH OF BROOKSIDE GLEN DRIVE	2,610
NORTH OF BROOKSIDE GLEN DRIVE	2,860
<b>SOUTH STREET</b>	3,022
<b>ZIMMERMAN DRIVE</b>	
WILLOW LANE	273
ELEMENTARY SCHOOL ENTRANCE	500
<b>SUNKIST / CORN SILK</b>	152
<b>LOST TREE / PRAIRIE PLACE</b>	128
<b>HARVEST COURT / PARKVIEW</b>	166
<b>FIRST STREET / PARKVIEW PASS</b>	134
<b>FIRST STREET / THRUSH COURT</b>	157
<b>RAMBLEWOOD / TIMBER EDGE</b>	87
<b>TOTALS</b>	<b>10,089</b>

EARTH EXCAVATION SCHEDULE				
LOCATION	20200100 EARTH EXCAVATION [CUT]	EARTH EXCAVATION ADJUSTED FOR SHRINKAGE (25%)	EMBANKMENT [FILL]	EARTHWORK BALANCE WASTE (+) OR SHORTAGE (-)
	(CU YD)	(CU YD)	(CU YD)	(CU YD)
1st & SOUTH STREETS	88.0	66.0	22.0	44.0
ZIMMERMAN DRIVE	846.0	634.5	2,758.0	-2,123.5
<b>TOTALS</b>	<b>934.0</b>	<b>700.5</b>	<b>2,780.0</b>	<b>-2,079.5</b>
<b>20400800 FURNISHED EXCAVATION (CU YD)</b>				<b>2,080</b>

FILE NAME = G:\S07009-01\oad\General\7009\Sched02.SHT	USER NAME = IE Consultants	DESIGNED -	REVISED -	<b>VILLAGE OF SHERMAN</b>	<b>SCHEDULE OF QUANTITIES</b>	F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.	
		DRAWN -	REVISED -					08-00014-00-SW	SANGAMON	47	6
		CHECKED -	REVISED -			SCALE:	SHEET NO. OF SHEETS STA. TO STA.	FED. ROAD DIST. NO.	ILLINOIS FED. AID PROJECT	CONTRACT NO. 93486	
		DATE -	REVISED -								