



CONCRETE GUTTER
DEPRESS GUTTER 4" @ RAMP
w/ 2' TRANSITION TO EXISTING,
8' TOTAL LENGTH EACH.

BILL OF MATERIALS

TOTAL PCC SIDEWALK 4"	= 87 SQ FT
TOTAL SIDEWALK REMOVAL	= 34 SQ FT
TOTAL CONCRETE GUTTER	= 16 FT
TOTAL GUTTER REMOVAL	= 16 FT
DETECTABLE WARNING	= 16 SQ FT

FILE NAME = G:\S07209-01\cadd\7209-01_Ent_Data\101.dwg	USER NAME = IE Consultants	DESIGNED -	REVISED -	VILLAGE OF SHERMAN	RAMP SIDEWALK DETAILS				F.A. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
	PLOT SCALE = 5.0000' / IN.	DRAWN -	REVISED -						08-00014-00-SW	SANGAMON	47	43	
	PLOT DATE = 2/12/2009	CHECKED -	REVISED -		SCALE: SHEET NO. OF SHEETS STA. TO STA.				CONTRACT NO. 93486				
		DATE -	REVISED -						FED. ROAD DIST. NO. [ILLINOIS] FED. AID PROJECT				