F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
9024	07-00187-02-RP	MADISON	111	3
FED. ROAD DIST. NO. _	ILLINOIS	FED. AID PROJECT		

CONTRACT NO. 97376

SUMMARY OF QUANTITIES

SUMMARY OF QUANTITIES

CODE NO.	ITEM DESCRIPTION	UNIT	TOTAL QUANTITY
20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	81
20100210	TREE REMOVAL (OVER 15 UNITS DIAMETER)	UNIT	158
20200100	EARTH EXCAVATION	CU YD	6175
20800150	TRENCH BACKFILL	CU YD	3610
21101615	TOPSOIL FURNISH AND PLACE, 4"	SQ YD	5706
25000100	SEEDING, CLASS 1	ACRE	1.2
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	108
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	108
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	108
25100120	MULCH, METHOD 2	TON	4.8
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	120
28000500	INLET AND PIPE PROTECTION	EACH	55
28100707	STONE DUMPED RIPRAP, CLASS A4	SQ YD	19
28200200	FILTER FABRIC	SQ YD	19
30200650	PROCESSING MODIFIED SOIL 12"	SQ YD	12217
30201500	LIME	TON	302
31100100	SUB-BASE GRANULAR MATERIAL, TYPE A	TON	2504
35100100	AGGREGATE BASE COURSE, TYPE A	TON	96
40200100	AGGREGATE SURFACE COURSE, TYPE A	TON	39
40201000	AGGREGATE FOR TEMPORARY ACCESS	TON	1000
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	2442
40603085	HOT-MIX ASPHALT BINDER COURSE, IL-19.0, N70	TON	2186
40603315	HOT-MIX ASPHALT SURFACE COURSE, MIX "C", N70	TON	1093
40800050	INCIDENTAL HOT-MIX ASPHALT SURFACING	TON	32
42001300	PROTECTIVE COAT	SQ YD	6963
42300200	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 6 INCH	SQ YD	2057
42300400	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 8 INCH	SQ YD	55
42400100	PORTLAND CEMENT CONCRETE SIDEWALK 4 INCH	SQ FT	24753
42400800	DETECTABLE WARNINGS	SQ FT	136
44000100	PAVEMENT REMOVAL	SQ YD	7911

SUMMARY OF QUANTITIES

CODE NO.	ITEM DESCRIPTION	UNIT	TOTAL QUANTITY
44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	1762
44000300	CURB REMOVAL	FOOT	110
44000600	SIDEWALK REMOVAL	SQ FT	2993
44201773	CLASS D PATCHES, TYPE I, 11 INCH	SQ YD	830
48101200	AGGREGATE SHOULDERS, TYPE B	TON	1
50105220	PIPE CULVERT REMOVAL	FOOT	657
542A0220	PIPE CULVERTS, CLASS A, TYPE 1 15"	FOOT	54
542C0217	PIPE CULVERTS, CLASS C, TYPE 1 12"	FOOT	56
54213681	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 36"	EACH	1
54248515	CONCRETE COLLAR	EACH	2
550B0030	STORM SEWERS, CLASS B, TYPE 1 8"	FOOT	2
550B0050	STORM SEWERS, CLASS B, TYPE 1 12"	FOOT	97
550B0070	STORM SEWERS, CLASS B, TYPE 1 15"	FOOT	140
550B0090	STORM SEWERS, CLASS B, TYPE 1 18"	FOOT	70
550B0120	STORM SEWERS, CLASS B, TYPE 1 24"	FOOT	38
550B0360	STORM SEWERS, CLASS B, TYPE 2 15"	FOOT	57
55019500	STORM SEWERS, TYPE 1, REINFORCED CONCRETE CULVERT, STORM DRAIN, AND SEWER PIPE, CLASS IV 12"	FOOT	178
55019600	STORM SEWERS, TYPE 1, REINFORCED CONCRETE CULVERT, STORM DRAIN, AND SEWER PIPE, CLASS IV 15"	FOOT	883
55019700	STORM SEWERS, TYPE 1, REINFORCED CONCRETE CULVERT, STORM DRAIN, AND SEWER PIPE, CLASS IV 18"	FOOT	151
55019900	STORM SEWERS, TYPE 1, REINFORCED CONCRETE CULVERT, STORM DRAIN, AND SEWER PIPE, CLASS IV 24"	FOOT	127
55020100	STORM SEWERS, TYPE 1, REINFORCED CONCRETE CULVERT, STORM DRAIN, AND SEWER PIPE, CLASS III 30"	FOOT	433
55021700	STORM SEWERS, TYPE 2, REINFORCED CONCRETE CULVERT, STORM DRAIN, AND SEWER PIPE, CLASS III 15"	FOOT	26
55021800	STORM SEWERS, TYPE 2, REINFORCED CONCRETE CULVERT, STORM DRAIN, AND SEWER PIPE, CLASS III 18"	FOOT	516

SUMMARY OF QUANTITIES

CODE NO.	ITEM DESCRIPTION	UNIT	TOTAL QUANTITY
55022000	STORM SEWERS, TYPE 2, REINFORCED CONCRETE CULVERT, STORM DRAIN, AND SEWER PIPE, CLASS III 24"	FOOT	629
55022200	STORM SEWERS, TYPE 2, REINFORCED CONCRETE CULVERT, STORM DRAIN, AND SEWER PIPE, CLASS III 30"	FOOT	1171
55022400	STORM SEWERS, TYPE 2, REINFORCED CONCRETE CULVERT, STORM DRAIN, AND SEWER PIPE, CLASS III 36"	FOOT	295
60219540	MANHOLES, TYPE A, 4'-DIAMETER, TYPE 24 FRAME AND GRATE	EACH	2
60221100	MANHOLES, TYPE A, 5'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	6
60222240	MANHOLES, TYPE A, 5'-DIAMETER, TYPE 24 FRAME AND GRATE	EACH	1
60224039	MANHOLES, TYPE A, 6'-DIAMETER, TYPE 24 FRAME AND GRATE	EACH	1
60235300	INLETS, TYPE A, TYPE 1 FRAME, CLOSED LID	EACH	1
60235700	INLETS, TYPE A, TYPE 3 FRAME AND GRATE	EACH	7
60240220	INLETS, TYPE B, TYPE 3 FRAME AND GRATE	EACH	2
60242900	INLETS, SPECIAL, TYPE 1	EACH	25
60243000	INLETS, SPECIAL, TYPE 2	EACH	5
60243100	INLETS, SPECIAL, TYPE 3	EACH	6
60243700	INLETS, SPECIAL, TYPE 4	EACH	2
60255500	MANHOLES TO BE ADJUSTED	EACH	2
60261540	INLETS TO BE ADJUSTED WITH NEW TYPE 24 FRAME AND GRATE	EACH	1
60500060	REMOVING INLETS	EACH	1
60605000	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24	FOOT	6303
66410400	CHAIN LINK FENCE TO BE REMOVED AND RE-ERECTED	FOOT	15
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	10
67100100	MOBILIZATION	L SUM	1
70103700	TRAFFIC CONTROL COMPLETE	L SUM	1
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	861
70300210	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	72
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	788

• SPECIALTY ITEMS

FINAL SURVEY	BY	DATE
SURVEYED		
PLOTTED		
NOTE BOOK TEMPLATE		
AREAS		
AREAS CHECKED		
NO.		

ORIGINAL SURVEY	BY	DATE
SURVEYED		
PLOTTED		
NOTE BOOK TEMPLATE		
AREAS		
AREAS CHECKED		
NO.		

Juneau Associates, Inc. P.C.
CONSULTING ENGINEERS AND LAND SURVEYORS
2100 State Street, P.O. Box 1325
Granite City, Illinois 62040
Phone:(618)877-1400/(618)452-5535
Fax:(618)452-5541
100 North Research Drive
Edwardsville, Illinois 62025
Phone: (618)659-0500/(618) 593-0800
Fax: (618)659-0941

REVISIONS

NO.	DATE	BY	REMARKS
DWG. NO.			

SUMMARY OF QUANTITIES
F.A.U. ROUTE 9024
MOCKINGBIRD LANE
GRANITE CITY, ILLINOIS
SECTION NO. 07-00187-02-RP

DSN. BY:	BFK	DATE:	04/03/09	SHEET	3
DWN. BY:	JDH	DATE:	04/03/09		
CHK'D:	BFK	DATE:	04/03/09		
JOB NO.	E050210	DGN. NAME:	SUMQTY	OF 111 SHTS	