


MANHOLE AND INLET SCHEDULE

BY _____ DATE _____
 SURVEYED _____
 PLOTTED _____
 NOTE BOOK TEMPLATE _____
 AREAS AS _____
 CHECKED _____
 NO. _____

BY _____ DATE _____
 SURVEYED _____
 PLOTTED _____
 NOTE BOOK TEMPLATE _____
 AREAS AS _____
 CHECKED _____
 NO. _____

STRUCTURE ID	LOCATION	INLET							MANHOLES					PRECAST FLARED END SECTION 36"
		TYPE A TY 1 F CL (EACH)	TYPE A TY 3 F & G (EACH)	TYPE B FST TY 3 F & G (EACH)	SPECIAL TYPE 1 3' X 3' (EACH)	SPECIAL TYPE 2 4' X 4' (EACH)	SPECIAL TYPE 3 5' X 5' (EACH)	SPECIAL TYPE 4 3'X3', AREA (EACH)	TYPE A FST, 4'-DIA TY 24 F&G (EACH)	TYPE A 5'-DIA TY 1 F&CL (EACH)	TYPE A FST, 5'-DIA TY 1 F&CL (EACH)	TYPE A FST, 5'-DIA TY 24 F&G (EACH)	TYPE A FST, 6'-DIA TY 24 F&G (EACH)	
	MOCKINGBIRD LANE													
D-27A	STA. 119+36.79 - 24.32' RT		1											
D-27	STA. 119+75.04 - 23.40' RT			1										
D-30	STA. 121+35.29 - 23.34' RT	1												
D-01	STA. 124+02.19 - 17.00' RT				1									
D-04	STA. 125+36.20 - 17.00' RT				1									
D-06	STA. 126+70.20 - 17.00' RT				1									
D-40	STA. 127+25.92 - 15.48' RT		1											
D-08	STA. 127+86.99 - 14.80' RT			1										
D-13	STA. 128+82.31 - 17.00' RT				1									
D-16	STA. 129+82.31 - 17.00' RT				1									
D-18	STA. 131+36.31 - 17.00' RT				1									
D-20	STA. 133+00.30 - 17.00' RT				1									
W-19	STA. 135+72.13 - 17.00' RT				1									
W-20	STA. 136+00.00 - 17.00' RT				1									
W-16	STA. 137+54.79 - 23.04' RT		1											
W-15	STA. 139+20.00 - 17.00' RT				1									
W-01	STA. 140+65.42 - 22.36' RT							1						
W-06	STA. 141+16.93 - 16.56' RT		1											
W-08	STA. 141+31.95 - 17.00' RT				1									
W-11	STA. 142+80.00 - 14.72' RT		1											
M-02	STA. 144+13.00 - 14.72' RT		1											
M-03	STA. 145+25.00 - 14.72' RT		1											
M-05	STA. 146+55.00 - 17.00' RT				1									
M-07	STA. 147+85.00 - 17.00' RT				1									
D-26	STA. 118+78.60 - 17.00' LT				1									
D-25	STA. 119+33.03 - 17.00' LT				1									
D-25A	STA. 119+33.03 - 26.80' LT													
D-24	STA. 120+18.90 - 18.00' LT							1						
D-28	STA. 121+50.00 - 17.50' LT							1						
D-02	STA. 124+02.22 - 17.50' LT							1						
D-03	STA. 125+36.20 - 17.50' LT							1						
D-05	STA. 126+70.20 - 17.50' LT							1						
D-07	STA. 127+95.00 - 18.00' LT													
D-10	STA. 128+82.31 - 18.00' LT								1					
D-15	STA. 129+82.31 - 18.00' LT								1					
D-17	STA. 131+36.31 - 18.00' LT								1					
D-29	STA. 132+14.98 - 16.00' LT												1	
X-01	STA. 10+77.47 - 00.00'										1			
X-02	STA. 10+00.00 - 00.00'													1
	SUBTOTAL 1	1	7	2	15	4	6	1	0	1	0	0	1	1

 Juneau Associates, Inc. P.C. CONSULTING ENGINEERS AND LAND SURVEYORS <small>200 State Street, P.O. Box 1325 Granite City, Illinois 62040 Phone: (618) 937-1400 / (618) 932-5510 Fax: (618) 932-5511</small>		QUANTITY SCHEDULES F.A.U. ROUTE 9024 MOCKINGBIRD LANE GRANITE CITY, ILLINOIS SECTION NO. 07-00187-02-RP											
<table border="1"> <tr> <th>NO.</th> <th>DATE</th> <th>BY</th> <th>REVISIONS</th> <th>REMARKS</th> </tr> <tr> <td> </td> <td> </td> <td> </td> <td> </td> <td> </td> </tr> </table>		NO.	DATE	BY	REVISIONS	REMARKS						SCALE: NOT TO SCALE	
NO.	DATE	BY	REVISIONS	REMARKS									
DSN. BY: BFK DWN. BY: JDH CHK'D: BFK		DATE: 04/03/09 DATE: 04/03/09 DATE: 04/03/09											
DWG. NO.		JOB NO. E050210 DGN. NAME: COMSCH OF 111 SHTS											