

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
9024	07-00187-02-RP	MADISON	111	14
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		
CONTRACT NO. 97376				

MANHOLE AND INLET SCHEDULE CONT.


STRUCTURE ID	LOCATION	INLET						MANHOLES					PRECAST FLARED END SECTION 36" (EACH)	
		TYPE A TY 1 F CL (EACH)	TYPE A TY 3 F & G (EACH)	TYPE B FST TY 3 F & G (EACH)	SPECIAL TYPE 1 3' X 3' (EACH)	SPECIAL TYPE 2 4' X 4' (EACH)	SPECIAL TYPE 3 5' X 5' (EACH)	SPECIAL TYPE 4 3'X3', AREA (EACH)	TYPE A FST, 4'-DIA TY 24 F&G (EACH)	TYPE A 5'-DIA TY 1 F&CL (EACH)	TYPE A FST, 5'-DIA TY 1 F&CL (EACH)	TYPE A FST, 5'-DIA TY 24 F&G (EACH)		TYPE A FST, 6'-DIA TY 24 F&G (EACH)
D-19	STA. 133+00.30 - 17.00' LT				1									
W-18	STA. 135+71.21 - 17.00' LT				1									
W-17	STA. 136+00.00 - 17.00' LT				1									
W-14	STA. 137+58.54 - 17.00' LT				1									
W-13	STA. 139+20.00 - 17.00' LT				1									
W-12	STA. 140+50.00 - 17.50' LT					1								
W-05	STA. 141+31.79 - 12.66' LT						1					1		
W-07	STA. 141+60.39 - 15.28' LT								1					
W-09	STA. 142+27.47 - 15.27' LT								1					
W-10	STA. 142+91.35 - 17.00' LT				1									
M-01	STA. 144+13.00 - 17.00' LT				1									
M-04	STA. 145+23.45 - 17.00' LT				1									
M-06	STA. 146+52.77 - 17.00' LT				1									
M-08	STA. 147+85.00 - 17.00' LT				1									
WHIPPOORWILL LANE														
J-04	STA. 10+65.33 - 05.49' RT										1			
J-06	STA. 11+46.80 - 05.34' RT										1			
J-01	STA. 14+65.33 - 04.76' RT										1			
J-02	STA. 18+65.33 - 05.03' RT									1				
J-03	STA. 22+26.63 - 05.28' RT									1				
J-07	STA. 11+46.76 - 15.98' LT							1						
SUBTOTAL 1		1	7	2	15	4	6	1	0	1	0	0	1	1
SUBTOTAL 2		0	0	0	10	1	0	1	2	2	3	1	0	0
TOTAL		1	7	2	25	5	6	2	2	3	3	1	1	1

PIPE CULVERT SCHEDULE

STRUCTURE ID	LOCATION	PIPE CULVERTS CMP, CLASS C, TYPE 1		PIPE CULVERTS CLASS A, TYPE 1	TRENCH BACKFILL
		12" (FOOT)	15" (FOOT)	15" (FOOT)	CU YD
MOCKINGBIRD LANE					
EX TO C-11	STA. 117+38.69 - 12.93' RT TO STA. 117+38.54 - 28.39' RT			16	1
EX TO C-13	STA. 117+42.98 - 13.09' RT TO STA. 117+42.83 - 28.39' RT			16	1
EX TO C-10	STA. 117+39.10 - 15.53' LT TO STA. 117+39.26 - 26.50' LT			11	1
EX TO C-12	STA. 117+43.25 - 15.49' LT TO STA. 117+43.35 - 26.80' LT			11	1
WHIPPOORWILL					
	STA. 10+88.46 - 14.55' RT TO STA. 10+88.48 - 13.57' LT		28		1
	STA. 15+68.24 - 15.42' LT TO STA. 15+69.50 - 12.21' RT		28		1
TOTAL			56	54	6

TRENCH BACKFILL SCHEDULE

LOCATION	TRENCH BACKFILL (CU YD)
MOCKINGBIRD LANE	
STORM SEWER	3573
PIPE CULVERT	6
PIPE CULVERT REMOVAL	31
TOTAL	3610



QUANTITY SCHEDULES
F.A.U. ROUTE 9024
MOCKINGBIRD LANE
GRANITE CITY, ILLINOIS
SECTION NO. 07-00187-02-RP

NO. DATE BY REVISIONS				REMARKS		SCALE: NOT TO SCALE	
						DSN. BY: BFK	DATE: 04/03/09
						DWN. BY: JDH	DATE: 04/03/09
						CHK'D: BFK	DATE: 04/03/09
DWG. NO.						JOB NO. E050210	DGN. NAME: MCOMSCH OF 111 SHTS

DATE	
BY	
FINAL SURVEYED SURVEY PLOTTED	
NOTE BOOK TEMPLATE AREAS CHECKED	
NO.	

DATE	
BY	
ORIGINAL SURVEYED SURVEY PLOTTED	
NOTE BOOK TEMPLATE AREAS CHECKED	
NO.	