F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
9024	07-00187-02-RP	MADISON	111	15
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

CONTRACT NO. 97376

STORM SEWER SCHEDULE

STRUCTURE ID	LOCATION	RCCP TYPE 1 CLASS IV (FOOT)				RCCP TYPE 1 CLASS III (FOOT)	RCCP TYPE 2 CLASS III (FOOT)					STORM SEWER CLASS B, TYPE 1, PVC (FOOT)					STORM SEWER CLASS B, TYPE 2, PVC (FOOT)	TRENCH BACKFILL
		12"	15"	18"	24"	30"	15"	18"	24"	30"	36"	8"	12"	15"	18"	24"	15"	(CU YD)
	MOCKINGBIRD LANE																	
D-26 TO D-25	STA. 118+78.60 - 17.00' LT TO STA. 119+33.03 - 17.00' LT	52																8
D-25 TO D-24	STA. 119+33.03 - 17.00' LT TO STA. 120+18.90 - 18.00' LT	83																22
D-25 TO D-25A	STA. 119+33.03 - 17.00' LT TO STA. 119+33.03 - 26.80' LT	7																
D-27A TO D-27	STA. 119+36.79 - 24.32' RT TO STA. 119+75.04 - 23.40' RT	36																5
D-27 TO D-24	STA. 119+75.04 - 23.40' RT TO STA. 120+18.90 - 18.00' LT												56					11
D-24 TO D-28	STA. 120+18.90 - 18.00' LT TO STA. 121+50.00 - 17.50' LT				127													66
D-28 TO D-30	STA. 121+50.00 - 17.50' LT TO STA. 121+35.29 - 23.34' RT												41					10
EX TO D-30	STA. 121+35.66 - 26.27' RT TO STA. 121+35.29 - 23.34' RT											2						
D-28 TO D-02	STA. 121+50.00 - 17.50' LT TO STA. 124+02.22 - 17.50' LT								248									237
D-01 TO D-02	STA. 124+02.19 - 17.00' RT TO STA. 124+02.22 - 17.50' LT		31															4
D-02 TO D-03	STA. 124+02.22 - 17.50' LT TO STA. 125+36.20 - 17.50' LT								130									118
D-04 TO D-03	STA. 125+36.20 - 17.00' RT TO STA. 125+36.20 - 17.50' LT		31															4
D-03 TO D-05	STA. 125+36.20 - 17.50' LT TO STA. 126+70.20 - 17.50' LT								130									111
D-06 TO D-05	STA. 126+70.20 - 17.00' RT TO STA. 126+70.20 - 17.50' LT		31															4
D-05 TO D-07	STA. 126+70.20 - 17.50' LT TO STA. 127+95.00 - 18.00' LT								121									98
D-40 TO D-08	STA. 127+25.92 - 15.48' RT TO STA. 127+86.99 - 14.80' RT													59				7
D-08 TO D-07	STA. 127+86.99 - 14.80' RT TO STA. 127+95.00 - 18.00' LT													30				4
D-07 TO D-10	STA. 127+95.00 - 18.00' LT TO STA. 128+82.31 - 18.00' LT									83								64
D-13 TO D-10	STA. 128+82.31 - 17.00' RT TO STA. 128+82.31 - 18.00' LT		31															4
D-10 TO D-15	STA. 128+82.31 - 18.00' LT TO STA. 129+82.31 - 18.00' LT									95								82
D-16 TO D-15	STA. 129+82.31 - 17.00' RT TO STA. 129+82.31 - 18.00' LT		31															4
D-15 TO D-17	STA. 129+82.31 - 18.00' LT TO STA. 131+36.31 - 18.00' LT									149								170
D-18 TO D-17	STA. 131+36.31 - 17.00' RT TO STA. 131+36.31 - 18.00' LT		31															4
D-17 TO D-29	STA. 131+36.31 - 18.00' LT TO STA. 132+14.98 - 16.00' LT									73								102
D-29 TO X-01	STA. 132+14.98 - 16.00' LT TO STA. 10+77.47 - 00.00' LT										228							
X-01 TO X-02	STA. 10+77.47 - 00.00' LT TO STA. 10+00.00 - 00.00' LT										67							
D-20 TO D-19	STA. 133+00.30 - 17.00' RT TO STA. 133+00.30 - 17.00' LT		31															4
D-19 TO D-29	STA. 133+00.30 - 17.00' LT TO STA. 132+14.98 - 16.00' LT		81															21
W-20 TO W-19	STA. 136+00.00 - 17.00' RT TO STA. 135+72.13 - 17.00' RT																26	20
W-19 TO W-18	STA. 135+72.13 - 17.00' RT TO STA. 135+71.21 - 17.00' LT																31	18
W-18 TO W-17	STA. 135+71.21 - 17.00' LT TO STA. 136+00.00 - 17.00' LT						26											21
W-17 TO W-14	STA. 136+00.00 - 17.00' LT TO STA. 137+58.54 - 17.00' LT							156										164
W-16 TO W-14	STA. 137+54.79 - 23.04' RT TO STA. 137+58.54 - 17.00' LT													38				11
W-14 TO W-13	STA. 137+58.54 - 17.00' LT TO STA. 139+20.00 - 17.00' LT							159										169
W-15 TO W-13	STA. 139+20.00 - 17.00' RT TO STA. 139+20.00 - 17.00' LT		31															8
W-13 TO W-12	STA. 139+20.00 - 17.00' LT TO STA. 140+50.00 - 17.50' LT			127														92
W-12 TO W-01	STA. 140+50.00 - 17.50' LT TO STA. 140+65.42 - 22.36' RT															38		6
W-05 TO W-01	STA. 141+31.79 - 12.66' LT TO STA. 140+65.42 - 22.36' RT														70			16
W-06 TO W-08	STA. 141+16.93 - 16.56' RT TO STA. 141+31.95 - 17.00' RT													13				
W-07 TO W-05	STA. 141+60.39 - 15.28' LT TO STA. 141+31.79 - 12.66' LT			24														5
W-08 TO W-05	STA. 141+31.95 - 17.00' RT TO STA. 141+31.79 - 12.66' LT		26															5
W-09 TO W-07	STA. 142+27.47 - 15.27' LT TO STA. 141+60.39 - 15.28' LT		63															14
W-10 TO W-09	STA. 142+91.35 - 17.00' LT TO STA. 142+27.47 - 15.27' LT		61															18
W-11 TO W-10	STA. 142+80.00 - 14.72' RT TO STA. 142+91.35 - 17.00' LT		31															6
M-02 TO M-01	STA. 144+13.00 - 14.72' RT TO STA. 144+13.00 - 17.00' LT		29															5
M-01 TO M-04	STA. 144+13.00 - 17.00' LT TO STA. 145+23.45 - 17.00' LT		108															38
M-03 TO M-04	STA. 145+25.00 - 14.72' RT TO STA. 145+23.45 - 17.00' LT		29															5
M-04 TO M-06	STA. 145+23.45 - 17.00' LT TO STA. 146+52.77 - 17.00' LT		127															93
M-05 TO M-06	STA. 146+55.00 - 17.00' RT TO STA. 146+52.77 - 17.00' LT		31															4
M-06 TO M-08	STA. 146+52.77 - 17.00' LT TO STA. 147+85.00 - 17.00' LT							129										136
M-07 TO M-08	STA. 147+85.00 - 17.00' RT TO STA. 147+85.00 - 17.00' LT		31															4
M-08 TO I-53	STA. 147+85.00 - 17.00' LT TO STA. 78+07.57 - 25.40' RT							72										93
	WHIPPOORWILL LANE																	
W-01 TO J-04	STA. 140+65.42 - 22.36' RT TO STA. 10+65.33 - 05.49' RT					42												13
J-04 TO J-06	STA. 10+65.33 - 05.49' RT TO STA. 11+46.80 - 05.34' RT					77												23
J-06 TO J-01	STA. 11+46.80 - 05.34' RT TO STA. 14+65.33 - 04.76' RT					314												261
J-06 TO J-07	STA. 11+46.80 - 05.34' RT TO STA. 11+46.76 - 15.98' LT		18															3
J-01 TO J-02	STA. 14+65.33 - 04.76' RT TO STA. 18+65.33 - 05.03' RT									395								540
J-02 TO J-03	STA. 18+65.33 - 05.03' RT TO STA. 22+26.63 - 05.28' RT									356								618
J-03 TO J-05	STA. 22+26.63 - 05.28' RT TO STA. 22+49.96 - 05.14' RT									20								0
	TOTAL	178	883	151	127	433	26	516	629	1171	295	2	97	140	70	38	57	3573

FINAL SURVEY	BY	DATE
SURVEYED		
PLOTTED		
TEMPLATE		
AREAS		
AREAS CHECKED		
NOTE BOOK NO.		

ORIGINAL SURVEY	BY	DATE
SURVEYED		
PLOTTED		
TEMPLATE		
AREAS		
AREAS CHECKED		
NOTE BOOK NO.		

Juneau Associates, Inc. P.C.
CONSULTING ENGINEERS AND LAND SURVEYORS
2100 State Street, P.O. Box 1325
Granite City, Illinois 62040
Phone:(618)877-1400/(618)452-5535
Fax:(618)452-0541
100 North Basswith Drive
Edwardsville, Illinois 62025
Phone: (618)659-0900/(618) 659-0800
Fax: (618)659-0941

REVISIONS			
NO.	DATE	BY	REMARKS
DWG. NO.			

QUANTITY SCHEDULES
F.A.U. ROUTE 9024
MOCKINGBIRD LANE
GRANITE CITY, ILLINOIS
SECTION NO. 07-00187-02-RP

SCALE: NOT TO SCALE				
DSN. BY:	BFK	DATE:	04/03/09	SHEET
DWN. BY:	JDH	DATE:	04/03/09	15
CHK'D:	BFK	DATE:	04/03/09	
JOB NO.	E050210	DGN. NAME:	MCOMSCH	OF 111 SHTS