F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
9024	07-00187-02-RP	MADISON	111	18
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

CONTRACT NO. 97376

SIDEWALK SCHEDULE

LOCATION	PCC SIDEWALK 4" (SQ FT)
MOCKINGBIRD LANE	
STA. 118+04.25-25.58' RT TO STA. 119+33.88-22.16' RT	736.6
STA. 119+77.52-22.16' RT TO STA. 120+27.61-21.58' RT	194.1
STA. 120+49.61-21.58' RT TO STA. 120+84.84-21.58' RT	127.7
STA. 121+02.84-21.58' RT TO STA. 122+00.20-21.58' RT	376.3
STA. 122+24.21-21.58' RT TO STA. 122+86.08-21.58' RT	234.0
STA. 123+06.08-21.58' RT TO STA. 123+66.87-21.58' RT	229.8
STA. 123+84.87-21.58' RT TO STA. 124+43.36-21.58' RT	215.0
STA. 124+67.36-21.58' RT TO STA. 124+94.40-21.58' RT	95.0
STA. 125+10.51-21.58' RT TO STA. 125+94.44-21.58' RT	316.5
STA. 126+12.44-21.58' RT TO STA. 126+87.41-21.58' RT	280.8
STA. 127+05.41-21.58' RT TO STA. 127+34.41-22.16' RT	109.7
STA. 127+77.90-22.16' RT TO STA. 128+05.47-21.58' RT	104.0
STA. 128+25.47-21.58' RT TO STA. 129+45.76-21.58' RT	461.3
STA. 129+59.82-21.58' RT TO STA. 129+92.41-21.58' RT	114.5
STA. 130+27.07-21.58' RT TO STA. 130+83.52-21.58' RT	212.5
STA. 130+95.52-21.58' RT TO STA. 131+61.21-21.58' RT	243.8
STA. 131+20.38-21.58' RT TO STA. 131+22.74-34.61' RT	30.7
STA. 131+73.22-21.58' RT TO STA. 132+34.79-21.58' RT	233.0
STA. 131+99.93-21.58' RT TO STA. 132+02.27-34.86' RT	31.0
STA. 132+46.79-21.58' RT TO STA. 133+14.77-21.58' RT	253.0
STA. 132+79.12-21.58' RT TO STA. 132+81.91-34.55' RT	36.1
STA. 133+33.77-21.58' RT TO STA. 133+86.93-21.58' RT	199.1
STA. 134+06.93-21.58' RT TO STA. 134+57.73-21.58' RT	190.0
STA. 134+77.73-21.58' RT TO STA. 135+40.77-21.58' RT	238.8
STA. 135+60.77-21.58' RT TO STA. 136+14.33-21.58' RT	189.5
STA. 136+36.33-21.58' RT TO STA. 137+63.84-53.93' RT	620.1
STA. 136+51.30-21.58' RT TO STA. 136+54.27-34.21' RT	37.3
STA. 137+04.32-21.58' RT TO STA. 137+06.85-34.36' RT	32.3
STA. 138+11.25-22.16' RT TO STA. 138+85.37-21.58' RT	287.3
STA. 138+53.88-21.58' RT TO STA. 138+56.67-34.31' RT	35.5
STA. 139+03.37-21.58' RT TO STA. 140+74.42-30.48' RT	683.6
STA. 139+22.98-21.58' RT TO STA. 139+25.87-33.97' RT	35.9
STA. 141+04.79-30.73' RT TO STA. 142+20.64-21.58' RT	465.8
STA. 142+38.64-21.58' RT TO STA. 142+91.91-21.58' RT	199.6
STA. 143+15.91-21.58' RT TO STA. 143+87.71-21.58' RT	273.7
STA. 144+03.71-21.58' RT TO STA. 144+67.45-21.58' RT	241.5
STA. 144+84.45-21.58' RT TO STA. 145+45.58-21.58' RT	230.0
STA. 145+66.58-21.58' RT TO STA. 146+78.90-21.58' RT	430.2
STA. 147+02.90-21.58' RT TO STA. 148+42.25-21.58' RT	545.1
STA. 118+04.25-25.58' LT TO STA. 118+38.35-25.58' LT	290.5
STA. 118+64.31-21.58' LT TO STA. 132+25.49-21.58' LT	7856.3
STA. 132+37.49-21.58' LT TO STA. 133+62.23-21.58' LT	704.8
STA. 133+74.23-21.58' LT TO STA. 134+46.18-21.58' LT	400.8
STA. 134+58.20-21.58' LT TO STA. 135+25.98-21.58' LT	377.6
STA. 135+49.98-21.58' LT TO STA. 136+33.49-21.58' LT	443.6
STA. 136+53.49-21.58' LT TO STA. 137+27.57-21.58' LT	414.5
STA. 137+45.57-21.58' LT TO STA. 138+14.45-21.58' LT	369.6
STA. 138+32.45-21.58' LT TO STA. 139+47.22-21.58' LT	645.6
STA. 139+64.23-21.58' LT TO STA. 139+95.58-21.58' LT	157.9
STA. 140+13.59-21.58' LT TO STA. 141+20.55-21.58' LT	589.2
STA. 141+37.55-21.58' LT TO STA. 141+71.73-22.08' LT	164.4
STA. 142+16.04-22.08' LT TO STA. 142+51.00-21.58' LT	169.0
STA. 142+75.00-21.58' LT TO STA. 143+29.54-21.58' LT	283.6
STA. 143+46.54-21.58' LT TO STA. 144+51.92-21.58' LT	588.5
STA. 144+69.92-21.58' LT TO STA. 145+36.48-21.58' LT	355.8
STA. 145+53.48-21.58' LT TO STA. 145+78.14-21.58' LT	118.0
STA. 145+96.14-21.58' LT TO STA. 146+65.80-21.58' LT	374.3
STA. 146+81.80-21.58' LT TO STA. 147+43.42-21.58' LT	339.8
STA. 147+67.43-21.58' LT TO STA. 148+59.78-30.08' LT	538.7
TOTAL	24753

ENTRANCE SCHEDULE

LOCATION	WIDTH (FT)	PCC DRIVEWAY PAVEMENT 6 IN (SQ YD)	PCC DRIVEWAY PAVEMENT 8 IN (SQ YD)	HOT-MIX ASPHALT DRIVEWAY PAVEMENT INCIDENTAL HOT-MIX ASPHALT SURFACE (TON)	HOT-MIX ASPHALT DRIVEWAY PAVEMENT TYPE A AGG BASE CSE (TON)	AGGREGATE PAVEMENT TYPE A AGG SURF CSE (TON)	"Y" DISTANCE (FT)
MOCKINGBIRD LANE							
PE @ 120+38.81 RT	22.0	87.3					28.1
PE @ 120+94.04 RT	18.0	32.2					8.2
PE @ 122+12.75 RT	24.0	59.5					14.9
PE @ 122+96.29 RT	20.0	51.3					15.3
PE @ 123+76.07 RT	18.0	52.5					18.3
PE @ 124+52.57 RT	24.0	45.9				5.1	13.1
PE @ 125+03.11 RT	16.0	29.7					8.5
PE @ 126+03.54 RT	18.0	40.3					12.2
PE @ 126+96.50 RT	18.0	56.5					20.3
PE @ 128+15.57 RT	20.0	91.7					33.5
PE @ 129+50.79 RT	14.0	27.8		1.9	5.8		20.3
PE @ 130+06.26 RT	12.0	24.9		1.2	3.5		17.6
PE @ 130+21.16 RT	19.0	49.7				6.6	25.8
PE @ 130+89.61 RT	12.0	37.8					19.5
PE @ 131+67.31 RT	12.0	52.6					30.5
PE @ 132+40.88 RT	12.0	24.1		4.2	12.7		37.0
PE @ 133+24.36 RT	19.0	35.8		10.4	31.7		53.0
PE @ 133+96.51 RT	20.0	80.0					28.2
PE @ 134+67.82 RT	20.0	37.2		1.0	3.1		13.0
PE @ 135+50.87 RT	20.0	37.1		1.0	3.2		13.1
PE @ 136+25.33 RT	22.0	40.3				9.0	19.6
PE @ 138+94.47 RT	18.0	40.9					12.5
PE @ 142+29.74 RT	18.0	42.7					13.4
PE @ 143+04.00 RT	24.0	66.6					17.5
PE @ 143+95.81 RT	16.0	29.6					8.5
PE @ 144+76.05 RT	17.0	31.2		0.8	2.6		12.5
PE @ 145+60.68 RT	21.0	37.6		1.0	3.0	2.3	15.1
PE @ 146+91.00 RT	24.0	42.3		3.6	10.9		20.4
CE @ 118+49.10 LT	22.0		54.7				7.8
PE @ 132+31.39 LT	12.0	22.3				1.4	11.2
PE @ 133+68.14 LT	12.0	22.2		1.3	3.9		16.9
PE @ 134+50.99 LT	12.0	50.3					29.2
PE @ 135+35.94 LT	24.0	71.0					17.3
PE @ 136+43.39 LT	20.0	38.6					9.9
PE @ 137+36.47 LT	18.0	32.1					8.4
PE @ 138+23.36 LT	18.0	40.6					12.6
PE @ 139+56.49 LT	17.0	30.2		5.2	15.6		32.8
PE @ 140+05.06 LT	18.0	35.1					9.9
PE @ 141+28.96 LT	17.0	14.7					35.3
PE @ 142+62.91 LT	24.0	131.2					33.4
PE @ 143+37.95 LT	17.0	37.7					12.2
PE @ 144+60.82 LT	18.0	34.5					9.6
PE @ 145+44.89 LT	17.0	41.5					14.2
PE @ 145+87.04 LT	18.0	50.5					17.6
PE @ 146+73.70 LT	16.0	34.2					11.3
PE @ 147+58.33 LT	24.0	85.1				14.5	33.0
TOTAL		2057	55	32	96	39	

FINAL SURVEY	BY	DATE
SURVEYED		
PLOTTED		
NOTE BOOK	TEMPLATE	
NO.	AREAS	
	AREAS CHECKED	

ORIGINAL SURVEY	BY	DATE
SURVEYED		
PLOTTED		
NOTE BOOK	TEMPLATE	
NO.	AREAS	
	AREAS CHECKED	

Juneau Associates, Inc. P.C.
CONSULTING ENGINEERS AND LAND SURVEYORS
2100 State Street, P.O. Box 1325
Granite City, Illinois 62040
Phone: (618)877-1450/(618)452-5535
Fax: (618)452-0341
100 North Bennett Drive
Edwardsville, Illinois 62025
Phone: (618)659-0900/(618) 659-0800
Fax: (618)659-0941

QUANTITY SCHEDULES
F.A.U. ROUTE 9024
MOCKINGBIRD LANE
GRANITE CITY, ILLINOIS
SECTION NO. 07-00187-02-RP

REVISIONS			
NO.	DATE	BY	REMARKS

SCALE: NOT TO SCALE

DSN. BY:	BFK	DATE:	04/03/09	SHEET
DWN. BY:	JDH	DATE:	04/03/09	18
CHK'D:	BFK	DATE:	04/03/09	
DWG. NO.	JOB NO. E050210	DGN. NAME: MCOMSCH		OF 111 SHTS