


REVISIONS

NUMBER	BY	DATE




INDEX TO SHEETS	
SHEET	TITLE
01	COVER SHEET
02	INDEX TO SHEETS AND SUMMARY OF QUANTITIES
03	SITE PLAN
04	SEQUENCE OF CONSTRUCTION
05	EXISTING CONDITIONS & REMOVALS
06	PROPOSED IMPROVEMENTS
07	TYPICAL SECTIONS
08	STAKING & GRADING PLAN
09	DRAINAGE PLAN
10	DRAINAGE DETAILS
11	MARKING PLAN & DETAILS
12	FENCING PLAN
13	FENCING DETAILS
14	EROSION CONTROL & EARTHWORK SUMMARY
15	EROSION CONTROL DETAILS
16	T-HANGAR CROSS SECTIONS STA. 9+83.97 TO STA. 13+00
17	ENTRANCE ROAD CROSS SECTIONS STA. 3+48 TO STA. 5+61.66

SUMMARY OF QUANTITIES

ITEM NO.	ITEM DESCRIPTION	UNIT	FEDERAL/STATE/ LOCAL	STATE/LOCAL	TOTAL PROJECT
AR150510	ENGINEER'S FIELD OFFICE	L.S.	1	0	1
AR152442	OFFSITE BORROW EXCAVATION	C.Y.	1740	310	2050
AR155540	BY-PRODUCT LIME	TON	80	0	80
AR155612	SOIL PROCESSING-12"	S.Y.	3250	0	3250
AR156510	SILT FENCE	L.F.	800	400	1200
AR156511	DITCH CHECK	EACH	0	4	4
AR162504	CLASS E FENCE 4'	L.F.	170	0	170
AR162604	CLASS E GATE-4'	EACH	1	0	1
AR162620	CLASS E GATE-20'	EACH	1	0	1
AR162900	REMOVE CLASS E FENCE	L.F.	245	0	245
AR162910	REMOVE CLASS E GATE	EACH	1	0	1
AR209510	CRUSHED AGGREGATE BASE COURSE	TON	1500	390	1890
AR401610	BITUMINOUS SURFACE COURSE	TON	770	190	960
AR602510	BITUMINOUS PRIME COAT	GAL.	1335	330	1665
AR603510	BITUMINOUS TACK COAT	GAL.	250	65	315
AR620510	PAVEMENT MARKING	S.F.	0	205	205
AR701512	12" RCP, CLASS IV	L.F.	0	55	55
AR751410	INLET	EACH	0	1	1
AR751940	ADJUST INLET	EACH	2	0	2
AR800223	RELOCATE SANITARY SEPTIC FIELD	L.S.	1	0	1
AR901510	SEEDING	ACRE	0.7	0.3	1
AR908510	MULCHING	ACRE	0.7	0.3	1
AR908520	EXCELSIOR BLANKET	S.Y.	2000	0	2000
AR910230	HANDICAP SIGN	EACH	0	1	1
AR910410	PARKING BLOCK	EACH	0	10	10

PINCKNEYVILLE-DUQUOIN AIRPORT
 PERRY COUNTY, ILLINOIS
 T-HANGAR SITE WORK
 INDEX TO SHEETS AND SUMMARY OF QUANTITIES



DESIGN BY: TJH/KLB
 DRAWN BY: CMT
 CHECKED BY: JEF
 APPROVED BY: JEF
 DATE: 4/17/2009
 JOB No: 07062-03-00
 IL PROJECT NO. PJY-3373
 A.I.P. PROJECT NO. 3-17-0037-B6
 SHEET 02 OF 17 SHEETS