SUMMARY OF QUANTITIES

SEQ NO	ITEM NO	DESCRIPTION	UNIT	BASE BID ITEM NO	BASE BID TAXIWAY B/A ESTIMATED QUANTITY	BASE BID RECORD QUANTITY	ADDITIVE ALTERNATE NO 1 ITEM NO	ADDITIVE ALTERNATE NO 1 TAXIWAY A ESTIMATED QUANTITY	ADDITIVE ALTERNATE NO 1 RECORD QUANTITY	ADDITIVE ALTERNATE NO. 2 RUNWAY 1/19 REHABILITATION (AT) QUANTITY (LO)	QUANTITY (LO)	TOTAL COST
1	AR108108	1/C #8 5 KV UG CABLE	LF	AR108108	5,630.00		AS108108	1,110.00				
2	AR108158	1/C #8 5 KV UG CABLE IN UD	LF	AR108158	16,000.00		AS108158	1,330.00				
3	AR109210	VAULT MODIFICATIONS	LS	AR109210	1.00							
4	AR110212	2" STEEL DUCT, DIRECT BURY	LF	AR110212	5,725.00		AS110212	1,180.00				
5	AR110504	4-WAY CONCRETE ENCASED DUCT	LF	AR110504	310.00							
6	AR110550	SPLIT DUCT	LF				AS110550	280.00				
7	AR110552	EXTEND 2-WAY DUCT	LF	AR110552	110.00							
8	AR110900	REMOVE DUCT	LF	AR110900	415.00							
9	AR110906	REMOVE ELECTRICAL HANDHOLE	EACH	AR110906	1.00							
10	AR125415	MITL-BASE MOUNTED	EACH	AR125415	97.00		AS125415	8.00				
11	AR125442	TAXI GUIDANCE SIGN, 2 CHARACTER	EACH	AR125442	2.00		AS125442	2.00				
12	AR125443	TAXI GUIDANCE SIGN, 3 CHARACTER	EACH	AR125443	2.00							
13	AR125444	TAXI GUIDANCE SIGN, 4 CHARACTER	EACH	AR125444	2.00							
14	AR125445	TAXI GUIDANCE SIGN, 5 CHARACTER	EACH	AR125445	3.00		AS125445	1.00				
15	AR125446	TAXI GUIDANCE SIGN, 6 CHARACTER	EACH	AR125446	1.00							
16	AR125461	TAXI GUIDANCE SIGN, SPECIAL	EACH	AR125461	1.00							
17	AR125565	SPLICE CAN	EACH	AR125565	1.00							
18	AR125902	REMOVE BASE MOUNTED LIGHT	EACH	AR125902	88.00		AS125902	10.00				
19	AR125904	REMOVE TAXI GUIDANCE SIGN	EACH	AR125904	12.00		AS125904	3.00				
20	AR125906	REMOVE SPLICE CAN	EACH	AR125906	1.00							
21	AR125922	REPLACE BASE MOUNTED LIGHT	EACH				AS125922	4.00				
22	AR125942	ADJUST BASE MOUNTED LIGHT	EACH	AR125942	5.00							
23	AR150510	ENGINEER'S FIELD OFFICE	LS	AR150510	1.00							
24	AR150515	FIELD LABORATORY	LS	AR150515	1.00							
25	AR150520	MOBILIZATION	LS	AR150520	1.00							
26	AR150540	HAUL ROUTE	LS	AR150540	1.00							
27	AR152410	UNCLASSIFIED EXCAVATION	CY	AR152410	11,970.00		AS152410	1,950.00				
28	AR152540	SOIL STABILIZATION FABRIC	SY	AR152540	23,160.00		AS152540	3,950.00				
29	AR156510	SILT FENCE	LF	AR156510	520.00							
30	AR156512	BALES	EACH	AR156512	104.00							
31	AR208515	POROUS GRANULAR EMBANKMENT	CY	AR208515	500.00		AS208515	200.00				
32	AR209608	CRUSHED AGG. BASE COURSE - 8"	SY	AR209608	18,510.00		AS209608	5,600.00				
33	AR209611	CRUSHED AGG. BASE COURSE - 11"	SY	AR209611	15,130.00							
34	AR401610	BITUMINOUS SURFACE COURSE	TON	AR401610	8,650.00		AS401610	1,000.00		AT401610	2,780.00	
35	AR401630	BITUMINOUS SURFACE TEST SECTION	EACH	AR401630	1.00							
36	AR401640	BITUMINOUS PAVEMENT GROOVING	SY							AT401640	12,140.00	
37	AR401650	BITUMINOUS PAVEMENT MILLING	SY	AR401650	41,170.00		AS401650	5,005.00		AT401650	12,140.00	
38	AR401655	BUTT JOINT CONSTRUCTION	SY	AR401655	950.00							
39	AR401910	REMOVE & REPLACE BIT. PAVEMENT	SY	AR401910	125.00							
40	AR501515	15" PCC PAVEMENT	SY	AR501515	17,500.00							
41	AR501518	18" PCC PAVEMENT	SY	AR501518	9,130.00		AS501518	2,000.00				
42	AR501530	PCC TEST BATCH	EACH	AR501530	1.00							
43	AR602510	BITUMINOUS PRIME COAT	GAL	AR602510	4,935.00		AS602510	1,000.00				
44	AR603510	BITUMINOUS TACK COAT	GAL	AR603510	3,230.00		AS603510	770.00		AT603510	3,680.00	
45	AR620520	PAVEMENT MARKING - WATERBORNE	SF	AR620520	18,800.00		AS620520	4,100.00				
46	AR620525	PAVEMENT MARKING - BLACK BORDER	SF	AR620525	18,225.00		AS620525	3,900.00				
47	AR701004	4" PVC STORM SEWER	LF	AR701004	440.00							
48	AR701512	12" RCP, CLASS IV	LF	AR701512	185.00							
49	AR705524	4" PERFORATED UNDERDRAIN W/ SOCK	LF	AR705524	2,275.00		AS705524	320.00				
50	AR751412	INLET - TYPE B	EACH	AR751412	1.00							
51	AR800816	L-804 RGL ELEVATED, BASE MOUNTED	EACH				AS800816	2.00				
52	AR800818	REFLECTIVE CRACK CONTROL - ISAC	LF							AT800818	7,280.00	
53	AR800860	ADJUST PAVEMENT SENSOR	EACH	AR800860	1.00							
54	AR800868	SOIL GUARD	SY	AR800868	38,720.00		AS800868	4,840.00				
55	AR901510	SEEDING	ACRE	AR901510	8.00		AS901510	1.00				
56	AR905520	TOPSOILING (FROM OFF SITE)	CY	AR905520	3,425.00							

SUMMARY OF QUANTITIES
(QTY1)

RO017
5A

CMT
CRAWFORD, MURPHY & TILLY, INC.
CONSULTING ENGINEERS
Copyright CMT, Inc.

Chicago Rockford International Airport

FLYRFD.COM

ROCKFORD, ILLINOIS

GREATER ROCKFORD AIRPORT AUTHOIRTY

3-17-0088-XX
RFD-3909

REHAB. TWY B SOUTH PHASE 2

Revisions

Date	Description

0 — 1
THIS BAR IS EQUAL TO 1" AT FULL SCALE (17 X 11).

DESIGN BY:	CMT-ARR
DRAWN BY:	CMT-ARR
CHECKED BY:	CMT-ARR
APPROVED BY:	CMT-RFD
DATE:	5/8/2009
JOB No:	09258-04-00

SUMMARY OF QUANTITIES (QTY1)

2

XREF DWG: tbcint.dwg
IMAGE FILES: 101-rfd_logo.jpg
101-rfd_logo.jpg
UPDATE BY: Jeff Plopp
LAYOUT: 2-QTY1
DATE: Thursday, May 21, 2009 2:35:10 PM
FILE: V:\Work\Rockford\09258904 Rehab Twy B South Ph2\Draw\Sheets\02-QTY1.dwg