

TA002

DATE	REVISION	BY

SUMMARY OF QUANTITIES

ITEM NO.	DESCRIPTION	UNIT	TOTAL QUANTITIES	AS BUILT QUANTITIES
AR150510	ENGINEER'S FIELD OFFICE	L.S.	1	
AR150530	TRAFFIC MAINTENANCE	L.S.	1	
AR150540	HAUL ROUTE	L.S.	1	
AR152480	SHOULDER ADJUSTMENT	S.Y.	3,998	
AR201661	CLEAN & SEAL BITUMINOUS CRACKS	L.F.	5,000	
AR401650	BITUMINOUS PAVEMENT MILLING	S.Y.	36,295	
AR401910	REMOVE & REPLACE BIT. PAVEMENT	S.Y.	1,037	
AR402610	POROUS FRICTION COURSE	TON	3,130	
AR603510	BITUMINOUS TACK COAT	GAL.	12,703	
AR620520	PAVEMENT MARKING-WATERBORNE	S.F.	35,259	
AR620525	PAVEMENT MARKING-BLACK BORDER	S.F.	214	

INDEX TO SHEETS

SHEET NO.	DESCRIPTION
1	COVER SHEET
2	SUMMARY OF QUANTITIES AND INDEX TO SHEETS
3	PROPOSED SAFETY PLAN
4	PROPOSED PAVEMENT PREPARATION PLAN STA. 262+00 TO STA. 276+00
5	PROPOSED PAVEMENT PREPARATION PLAN STA. 276+00 TO STA. 290+00
6	PROPOSED PAVEMENT PREPARATION PLAN STA. 290+00 TO STA. 302+00
7	PROPOSED CONSTRUCTION PLAN STA. 262+00 TO STA. 276+00
8	PROPOSED CONSTRUCTION PLAN STA. 276+00 TO STA. 290+00
9	PROPOSED CONSTRUCTION PLAN STA. 290+00 TO STA. 302+00
10	PROPOSED TYPICAL SECTIONS
11	PROPOSED MARKING PLAN STA. 262+00 TO STA. 276+00
12	PROPOSED MARKING PLAN STA. 276+00 TO STA. 290+00
13	PROPOSED MARKING PLAN STA. 290+00 TO STA. 302+00

**TAYLORVILLE MUNICIPAL AIRPORT
 TAYLORVILLE, ILLINOIS**

IL. PROJ.: TAZ-3890 A.I.P. PROJ.: 3-17-0100-B11

Hanson Project No. 08A0189D_0800	
Revision	R-002ELP.DWG
Scale	NOT TO SCALE
Date	03/10/09
LAYOUT	RAW 03/10/09
DRAWN	BAK 03/10/09
REVIEWED	RAW 04/02/09



Hanson Professional Services Inc.
 1525 South Sixth Street
 Springfield, Illinois 62703-2886
 Offices Nationwide

**REHABILITATE RUNWAY
 18-36 AND TAXIWAY "A"**

**SUMMARY OF QUANTITIES
 AND
 INDEX TO SHEETS**