



Illinois Department of Transportation

2300 South Dirksen Parkway / Springfield, Illinois / 62764

May 29, 2020

SUBJECT: FAP Route 836 (IL 49)
Project STP-HSIP-1EWY(408)
Section (116,117)RS-5, D5 HSIP 2020-1
Douglas and Edgar Counties
Contract No. 70D74
Item No. 57, June 12, 2020 Letting
Addendum A

NOTICE TO PROSPECTIVE BIDDERS:

Attached is an addendum to the plans or proposal. This addendum involves revised and/or added material.

1. Revised page ii of the Table of Contents to the Special Provisions.
2. Added page 185 to the Special Provisions.
3. Revised sheets 39, 89, and 92 of the Plans.

Prime contractors must utilize the enclosed material when preparing their bid and must include any changes to the Schedule of Prices in their bid.

Very truly yours,

A handwritten signature in black ink, appearing to read "Jack A. Elston".

Jack A. Elston, P.E.
Bureau Chief, Design and Environment

DISPOSAL FEES (BDE)51

EMULSIFIED ASPHALTS (BDE)52

ENGINEER’S FIELD OFFICE AND LABORATORY (BDE)55

EQUIPMENT PARKING AND STORAGE (BDE)58

FUEL COST ADJUSTMENT (BDE)58

GROOVING FOR RECESSED PAVEMENT MARKINGS (BDE).....60

HOT-MIX ASPHALT – BINDER AND SURFACE COURSE (BDE)62

HOT-MIX ASPHALT – LONGITUDINAL JOINT SEALANT (BDE).....69

HOT-MIX ASPHALT – MIXTURE DESIGN VERIFICATION AND PRODUCTION (MODIFIED FOR I-FIT DATA COLLECTION) (BDE).....73

HOT MIX ASPHALT - PAY FOR PERFORMANCE USING PERCENT WITHIN LIMITS - JOBSITE SAMPLING (BDE).....76

MOBILIZATION (BDE).....81

PAVEMENT MARKING REMOVAL (BDE).....81

PORTLAND CEMENT CONCRETE (BDE)82

RAILROAD PROTECTIVE LIABILITY INSURANCE (BDE).....83

RECLAIMED ASPHALT PAVEMENT AND RECLAIMED ASPHALT SHINGLES (BDE).....84

SILT FENCE, INLET FILTERS, GROUND STABILIZATION AND RIPRAP FILTER FABRIC (BDE).....92

STEEL COST ADJUSTMENT (BDE)98

STEEL PLATE BEAM GUARDRAIL MANUFACTURING (BDE)100

SUBCONTRACTOR AND DBE PAYMENT REPORTING (BDE).....101

SUBCONTRACTOR MOBILIZATION PAYMENTS (BDE).....101

TEMPORARY PAVEMENT MARKING (BDE).....102

TRAFFIC BARRIER TERMINAL, TYPE 1 SPECIAL (BDE).....104

TRAFFIC CONTROL DEVICES - CONES (BDE).....105

WARM MIX ASPHALT (BDE)105

WEEKLY DBE TRUCKING REPORTS (BDE).....107

WORK ZONE TRAFFIC CONTROL DEVICES (BDE).....107

WORKING DAYS (BDE).....109

SWPPP.....110

TRAFFIC BARRIER TERMINAL, TYPE 6A (SPECIAL)185

TRAFFIC BARRIER TERMINAL, TYPE 6A (SPECIAL)

Description This work shall consist of the furnishing and erecting of a Traffic Barrier Terminal, Type 6A (Special), including the field adjustments of guardrail lengths, drilling of mounting holes, re-galvanizing of all exposed metal surfaces and any other items needed to complete the work. This work shall conform to the application portion of Section 631 of the Standard Specifications.

Traffic Barrier Terminal Type 6A (Special) shall be as shown on Standard 631032-09 and the detail seen in the plans, except the rail on the south-east quadrant of S.N. 023-2010 shall be bent between posts 1 to 11 with a radius of 16 FT. The Contractor shall verify all dimensions and modifications in the field prior to ordering materials.

The terminal shall be installed according to the manufacturer's specifications and shall include all necessary transitions between the terminal and the items to which it is attached.

Method of Measurement The method of measurement shall be in accordance with Article 631.12 of the Standard Specifications.

Basis of Payment The basis of payment shall be the contract unit price each for TRAFFIC BARRIER TERMINAL TYPE 6A (SPECIAL). All bolts, nuts, block-outs, galvanizing, or any other items needed to complete this work shall be included, and no other compensation will be allowed.

Added May 29, 2020