F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
55	*	WILL	608	8
STA.		TO STA.		
FED. ROAD DIST. NO. 1	ILLINOIS	FED. AID PROJECT		

* (26, 26HB-1&114) R-2 CONTRACT NO. 60363

SUMMARY OF QUANTITIES

CODE NO.	ITEM	UNIT	URBAN TOTAL QUANTITY	WILL COUNTY: ROADWAY IL-59 90% FED 10% STATE	ROADWAY I-55 90% FED 10% STATE	ROADWAY NB RAMP 90% FED 10% STATE	ROADWAY SB RAMP 90% FED 10% STATE	ROADWAY SEIL RD 90% FED 10% STATE	ROADWAY FRONTG RD 90% FED 10% STATE	BRIDGE IL59 NB EXIT RAMP OVER I-55	BRIDGE IL59 OVER DUPAGE RIVER	SIGNING	EXPRESSWAY LIGHTING 100% STATE	VILLAGE LIGHTING 100% VOS	TRAFFIC SIGNALS 90% FED 6.7% STATE 3.3% VOS	CITY OF JOLIET 100% JOLIET	90% FED/10% STATE: RETAINING WALLS CULVERTS	VILLAGE OF SHOREWOOD 100% VOS
				CONSTRUCTION TYPE CODE														
				J000-2A	I000-2A	J000-2A	J000-2A	I000-2A	I000-2A	X271-2A	X081-2A	Y002-2A	Y030-1E	Y030-1E	Y031-1F	J000-2A	Y007	J000-2A
5421A012	PIPE CULVERTS, CLASS A, TYPE 1 12" (TEMPORARY)	FOOT	80	80														
5421A015	PIPE CULVERTS, CLASS A, TYPE 1 15" (TEMPORARY)	FOOT	40					40										
5421A018	PIPE CULVERTS, CLASS A, TYPE 1 18" (TEMPORARY)	FOOT	20	20														
5421A036	PIPE CULVERTS, CLASS A, TYPE 1 36" (TEMPORARY)	FOOT	177					177										
542A0215	PIPE CULVERTS, CLASS A, TYPE 1 10"	FOOT	52					52										
542A0217	PIPE CULVERTS, CLASS A, TYPE 1 12"	FOOT	183	57				45	81									
542A0220	PIPE CULVERTS, CLASS A, TYPE 1 15"	FOOT	53					53										
542A0235	PIPE CULVERTS, CLASS A, TYPE 1 30"	FOOT	50			50												
542A1057	PIPE CULVERTS, CLASS A, TYPE 2 12"	FOOT	260	260														
542A1060	PIPE CULVERTS, CLASS A, TYPE 2 15"	FOOT	60	60														
542A1066	PIPE CULVERTS, CLASS A, TYPE 2 21"	FOOT	42				42											
542A1069	PIPE CULVERTS, CLASS A, TYPE 2 24"	FOOT	124	51			73											
542A5473	PIPE CULVERTS, CLASS A, TYPE 1 EQUIVALENT ROUND-SIZE 18"	FOOT	106				69	37										
542A5479	PIPE CULVERTS, CLASS A, TYPE 1 EQUIVALENT ROUND-SIZE 24"	FOOT	444					444										
542A5491	PIPE CULVERTS, CLASS A, TYPE 1 EQUIVALENT ROUND-SIZE 36"	FOOT	38						38									
55034300	STORM SEWERS, TYPE 1, REINFORCED CONCRETE ELLIPTICAL PIPE, SPAN 30, RISE 19	FOOT	113					113										
55034400	STORM SEWERS, TYPE 1, REINFORCED CONCRETE ELLIPTICAL PIPE SPAN 34, RISE 22	FOOT	331	331														
55034600	STORM SEWERS, TYPE 1, REINFORCED CONCRETE ELLIPTICAL PIPE, SPAN 45, RISE 29	FOOT	724					724										
55035400	STORM SEWERS, TYPE 2, REINFORCED CONCRETE ELLIPTICAL PIPE, SPAN 30, RISE 19	FOOT	47				47											
550A0050	STORM SEWERS, CLASS A, TYPE 1 12"	FOOT	939	349			14	576										
550A0070	STORM SEWERS, CLASS A, TYPE 1 15"	FOOT	271	9				262										
550A0200	STORM SEWERS, CLASS A, TYPE 1 54"	FOOT	208	208														
550A0210	STORM SEWERS, CLASS A, TYPE 1 60"	FOOT	427	427														
550A0230	STORM SEWERS, CLASS A, TYPE 1 72"	FOOT	645	645														
550A0260	STORM SEWERS, CLASS A, TYPE 1 90"	FOOT	146	146														
550A0340	STORM SEWERS, CLASS A, TYPE 2 12"	FOOT	3257	3081		96		77										
550A0360	STORM SEWERS, CLASS A, TYPE 2 15"	FOOT	1729	1278		416	35											
550A0380	STORM SEWERS, CLASS A, TYPE 2 18"	FOOT	368	268		100												
550A0410	STORM SEWERS, CLASS A, TYPE 2 24"	FOOT	5	5														
550A0420	STORM SEWERS, CLASS A, TYPE 2 27"	FOOT	326	326														
550A0520	STORM SEWERS, CLASS A, TYPE 2 72"	FOOT	209	209														

* DENOTES SPECIALTY ITEMS

REVISIONS	
NAME	DATE

Rev.

ILLINOIS DEPARTMENT OF TRANSPORTATION
FAI 55 AT FAP 338 ILLINOIS ROUTE 59
SECTION: (26, 26HB-1&114) R-2

SUMMARY OF QUANTITIES 5

SCALE:
DATE: 03/14/08
DRAWN BY: JB
CHECKED BY: ACL

TENG

TENG & ASSOCIATES, INC.
ENGINEERS•ARCHITECTS•PLANNERS
205 N. MICHIGAN AVE. CHICAGO, IL 60601
TELEPHONE: 312-616-0000

..\SUDOORS5.DGN,..\SUDOORS3.DGN,..\TTBUDRWN.DGN
3-24-2008,10:37:48 T:\DOCUMENT\93279DN\CIVIL\DGN\SUDOOSOA.DGN
BONDHUJO
1 2 3 4 5 6 7 8 9 10 11 12 13 14 15 16 17 18 19 20 21 22 23 24 25 26 27 28 29 30 31 32 33 34 35 36 37 38 39 40 41 42 43 44 45 46 47 48 49 50 51 52 53 54 55 56 57 58 59 60 61 62 63