

LOCATION STATION TO STATION	TOPSOIL EXCAVATION (CU YD)			EARTH EXCAVATION (ALL SUITABLE) (CU YD)			EARTH EXCAVATION TO BE USED IN EMBANKMENT (15% SHRINKAGE) (CU YD)			EMBANKMENT (CU YD)			EARTHWORK BALANCE (CU YD)			REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL (CU YD)								
	PRE-ST	STA 1	STA 2	STA 3	PRE-ST	STA 1	STA 2	STA 3	PRE-ST	STA 1	STA 2	STA 3	PRE-ST	STA 1	STA 2	STA 3	PRE-ST	STA 1	STA 2	STA 3				
SEIL ROAD																								
4004+00.00 4004+50.00	0.0	0.0	76.8	0.0	0.0	0.0	57.4	0.0	0.0	0.0	48.7	0.0	0.0	0.0	63.4	0.0	0.0	0.0	-14.6	0.0	0.0	0.0	59.1	0.0
4004+50.00 4005+00.00	0.0	0.0	78.8	0.0	0.0	0.0	50.7	0.0	0.0	0.0	43.1	0.0	0.0	0.0	91.2	0.0	0.0	0.0	-48.1	0.0	0.0	0.0	60.7	0.0
4005+00.00 4005+50.00	0.0	0.0	91.3	0.0	0.0	0.0	41.7	0.0	0.0	0.0	35.5	0.0	0.0	0.0	100.3	0.0	0.0	0.0	-64.9	0.0	0.0	0.0	70.5	0.0
4005+50.00 4006+00.00	0.0	0.0	92.3	0.0	0.0	0.0	27.7	0.0	0.0	0.0	23.6	0.0	0.0	0.0	117.9	0.0	0.0	0.0	-94.4	0.0	0.0	0.0	71.6	0.0
4006+00.00 4006+50.00	0.0	0.0	89.7	0.0	0.0	0.0	14.1	0.0	0.0	0.0	12.0	0.0	0.0	0.0	137.9	0.0	0.0	0.0	-126.0	0.0	0.0	0.0	70.9	0.0
4006+50.00 4007+00.00	0.0	0.0	94.9	0.0	0.0	0.0	6.9	0.0	0.0	0.0	5.9	0.0	0.0	0.0	144.0	0.0	0.0	0.0	-138.2	0.0	0.0	0.0	74.8	0.0
4007+00.00 4007+50.00	17.0	0.0	99.6	0.0	0.0	0.0	3.4	0.0	0.0	0.0	2.9	0.0	16.7	0.0	164.3	0.0	-16.7	0.0	-161.4	0.0	12.5	0.0	79.1	0.0
4007+50.00 4008+00.00	45.7	0.0	128.9	0.0	9.0	0.0	1.0	0.0	7.6	0.0	0.9	0.0	38.9	0.0	220.5	0.0	-31.3	0.0	-219.6	0.0	34.4	0.0	111.1	0.0
4008+00.00 4008+50.00	60.6	0.0	134.7	0.0	32.3	0.0	8.1	0.0	27.5	0.0	6.9	0.0	45.3	0.0	213.6	0.0	-17.8	0.0	-206.7	0.0	47.4	0.0	113.5	0.0
4008+50.00 4009+00.00	66.2	0.0	98.9	22.2	56.0	0.0	12.2	5.1	47.6	0.0	10.4	4.4	44.5	0.0	129.1	62.3	3.1	0.0	-118.8	-57.9	53.8	0.0	78.3	15.2
4009+00.00 4009+50.00	70.7	0.0	82.3	22.2	65.9	0.0	12.9	15.8	56.0	0.0	11.0	13.5	46.8	0.0	77.9	76.9	9.3	0.0	-66.9	-63.5	59.5	0.0	68.4	13.0
4009+50.00 4010+00.00	74.5	0.0	71.9	0.0	33.2	0.0	21.3	20.8	28.3	0.0	18.1	17.7	108.4	0.0	67.5	34.1	-80.2	0.0	-49.4	-16.4	64.7	0.0	58.8	-4.4
4010+00.00 4010+50.00	74.2	0.0	30.4	0.0	0.0	0.0	44.0	17.6	0.0	0.0	37.4	15.0	137.1	0.0	30.8	41.9	-137.1	0.0	6.5	-27.0	66.7	0.0	23.8	-4.6
4010+50.00 4011+00.00	73.8	0.0	14.5	0.0	1.4	0.0	43.4	15.0	1.2	0.0	36.9	12.8	92.6	0.0	20.3	44.0	-91.4	0.0	16.6	-31.2	67.4	0.0	11.4	-11.8
4011+00.00 4011+50.00	73.7	0.0	35.2	0.0	1.4	0.0	21.2	12.1	1.2	0.0	18.0	10.3	78.2	0.0	52.1	42.2	-77.1	0.0	-34.1	-31.9	67.3	0.0	28.5	-18.4
4011+50.00 4012+00.00	70.2	0.0	75.3	0.0	0.0	0.0	12.2	9.5	0.0	0.0	10.4	8.1	96.5	0.0	100.8	39.1	-96.5	0.0	-90.4	-31.0	64.6	0.0	71.7	-17.4
4012+00.00 4012+50.00	69.8	0.0	107.7	0.0	0.0	0.0	8.0	5.0	0.0	0.0	6.8	4.3	82.5	0.0	99.7	47.8	-82.5	0.0	-93.0	-43.5	64.4	0.0	102.1	-11.6
4012+50.00 4013+00.00	74.1	0.0	105.0	0.0	1.3	0.0	6.9	8.3	1.1	0.0	5.8	7.0	66.0	0.0	71.9	51.1	-64.9	0.0	-66.0	-44.1	67.5	0.0	94.1	-9.9
4013+00.00 4013+50.00	78.9	0.0	101.4	0.0	4.1	0.0	4.1	19.3	3.5	0.0	3.4	16.4	95.1	0.0	111.2	58.7	-91.6	0.0	-107.8	-42.2	71.9	0.0	90.5	-14.7
4013+50.00 4014+00.00	90.9	0.0	103.2	6.4	11.2	0.0	3.2	21.3	9.5	0.0	2.7	18.1	104.8	0.0	184.9	73.8	-95.3	0.0	-182.2	-55.7	84.0	0.0	91.7	-11.5
4014+00.00 4014+50.00	50.5	46.9	53.8	6.4	8.4	0.0	33.7	30.3	7.2	0.0	28.6	25.8	50.1	273.1	114.8	53.3	-42.9	-273.1	-86.1	-27.5	46.8	46.9	42.7	-15.0
4014+50.00 4015+00.00	0.0	104.2	0.0	0.0	0.0	0.0	88.3	20.1	0.0	0.0	75.0	17.1	0.0	742.0	16.4	16.4	0.0	-742.0	58.6	0.6	0.0	104.2	-23.2	-11.4
4015+00.00 4015+50.00	0.0	136.3	0.0	0.0	0.0	0.9	56.3	0.0	0.0	0.8	47.9	0.0	0.0	1072.2	49.3	0.0	0.0	-1071.4	-1.5	0.0	0.0	133.3	-43.6	0.0
4015+50.00 4016+00.00	0.0	192.7	0.0	0.0	0.0	11.3	0.3	0.0	0.0	9.6	0.3	0.0	0.0	1695.4	65.8	0.0	0.0	-1685.8	-65.5	0.0	0.0	184.5	-57.5	0.0
4016+00.00 4016+50.00	0.0	244.1	0.0	0.0	0.0	27.5	0.3	0.0	0.0	23.4	0.3	0.0	0.0	2487.0	65.8	0.0	0.0	-2463.7	-65.5	0.0	0.0	232.6	-70.0	0.0
4016+50.00 4017+00.00	0.0	231.1	0.0	0.0	0.0	17.1	0.5	0.0	0.0	14.6	0.4	0.0	0.0	1394.9	65.8	0.0	0.0	-1380.3	-65.4	0.0	0.0	-1483.5	-72.3	0.0
4017+00.00 4017+50.00	0.0	221.9	0.0	0.0	0.0	0.8	0.0	0.0	0.0	0.7	0.0	0.0	0.0	120.1	0.0	0.0	0.0	-119.4	0.0	0.0	0.0	-3725.2	-66.5	0.0
4017+50.00 4018+00.00	0.0	121.2	0.0	0.0	0.0	0.5	0.0	0.0	0.0	0.4	0.0	0.0	0.0	87.2	0.0	0.0	0.0	-86.8	0.0	0.0	0.0	-2117.6	-32.1	0.0
4018+00.00 4018+50.00	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
4018+50.00 4019+00.00	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
4019+00.00 4019+50.00	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
4019+50.00 4020+00.00	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
4020+00.00 4020+50.00	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
4020+50.00 4021+00.00	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
4021+00.00 4021+50.00	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
4021+50.00 4022+00.00	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
4022+00.00 4022+50.00	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
4022+50.00 4023+00.00	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
4023+00.00 4023+50.00	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
4023+50.00 4024+00.00	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
4024+00.00 END	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
TOTALS	990.9	1,298.3	1,766.6	57.1	224.3	56.9	580.9	200.3	190.6	48.3	493.7	170.3	1,103.5	7,664.6	2,784.5	641.6	-912.9	-7,616.3	-2,290.7	-471.3	873.0	-6,624.8	1,108.1	-102.5

NOTES:

1. THE REMOVAL AND DISPOSAL OF UNSUITABLE MATERIALS INCLUDES THE VOLUME OF TOPSOIL REMOVED WHICH WILL NOT BE STOCKPILED OR PLACED ON SITE.
2. TOPSOIL REMOVAL SHALL BE PAID FOR AS EITHER TOPSOIL EXCAVATION AND PLACEMENT (21101505) OR REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL (20201200).
3. TOPSOIL EXCAVATION AND PLACEMENT SHALL INCLUDE EXCAVATION AND PLACEMENT AT A STOCKPILE (IF NECESSARY) AND SUBSEQUENT PLACEMENT AT THE PROPOSED LOCATION.

THE FOLLOWING AREAS SHALL HAVE AN ADDITIONAL 24" OF POROUS GRANULAR EMBANKMENT, SUBGRADE (PGES) PLACED ACROSS THE ENTIRE WIDTH OF THE FILL SECTION. THE PGES SHALL BE PLACED AT THE BOTTOM OF THE FILL SECTION.

NORTHBOUND RAMP  
8008+00 TO 8011+25

SOUTHBOUND RAMP  
7016+50 TO 7019+75  
7026+00 TO 7029+00

IL ROUTE 59 (12" ONLY)  
7499+00 TO 7501+00

TEMPORARY RUNAROUND  
1004+00 TO 1014+00

EAST FRONTAGE ROAD  
6508+00 TO 6514+00  
6516+50 TO 6521+50

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

### SCHEDULE OF QUANTITIES 1

SCALE: \_\_\_\_\_ DRAWN BY: JB  
DATE: 03/14/08 CHECKED BY: ACL

\S:\0002\JUDON\ATTBORR\ADON\SC000017.DGN  
 3-4-2008 15:28:51  
 T:\DOCUMENT\03279\ACIV\ADON\SC000017.DGN  
 1 2 3 4 5 6 7 8 9 10 11 12 13 14 15 16 17 18 19 20 21 22 23 24 25 26 27 28 29 30 31 32 33 34 35 36 37 38 39 40 41 42 43 44 45 46 47 48 49 50 51 52 53 54 55 56 57 58 59 60 61 62 63