F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
55	*	WILL	608	33
STA.		TO STA.		
FED. ROAD DIST. NO. 1	ILLINOIS	FED. AID PROJECT		

* (26, 26HB-1&114) R-2 CONTRACT NO. 60363

LOCATION STATION TO STATION		TOPSOIL EXCAVATION (CU YD)				EARTH EXCAVATION (ALL SUITABLE) (CU YD)				EARTH EXCAVATION TO BE USED IN EMBANKMENT (15% SHRINKAGE) (CU YD)				EMBANKMENT (CU YD)				EARTHWORK BALANCE (CU YD)				REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL (CU YD)			
TEMPORARY RUNAROUND		PRE-ST	STA 1	STA 2	STA 3	PRE-ST	STA 1	STA 2	STA 3	PRE-ST	STA 1	STA 2	STA 3	PRE-ST	STA 1	STA 2	STA 3	PRE-ST	STA 1	STA 2	STA 3	PRE-ST	STA 1	STA 2	STA 3
1004+00.00	1005+00.00	324.2	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	640.8	0.0	0.0	0.0	-640.8	0.0	0.0	0.0	324.2	0.0	0.0	0.0
1005+00.00	1006+00.00	369.1	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	1001.2	0.0	0.0	0.0	-1001.2	0.0	0.0	0.0	369.1	0.0	0.0	0.0
1006+00.00	1007+00.00	395.3	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	1259.6	0.0	0.0	0.0	-1259.6	0.0	0.0	0.0	395.3	0.0	0.0	0.0
1007+00.00	1008+00.00	424.5	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	1485.4	0.0	0.0	0.0	-1485.4	0.0	0.0	0.0	424.5	0.0	0.0	0.0
1008+00.00	1009+00.00	427.6	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	1574.9	0.0	0.0	0.0	-1574.9	0.0	0.0	0.0	427.6	0.0	0.0	0.0
1009+00.00	1010+00.00	211.5	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	805.6	0.0	0.0	0.0	-805.6	0.0	0.0	0.0	211.5	0.0	0.0	0.0
1010+00.00	1011+00.00	120.9	0.0	0.0	0.0	2.9	0.0	0.0	0.0	2.5	0.0	0.0	0.0	190.5	0.0	0.0	0.0	-188.0	0.0	0.0	0.0	120.9	0.0	0.0	0.0
1011+00.00	1012+00.00	126.3	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	180.6	0.0	0.0	0.0	-180.6	0.0	0.0	0.0	126.3	0.0	0.0	0.0
1012+00.00	1013+00.00	158.0	0.0	0.0	0.0	2.9	0.0	0.0	0.0	2.5	0.0	0.0	0.0	148.4	0.0	0.0	0.0	-145.9	0.0	0.0	0.0	158.0	0.0	0.0	0.0
1013+00.00	1014+00.00	235.4	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	416.1	0.0	0.0	0.0	-416.1	0.0	0.0	0.0	235.4	0.0	0.0	0.0
1014+00.00	1015+00.00	103.3	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	75.7	0.0	0.0	0.0	-75.7	0.0	0.0	0.0	103.3	0.0	0.0	0.0
1015+00.00	1016+00.00	109.2	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	235.6	0.0	0.0	0.0	-235.6	0.0	0.0	0.0	109.2	0.0	0.0	0.0
1016+00.00	END	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
	TOTALS	3,005.4	0.0	0.0	0.0	5.9	0.0	0.0	0.0	5.0	0.0	0.0	0.0	8,014.2	0.0	0.0	0.0	-8,009.2	0.0	0.0	0.0	3,005.4	0.0	0.0	0.0

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
FAI 55 AT FAP 338 ILLINOIS ROUTE 59
SECTION: (26, 26HB-1&114) R-2

SCHEDULE OF QUANTITIES 8

SCALE:
DATE: 03/14/08
DRAWN BY: JB
CHECKED BY: ACL

TENG

TENG & ASSOCIATES, INC.
ENGINEERS&ARCHITECTS&PLANNERS
300 N. MICHIGAN AVE. CHICAGO, IL. 60601
TELEPHONE: 1(312)-616-0000

..\SC0007U0.DGN, ..\TTBORN\NO.DGN, ..\SC0002_NO.DGN, ..\SC0002_NO.DGN, ..\SC0002_NO.DGN, ..\SC0002_NO.DGN, ..\SC0002_V.DGN
3-14-2008, 1:28:48 F:\DOCUMENT\93279\CIVIL\DGN\SC0007U0.DGN
BONDHWJO