F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
55	*	WILL	608	35
STA.		TO STA.		
FED. ROAD DIST. NO. 1	ILLINOIS	FED. AID PROJECT		

* (26, 26HB-1&114) R-2 CONTRACT NO. 60363

LOCATION STATION TO STATION		TOPSOIL EXCAVATION (CU YD)				EARTH EXCAVATION (ALL SUITABLE) (CU YD)				EARTH EXCAVATION TO BE USED IN EMBANKMENT (15% SHRINKAGE) (CU YD)				EMBANKMENT (CU YD)				EARTHWORK BALANCE (CU YD)				REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL (CU YD)			
EX. NORTHBOUND I-55 RAMP		STA 1	STA 2	STA 3	STA 4	STA 1	STA 2	STA 3	STA 4	STA 1	STA 2	STA 3	STA 4	STA 1	STA 2	STA 3	STA 4	STA 1	STA 2	STA 3	STA 4	STA 1	STA 2	STA 3	STA 4
135+00.00	136+00.00	0.0	0.0	0.0	0.0	0.0	0.0	0.0	137.0	0.0	0.0	0.0	116.4	0.0	0.0	0.0	0.0	0.0	0.0	0.0	116.4	0.0	0.0	0.0	0.0
136+00.00	137+00.00	0.0	0.0	0.0	0.0	0.0	0.0	0.0	137.7	0.0	0.0	0.0	117.1	0.0	0.0	0.0	0.1	0.0	0.0	0.0	117.0	0.0	0.0	0.0	0.0
137+00.00	138+00.00	0.0	0.0	0.0	0.0	0.0	0.0	0.0	141.4	0.0	0.0	0.0	120.2	0.0	0.0	0.0	0.1	0.0	0.0	0.0	120.1	0.0	0.0	0.0	0.0
138+00.00	139+00.00	0.0	0.0	0.0	0.0	0.0	0.0	0.0	151.4	0.0	0.0	0.0	128.7	0.0	0.0	0.0	0.0	0.0	0.0	0.0	128.7	0.0	0.0	0.0	0.0
139+00.00	140+00.00	0.0	0.0	0.0	0.0	0.0	0.0	0.0	74.0	0.0	0.0	0.0	62.9	0.0	0.0	0.0	0.0	0.0	0.0	0.0	62.9	0.0	0.0	0.0	0.0
140+00.00	141+00.00	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0	0.0
141+00.00	142+00.00	0.0	0.0	0.0	0.0	0.0	0.0	0.0	116.8	0.0	0.0	0.0	99.2	0.0	0.0	0.0	0.0	0.0	0.0	0.0	99.2	0.0	0.0	0.0	0.0
142+00.00	143+00.00	0.0	0.0	0.0	0.0	0.0	0.0	0.0	103.8	0.0	0.0	0.0	88.2	0.0	0.0	0.0	0.0	0.0	0.0	0.0	88.2	0.0	0.0	0.0	0.0
143+00.00	144+00.00	0.0	0.0	0.0	0.0	0.0	0.0	0.0	201.9	0.0	0.0	0.0	171.6	0.0	0.0	0.0	0.0	0.0	0.0	0.0	171.6	0.0	0.0	0.0	0.0
144+00.00	145+00.00	0.0	0.0	0.0	0.0	0.0	0.0	0.0	200.7	0.0	0.0	0.0	170.6	0.0	0.0	0.0	0.0	0.0	0.0	0.0	170.6	0.0	0.0	0.0	0.0
145+00.00	146+00.00	0.0	0.0	0.0	0.0	0.0	0.0	0.0	186.6	0.0	0.0	0.0	158.6	0.0	0.0	0.0	0.0	0.0	0.0	0.0	158.6	0.0	0.0	0.0	0.0
146+00.00	147+00.00	0.0	0.0	0.0	0.0	0.0	0.0	0.0	153.4	0.0	0.0	0.0	130.4	0.0	0.0	0.0	96.1	0.0	0.0	0.0	34.3	0.0	0.0	0.0	0.0
147+00.00	148+00.00	0.0	4.9	0.0	0.0	0.0	17.5	0.0	180.4	0.0	14.9	0.0	153.3	0.0	4.3	0.0	0.0	0.0	10.6	0.0	153.3	0.0	4.9	0.0	0.0
148+00.00	149+00.00	0.0	0.0	0.0	0.0	0.0	0.0	0.0	56.6	0.0	0.0	0.0	48.1	0.0	0.0	0.0	96.1	0.0	0.0	0.0	-48.0	0.0	0.0	0.0	0.0
149+00.00	150+00.00	0.0	4.9	0.0	0.0	0.0	17.5	0.0	78.9	0.0	14.9	0.0	67.0	0.0	4.3	0.0	0.0	0.0	10.6	0.0	67.0	0.0	4.9	0.0	0.0
150+00.00	151+00.00	0.0	46.7	0.0	0.0	0.0	15.4	0.0	0.0	0.0	13.1	0.0	0.0	0.0	73.3	0.0	0.0	0.0	-60.2	0.0	0.0	0.0	46.7	0.0	0.0
151+00.00	152+00.00	0.0	46.6	0.0	0.0	0.0	12.3	0.0	0.0	0.0	10.5	0.0	0.0	0.0	59.6	0.0	0.0	0.0	-49.2	0.0	0.0	0.0	46.6	0.0	0.0
152+00.00	END	0.0	44.8	0.0	0.0	0.0	4.4	0.0	0.0	0.0	3.7	0.0	0.0	0.0	44.9	0.0	0.0	0.0	-41.2	0.0	0.0	0.0	44.8	0.0	0.0
	TOTALS	0.0	147.9	0.0	0.0	0.0	67.2	0.0	1,920.6	0.0	57.1	0.0	1,632.5	0.0	186.5	0.0	192.4	0.0	-129.4	0.0	1,440.1	0.0	147.9	0.0	0.0

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
FAI 55 AT FAP 338 ILLINOIS ROUTE 59
SECTION: (26, 26HB-1&114) R-2

SCHEDULE OF QUANTITIES 10

SCALE:
DRAWN BY: JB
DATE: 03/14/08
CHECKED BY: ACL

TENG

TENG & ASSOCIATES, INC.
ENGINEERS/ARCHITECTS/PLANNERS
300 N. MICHIGAN AVE. CHICAGO, IL 60601
TELEPHONE: 312/616-0300

..\SC00GR4.DGN,..\TTBGGRN.DGN,..\SC00GZ.V.DGN
3-14-2008,1:28:54 T1:\DOCUMENTS\SC2TP\SC2TP04\PLAN\SC00QTY7.DGN
1 2 3 4 5 6 7 8 9 10 11 12 13 14 15 16 17 18 19 20 21 22 23 24 25 26 27 28 29 30 31 32 33 34 35 36 37 38 39 40 41 42 43 44 45 46 47 48 49 50 51 52 53 54 55 56 57 58 59 60 61 62 63
BONDHUD